



NOTE: INLET RIM ELEVATIONS ARE AT  
EDGE OF PAVEMENT.  
STATIONS AND OFFSETS ARE AT  
BACK OF CURB.

STRUCTURE NO.	1	2	5	6	7	8	9	10
STA	70+97.19	71+04.40	70+67.24	70+67.26	10+62.54	10+69.00	10+41.17	10+38.20
OFFSET	40.65' RT	40.75' RT	32.94' LT	24.43' LT	32.30' LT	17.88' LT	41.23' RT	41.20' RT
STRUCTURE TYPE	I-A	EX I-A	I-A	EX I-A	I-A	EX MH	I-A	EX CB
F&G TYPE	3	--	4	--	4	--	4	--
RIM ELEVATION	880.68	880.71	880.89	880.91	881.10	878.45	880.50	880.52
EAST INVERT	--	--	--	--	--	--	--	--
WEST INVERT	--	--	878.56	878.49	877.71	--	--	--
NORTH INVERT	--	--	--	--	--	877.56	877.64	877.62
SOUTH INVERT	877.47	877.41	--	--	--	--	--	--
PIPE NUMBER	1	--	3	--	4	--	5	--
SIZE	12"	--	12"	--	12"	--	12"	--
LENGTH	6'	--	7'	--	15'	--	2'	--
CLASS	A (RG)	--	A	--	A (RG)	--	A	--
TYPE	1	--	1	--	1	--	1	--
% SLOPE	1%	--	1%	--	1%	--	1%	--
TRENCH BACKFILL	0.7	--	0.2	--	0.2	--	0.2	--

RG = RUBBER GASKET

FILE NAME =  
0366983-SHT-DRAIN-68-13.DGN

USER NAME = ---  
PLOT SCALE = 1"=20'  
PLOT DATE = 01/11

DESIGNED - DJD  
DRAWN - NV  
CHECKED - DJD  
DATE - 01/11

REVISED - ---  
REVISED - ---  
REVISED - ---  
REVISED - ---

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DRAINAGE AND UTILITY PLAN**

SCALE: 1"=20' SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(28)N, TS & I	DEKALB	120	29
CONTRACT NO. 66983				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				