

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/72	D6 PATCHING 2012	SANGAMON	10	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	CLASS A PATCHES					CLASS B PATCHES				CLASS A PATCHES			CLASS B PATCHES			SAW CUTS	TIE BARS	DOWEL BARS	PATCH REINF										
	LENGTH (FT)	WIDTH	SQ YD	PASS.	CENT.	DRIV.	WIDTH	SQ YD	12 IN	12 IN	12 IN	12 IN	12 IN	12 IN	13 IN					13 IN	13 IN	13 IN	16 IN	16 IN	16 IN	FOOT	EACH	EACH	SQ YD
									TY II	TY III	TY IV	TY II	TY III	TY IV	TY I					TY II	TY III	TY IV	TY II	TY III	TY IV				
NORTHBOUND I-55	PASS.	CENT.	DRIV.			PASS.	CENT.	DRIV.																					
STA 437+15			6.0	12.0	8.0										8.0							60.0			8.0				
STA 232+10			6.0	12.0	8.0										8.0							60.0			8.0				
STA 144+408			6.0	12.0	8.0										8.0							60.0			8.0				
STA 144+408	10.0			12.0	13.3										13.3							60.0			13.3				
STA 144+414			6.0	12.0	8.0										8.0							60.0			8.0				
STA 144+517			23.0	12.0	30.7												30.7					94.0	12		30.7				
STA 144+898			6.0	12.0	8.0										8.0							60.0			8.0				
STA 145+191			25.0	12.0	33.3												33.3					98.0	13		33.3				
STA 145+215			6.0	12.0	8.0										8.0							60.0			8.0				
STA 32+80								6.0	12.0	8.0									8.0			48.0			20				
STA 32+95								6.0	12.0	8.0									8.0			48.0			20				
STA 72+00							6.0		12.0	8.0									8.0			48.0			20				
STA 72+00						6.0			12.0	8.0									8.0			48.0			20				
STA 73+00							6.0		12.0	8.0									8.0			48.0			20				
STA 73+00						6.0			12.0	8.0									8.0			48.0			20				
STA 80+30								6.0	12.0	8.0									8.0			48.0			20				
STA 98+05								6.0	12.0	8.0									8.0			48.0			20				
STA 98+05						6.0			12.0	8.0									8.0			48.0			20				
STA 197+50								6.0	12.0	8.0									8.0			48.0			20				
STA 197+50						6.0			12.0	8.0									8.0			48.0			20				
STA 201+80								6.0	12.0	8.0									8.0			48.0			20				
STA 210+20								6.0	12.0	8.0									8.0			48.0			20				
STA 212+40						6.0			12.0	8.0									8.0			48.0			20				
STA 213+05								6.0	12.0	8.0									8.0			48.0			20				
STA 232+00								6.0	12.0	8.0									8.0			48.0			20				
STA 241+40								6.0	12.0	8.0									8.0			48.0			20				
EXIT RAMP - I-55																													
/I-72(CLEARLAKE)																													
STA 21+00								6.0	8.0	5.3												36.0			20				
STA 21+75								6.0	8.0	5.3												36.0			20				
STA 22+50								6.0	8.0	5.3												36.0			20				
STA 22+80								6.0	8.0	5.3												36.0			20				
STA 23+25								6.0	8.0	5.3												36.0			20				
STA 26+00								6.0	16.0	10.7												60.0			26				
STA 27+00								23.0	16.0	40.9												94.0			40.9				
N.B. TOTALS					125.3						214.2	0.0	0.0	0.0	37.2	0.0	40.9	0.0	61.3	0.0	64.0	136.0	0.0	0.0	1762.0	25	492	166.2	

PLOT DATE = 11-07-2011 10:08:20AM
 FILE NAME = S:\CONTRACTS\72E60\SCHEDULES.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = ahp

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

FAI 55& FAI 72 (I 55, I 72)
SECTION D6 PATCHING 2012
SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
DATE _____ CHECKED BY _____