

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011 100% STATE			CODE NO	ITEM	UNIT		0011 100% STATE		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	70	70		67100100	MOBILIZATION	L SUM	1	1			
20300100	CHANNEL EXCAVATION	CU YD	53	53		70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1			
20400800	FURNISHED EXCAVATION	CU YD	48	48		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
25000200	SEEDING, CLASS 2	ACRE	0.1	0.1		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	12		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8	8		70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5		70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6			
25100105	MULCH, METHOD 1	ACRE	0.2	0.2		70300100	SHORT TERM PAVEMENT MARKING	FOOT	64	64			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	22	22		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	834	834			
28000305	TEMPORARY DITCH CHECKS	FOOT	144	144		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21	21			
28000400	PERIMETER EROSION BARRIER	FOOT	180	180		70400100	TEMPORARY CONCRETE BARRIER	FOOT	287.5	287.5			
28100107	STONE RIPRAP, CLASS A4	SQ YD	185	185		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	287.5	287.5			
28200200	FILTER FABRIC	SQ YD	185	185		*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	834	834			
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	250	250		*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4			
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SQ YD	388	388		*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1		78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
40600300	AGGREGATE (PRIME COAT)	TON	0.6	0.6		78300100	PAVEMENT MARKING REMOVAL	SQ FT	469	469			
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	<b>372</b>	<b>372</b>		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4			
44000100	PAVEMENT REMOVAL	SQ YD	348	348		X0323265	REMOVE EXISTING RIPRAP	SQ YD	68	68			
44004250	PAVED SHOULDER REMOVAL	SQ YD	254	254		Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	<b>29,900</b>	<b>29,900</b>		Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	<b>430</b>	<b>430</b>			
50800515	BAR SPLICERS	EACH	159	159									
51500100	NAME PLATES	EACH	1	1									
54003000	CONCRETE BOX CULVERTS	CU YD	<b>163.2</b>	<b>163.2</b>									
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	270	270									
*63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	58	58									
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4									
63200310	GUARDRAIL REMOVAL	FOOT	347	347									
63500105	DELINEATORS	EACH	2	2									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6									

\* SPECIALTY ITEM