

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0011	
20200100	EARTH EXCAVATION	CU YD	430	430	
20300100	CHANNEL EXCAVATION	CU YD	690	690	
* 25000200	SEEDING, CLASS 2	ACRE	0.5	0.5	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27	
* 25100105	MULCH, METHOD 1	ACRE	1	1	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	54	54	
28000305	TEMPORARY DITCH CHECKS	FOOT	136	136	
28100107	STONE RIPRAP, CLASS A4	SO YD	867	867	
28200200	FILTER FABRIC	SO YD	989	989	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SO YD	96	96	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	34	34	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	167	167	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	51	51	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	51	51	
44000100	PAVEMENT REMOVAL	SO YD	303	303	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	452	452	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	151	151	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	76	76	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	9	9	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	104	104	
50200100	STRUCTURE EXCAVATION	CU YD	296	296	
50300100	FLOOR DRAINS	EACH	6	6	
50300225	CONCRETE STRUCTURES	CU YD	57.6	57.6	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	238	238	
50300260	BRIDGE DECK GROOVING	SO YD	518	518	
50300280	CONCRETE ENCASEMENT	CU YD	4.2	4.2	
50300300	PROTECTIVE COAT	SO YD	643	643	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0011	
50500505	STUD SHEAR CONNECTORS	EACH	1620	1620	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	59980	59980	
50800515	BAR SPLICERS	EACH	565	565	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	243	243	
51202305	DRIVING PILES	FOOT	243	243	
51203600	TEST PILE STEEL HP12X53	EACH	1	1	
51204650	PILE SHOES	EACH	12	12	
51500100	NAME PLATES	EACH	1	1	
52100520	ANCHOR BOLTS, 1"	EACH	24	24	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	75	75	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT PDSTS	FOOT	50	50	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	410	410	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	671	671	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2899	2899	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	775	775	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1190	1190	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	412.5	412.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5	362.5	
* 72000100	SIGN PANEL - TYPE 1	SO FT	10	10	
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	24	24	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1753	1753	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	446	446	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2	

\* SPECIALTY ITEM

FILE NAME =	USER NAME = BergMD	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\pwwork\pwwdot\gel\inh\dms52647\d76c2	-sht-500.dgn	DRAWN -	REVISED -			690	481B	CLINTON	46	3	
	PLOT SCALE = 50.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 76C21					
	PLOT DATE = 7/12/2011	DATE -	REVISED -			SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT