

**SUMMARY OF QUANTITIES**

				WILLIAMSON COUNTY	
				URBAN	
				FUNDING: STP 80% FEDERAL 20% STATE	FUNDING: STP 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	8,243	8,243	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	16	16	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,921	6,921	
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	1,800	1,800	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1,080	1,080	
42001300	PROTECTIVE COAT	SQ YD	5,154	5,154	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	195	195	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3,787	3,787	
42400800	DETECTABLE WARNINGS	SQ FT	81.2	81.2	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	27	27	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	44	44	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,900	1,900	
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	10	10	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	55,660		55,660
50901720	BICYCLE RAILING	FOOT	61		61
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	282.1		282.1
54010503	PRECAST CONCRETE BOX CULVERTS 5' X 3'	FOOT	50	50	
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	60	60	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8	8	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	562	562	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	277	277	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	245	245	

FILE NAME = J:\100T\09066803\Draw\CADD_Sheets\Frontage	USER NAME = Brian Bond	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES ILLINOIS ROUTE 13 FRONTAGE ROAD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	Road Contract\0998859-shr-500001.dgn	DRAWN -	REVISED -		331	(IX-1) R-7	WILLIAMSON	79	4				
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -						CONTRACT NO. 78251				
	PLOT DATE = 7/1/2011	DATE - 3/16/11	REVISED -		SCALE: N/A	SHEET NO.	OF	SHEETS	STA. N/A	TO STA. N/A	ILLINOIS FED. AID PROJECT		