

SUMMARY OF QUANTITIES				CONSTRUCTION CODES		
CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	0021	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701		L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801		L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	1440	1440	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS		SQ FT	520.0	520.0	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"		FOOT	6129	6129	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"		FOOT	671	671	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"		FOOT	1152	1152	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"		FOOT	217	217	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	5475	5475	
72000200	SIGN PANEL - TYPE 2		SQ FT	47.5	47.5	
Δ 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"		FOOT	5901	5901	
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"		FOOT	671	671	
Δ 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS		SQ FT	436.8	436.8	
Δ 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"		FOOT	954	954	
Δ 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"		FOOT	193	193	
78300100	PAVEMENT MARKING REMOVAL		SQ FT	347	347	
Δ 80400100	ELECTRIC SERVICE INSTALLATION		EACH	1	1	
Δ 81000400	CONDUIT IN TRENCH, 1/4" DIA., GALVANIZED STEEL		FOOT	21	21	
Δ 81000500	CONDUIT IN TRENCH, 1/2" DIA., GALVANIZED STEEL		FOOT	9	9	
Δ 81012600	CONDUIT IN TRENCH, 2" DIA., PVC		FOOT	84	84	
Δ 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC		FOOT	108	108	
Δ 81012800	CONDUIT IN TRENCH, 3" DIA., PVC		FOOT	45	45	
Δ 81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC		FOOT	9	9	
Δ 81013000	CONDUIT IN TRENCH, 4" DIA., PVC		FOOT	88	88	
Δ 81013100	CONDUIT IN TRENCH, 5" DIA., PVC		FOOT	52	52	
Δ 81013200	CONDUIT IN TRENCH, 6" DIA., PVC		FOOT	47	47	
Δ 81021380	CONDUIT, PUSHED 5" DIA., PVC	•	FOOT	62	62	
Δ 81021390	CONDUIT, PUSHED 6" DIA., PVC	•	FOOT	46	46	
Δ 81400100	HANDHOLE		EACH	4	4	
Δ 81400300	DOUBLE HANDHOLE		EACH	1	1	

Δ SPECIALTY ITEMS

FILE NAME = P:\08files\080297\05 Plans\Construction	USER NAME = seb	DESIGNED -	REVISED -	<b>CITY OF QUINCY</b> <b>730 MAINE STREET</b> <b>QUINCY, IL 62301</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.U. RTE. 7807	SECTION 08-00307-00-TL	COUNTY ADAMS	TOTAL SHEETS 50	SHEET NO. 4			
	ana\QUANT_080297.dgn	DRAWN -	REVISED -					SCALE: None		SHEET NO. 2 OF 4 SHEETS	STA. TO STA.	CONTRACT NO. 93554			
	PLOT SCALE = 20,0000 ' / IN.	CHECKED -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
	PLOT DATE = 6/28/2011	DATE -	REVISED -												