

**UTILITY ADJUSTMENT SCHEDULE**

LOCATION		56109210	56400510	60255500
		WATER VALVES TO BE ADJUSTED	FIRE HYDRANTS TO BE REMOVED AND REPLACED	MANHOLES TO BE ADJUSTED
		EACH	EACH	EACH
MAINE	109+62.3 44.5' LT	-	1	-
	109+95.0 33.6' RT	-	-	1
	110+13.5 33.1' RT	-	-	1
	112+81.2 28.0' LT	-	1	-
	114+14.4 27.2' LT	1	-	-
	114+17.2 28.4' LT	1	-	-
	114+18.3 28.4' LT	1	-	-
	116+54.5 28.0' LT	-	1	-
	120+58.9 28.0' LT	-	-	-
<b>TOTALS:</b>		<b>3</b>	<b>3</b>	<b>2</b>

**CURB & GUTTER SCHEDULE**

LOCATION	60603800
	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12
	FOOT
SW CORNER - 30TH & MAINE	18.1
NW CORNER - 30TH & MAINE	20.4
NE CORNER - 30TH & MAINE	15.7
MAINE - 98+72.5 TO 99+07.3 LT	34.8
MAINE - 99+88.4 TO 100+75.6 LT	87.2
MAINE - 104+73.2 TO 105+38.7 LT	65.5
MAINE - 106+54.9 TO 109+38.4 RT	284.1
MAINE - 106+35.2 TO 108+57.0 LT	221.8
NW CORNER - 33RD & MAINE	46.2
SW CORNER - 33RD & MAINE	54.7
NE CORNER - 33RD & MAINE	40.8
SE CORNER - 33RD & MAINE	86.0
MAINE - 110+83.5 TO 111+60.0 RT	76.5
MAINE - 111+99.3 TO 112+24.0 LT	24.7
MAINE - 113+29.9 TO 113+55.8 LT	25.9
<b>TOTALS:</b>	<b>1,102</b>

**PAVEMENT MARKING SCHEDULE**

LOCATION		78000300	78000400	78004200	78004250	78004280	X7800605	X7800620	X7800650	X7800680	Z0036200
		THERMOPLASTIC PAVEMENT MARKING - LINE 5"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	PREFORMED PLASTIC PVMT MARKING, TY B - INLAID - L&S	PREFORMED PLASTIC PVMT MARKING, TY B - INLAID - LINE 12"	PREFORMED PLASTIC PVMT MARKING, TY B - INLAID - LINE 24"	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	URETHANE PAVEMENT MARKING - LINE 5"	URETHANE PAVEMENT MARKING - LINE 12"	URETHANE PAVEMENT MARKING - LINE 24"	PAINT CURB
		YELLOW	WHITE	WHITE & YELLOW	WHITE	WHITE	WHITE & YELLOW	YELLOW	WHITE	WHITE	YELLOW
		FOOT	FOOT	SQ FT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT
MAINE	96+34 TO 96+85	18.0	13.0	-	136.0	23.2	-	-	-	-	-
	96+85 TO 101+00	1026.0	119.0	62.4	136.0	27.6	-	-	-	-	-
	101+00 TO 107+00	1500.0	-	78.0	-	-	-	-	-	-	-
	107+00 TO 110+00	583.0	290.0	93.6	150.0	38.4	-	-	-	-	-
	110+00 TO 113+00	643.7	170.0	46.8	128.0	29.3	-	-	-	-	-
	113+00 TO 119+00	1559.0	-	93.6	-	-	-	-	-	-	-
	119+00 TO 120+95	425.6	-	31.2	-	-	-	228.2	-	-	-
	30TH	39+00 to 40+00	114.0	60.0	31.2	128.0	24.8	-	-	-	-
	40+00 to 40+50	12.0	9.0	-	130.0	24.2	-	-	-	-	
33RD	7+86 TO 9+00	-	-	-	-	-	83.2	-	198.0	24.4	
QHS ENT	4+36 TO 5+00	19.4	9.7	-	146.0	25.2	-	-	-	-	
33RD & MAINE NW CURB		-	-	-	-	-	-	-	-	14.7	
33RD & MAINE NE CURB		-	-	-	-	-	-	-	-	11.7	
<b>TOTALS:</b>		<b>5,901</b>	<b>671</b>	<b>436.8</b>	<b>954</b>	<b>193</b>	<b>83.2</b>	<b>228</b>	<b>198</b>	<b>24</b>	<b>26</b>

**PAVEMENT MARKING REMOVAL SCHEDULE**

LOCATION	WIDTH	LENGTH	78300100
			PAVEMENT MARKING REMOVAL SQ FT
MAINE	120+36.4 TO 120+95	0.42'	232.0'
33RD	7+86 TO 8+06	0.50'	175.5'
		2.00'	5.5'
	8+06 TO 8+19	2.00'	27.8'
		0.42'	30.0'
	8+19 TO 9+50	-	-
<b>TOTALS:</b>			<b>346.8</b>

**SEEDING SCHEDULE**

LOCATION		25100105	X2500900
		MULCH, METHOD 1	SEEDING, CLASS 1 (SPECIAL)
		ACRE	ACRE
MAINE	97+00 TO 101+00 LT	0.034	0.034
	101+00 TO 107+00 LT	0.188	0.188
	101+00 TO 107+00 RT	0.005	0.005
	107+00 TO 109+96 LT	0.072	0.072
	107+00 TO 109+96 RT	0.069	0.069
	109+96 TO 113+00 LT	0.094	0.094
	109+96 TO 113+00 RT	0.046	0.046
	113+00 TO 119+00 LT	0.094	0.094
	119+00 TO 121+50 LT	0.054	0.054
<b>TOTALS:</b>		<b>0.7</b>	<b>0.7</b>

**PATCHING SCHEDULE**

LOCATION		44201737	44201741
		CLASS D PATCHES TYPE I, 8 INCH	CLASS D PATCHES TYPE II, 8 INCH
		SQ YD	SQ YD
MAINE	ESTIMATED QUANTITY	30	50
<b>TOTALS:</b>		<b>30</b>	<b>50</b>

LOCATIONS TO BE DETERMINED IN THE FILED BY THE ENGINEER.