

GENERAL NOTES

GENERAL

1. THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", PREPARED BY THE DEPARTMENT OF TRANSPORTATION OF THE STATE OF ILLINOIS AND ADOPTED BY SAID DEPARTMENT ON JANUARY 1, 2007, THE "MANUAL OF TEST PROCEDURES FOR MATERIALS" IN EFFECT OF THE DATE OF THE INVITATION FOR BIDS SHALL APPLY TO AND GOVERN THE CONSTRUCTION OF THE PROPOSED IMPROVEMENT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO ORDERING MATERIALS AND COMMENCING CONSTRUCTION.
3. THE CONTRACTOR SHALL STAGE ALL WORK IN SUCH A WAY AS TO MAINTAIN INGRESS AND EGRESS TO ALL ABUTTING PROPERTIES AT ALL TIMES DURING CONSTRUCTION. A QUANTITY FOR AGGREGATE FOR TEMPORARY ACCESS IS INCLUDED FOR THIS PURPOSE.

UTILITIES

1. UNDERGROUND FACILITIES, STRUCTURES AND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS. THEIR LOCATIONS MUST BE CONSIDERED TO BE APPROXIMATE ONLY. IT IS POSSIBLE THERE MAY BE OTHERS, THE EXISTENCE OF WHICH IS NOT PRESENTLY KNOWN OR SHOWN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THEIR EXISTENCE AND EXACT LOCATION AND TO AVOID DAMAGE THERETO. ILLINOIS LAW REQUIRES A MINIMUM 48-HOUR NOTICE TO ALL UTILITY COMPANIES BEFORE DIGGING. FIELD LOCATIONS OF UNDERGROUND FACILITIES MAY BE OBTAINED BY CALLING THE J.U.L.I.E. SYSTEM AT 1-800-892-0123 AND PROVIDING 48 HOURS ADVANCE NOTICE. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT LIMITS ARE LISTED BELOW.
2. ALL ROADSIDE OBJECTS (UTILITY POLES, FIRE HYDRANTS, SIGNS, ETC.) SHALL BE RELOCATED TO PROVIDE A MINIMUM OF 1.5 FEET CLEARANCE, MEASURED FROM THE FACE OF CURB TO THE NEAR EDGE OF THE OBJECT.
3. THE FOLLOWING UTILITY COMPANIES MAY HAVE FACILITIES LOCATED WITHIN THE LIMITS OF CONSTRUCTION WHICH MAY REQUIRE ADJUSTMENT, RELOCATION OR REMOVAL.

AMEREN IP (GAS & ELECTRIC)
1050 WEST BOULEVARD
BELLEVILLE, IL 62221
(618) 346-1287

HARRISON TELEPHONE CO. (TELEPHONE)
213 SOUTH MAIN
WATERLOO, IL 62298
(618) 939-9256

CHARTER COMMUNICATIONS (CABLE TV)
815 CHARTER COMMONS
TOWN & COUNTRY, MO 63017
(618) 387-6650

CITY OF COLUMBIA (SEWER & WATER)
110 WEST SAND BANK ROAD
COLUMBIA, IL 62236
(618) 281-4264

THE ABOVE INFORMATION REPRESENTS THE BEST INFORMATION AVAILABLE TO THE LOCAL AGENCY AND IS ONLY INCLUDED FOR THE CONVENIENCE OF THE BIDDER. IT IS UNDERSTOOD AND AGREED THAT THE CONTRACTOR HAS TAKEN THE FOREGOING INTO CONSIDERATION IN PREPARING HIS/HER BID, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ANY DELAYS OR INCONVENIENCE CAUSED BY SAME.

4. THE CONTRACTOR SHALL ADJUST WATER VALVES, MANHOLES, GAS VALVES AND OTHER ITEMS LOCATED WITHIN THE EXISTING ROADWAY AND SIDEWALK TO MATCH THE PROPOSED ROADWAY AND/OR SIDEWALK SURFACE. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

REMOVAL AND RESTORATION

1. THE CONTRACTOR SHALL PROVIDE BLOCKOUTS IN THE PROPOSED SIDEWALK FOR PLACEMENT OF SIGN POSTS AND MAILBOX SUPPORTS, AS DIRECTED BY THE ENGINEER.

3. THE CONTRACTOR SHALL CONFINE ALL OPERATIONS TO THE AREA LOCATED WITHIN THE CONSTRUCTION LIMITS AS SHOWN ON THE PLANS. ANY AREA DISTURBED BEYOND THESE LIMITS SHALL BE RESTORED TO ITS ORIGINAL CONDITION. ALL EARTH SURFACES DISTURBED BY CONSTRUCTION, INCLUDING THOSE OUTSIDE THE CONSTRUCTION LIMITS, SHALL BE FERTILIZED, GRADED, SEEDED AND MULCHED. AREAS OUTSIDE THE CONSTRUCTION LIMITS SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE. SEE THE SPECIAL PROVISIONS FOR MORE INFORMATION ON RESTORATION.
5. PAVEMENT, SIDEWALK AND CURB REMOVAL INCLUDES THE REMOVAL OF THE EXISTING AGGREGATE BASE NECESSARY TO GRADE FOR AND CONSTRUCT THE PROPOSED IMPROVEMENTS. SURPLUS AND/OR UNSUITABLE MATERIAL SHALL BE DISPOSED OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION."
6. THE CONTRACTOR SHALL NOTE THE LOCATION OF ALL MANHOLE, METER AND VALVE VAULT FRAMES AND LIDS LOCATED WITHIN THE CONSTRUCTION LIMITS. APPROPRIATE CARE SHALL BE TAKEN TO PROTECT THESE ITEMS DURING REMOVAL OPERATIONS.
7. THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA MIXTURES ARE PLACED.
9. ALL EXISTING FEATURES SUCH AS PAVEMENT, CURB, SIDEWALK, DRIVEWAY PAVEMENT, ROADWAY PAVEMENT, ETC. WHICH INTERFERE WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY THE CONTRACTOR UNLESS NOTED OTHERWISE ON THE PLANS. ALL MISCELLANEOUS FEATURES WHICH ARE TO BE REMOVED AND FOR WHICH THERE IS NO SPECIFIC PAY ITEM, WILL NOT BE MEASURED SEPARATELY FOR PAYMENT. THE COST OF THIS REMOVAL WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID FOR THE VARIOUS REMOVAL ITEMS INCLUDED IN THE CONTRACT.
11. THE CONTRACTOR SHALL MATCH PROPOSED IMPROVEMENTS INTO EXISTING CONDITIONS, INCLUDING MINOR GRADING AND PATCHING AT NO ADDITIONAL COST TO THE CONTRACT.
12. THE CONTRACTOR SHALL NOT REMOVE ANY CURB OR SIDEWALK THAT CANNOT BE RECONSTRUCTED WITHIN FIVE CALENDAR DAYS. ACCESS TO ALL BUSINESSES AND RESIDENCES SHALL BE MAINTAINED AT ALL TIMES EXCEPT DURING CONCRETE PLACEMENT. THE CONTRACTOR SHALL CONTACT BUSINESS OWNERS AND RESIDENTS 48 HOURS PRIOR TO CONSTRUCTION ADJACENT TO THEIR AFFECTED PROPERTIES.

PAVEMENT AND SIDEWALK

1. THE CONTRACTOR SHALL CONTACT THE ENGINEER UPON COMPLETION OF THE SUBGRADE AND PRIOR TO CONSTRUCTION OF THE AGGREGATE BASE COURSE PLACEMENT TO DETERMINE THE NECESSITY OF THE PROPOSED SUBGRADE IMPROVEMENTS.
2. HIGH EARLY STRENGTH CONCRETE MIX SHALL BE USED FOR THE CONSTRUCTION OF PCC ENTRANCES. THE COST OF HIGH EARLY STRENGTH CONCRETE MIX SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID FOR PCC DRIVEWAY PAVEMENT, 6 INCH.
3. AT VARIOUS LOCATIONS, IT MAY BE NECESSARY TO TRANSITION PROPOSED COMBINATION CURB AND GUTTER TO MEET EXISTING CURBS OR GUTTERS. THE MINIMUM LENGTH OF TRANSITIONAL COMBINATION CURB AND GUTTER SHALL BE 10 FEET, UNLESS DIRECTED OTHERWISE BY THE ENGINEER.
4. THE PAVEMENT MARKING LOCATIONS SHOWN IN THE PLANS ARE APPROXIMATE AND SHALL BE ADJUSTED AS DIRECTED BY THE ENGINEER, IF NECESSARY, TO MATCH FIELD CONDITIONS.

MISC

1. SEE THE SPECIAL PROVISIONS FOR OTHER INCLUDED CONSTRUCTION ITEMS AND OPERATIONS WHICH ARE TO BE INCLUDED WITH AND PAID FOR UNDER CERTAIN SPECIFICATION PAY ITEMS.
2. EXCAVATIONS SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES WITH APPROPRIATE LIGHTS.
3. ALL METALS AND COATINGS USED IN CONSTRUCTION FOR THE POLES, DOORS, FRAME AND GRATES, ETC. SHALL BE AMERICAN-MADE PER POLICY.

3. CARE SHALL BE TAKEN TO AVOID PROPOSED ELECTRICAL CONDUIT CONFLICTS WITH OTHER PROPOSED WORK. IF THE PROPOSED ELECTRICAL CONDUIT CONFLICTS WITH OTHER PROPOSED WORK, SUCH AS SIGN POST FOUNDATIONS, OR CONCRETE CURB, ETC., IT SHALL BE REMOVED AND RESET AT THE CONTRACTOR'S EXPENSE.
4. THE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL TO PROTECT LOCAL TRAFFIC IN ACCORDANCE WITH APPROPRIATE IDOT HIGHWAY STANDARDS FOR ALL WORK ALONG ROADWAYS.
5. THE FOLLOWING ITEMS ARE APPROXIMATE QUANTITIES AND ARE INCLUDED IN THE "SCHEDULE OF PRICES" IN ORDER TO ESTABLISH A UNIT COST FOR WORK WHICH MAY BE REQUIRED TO CONSTRUCT THIS SECTION. THE ACTUAL QUANTITY OF EACH ITEM SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.

EARTH EXCAVATION (SPECIAL)	130	CU YD
AGGREGATE FOR TEMPORARY ACCESS	50	TON
LOCATING UNDERGROUND CABLE	100	FT

6. THE FOLLOWING ABBREVIATIONS ARE USED IN THE PLANS AND SUPPLEMENT HIGHWAY STANDARD 000001.

BO	BY OTHERS (USED IN CONJUNCTION WITH TBA, & TBR)
CMU	CONCRETE MASONRY UNIT
CONSTR	CONSTRUCTION
CP	CONTROL POINT
ESMT	EASEMENT
INCL	INCLUDED
ME	MATCH EXISTING
PKG	PARKING
PE	PERMANENT EASEMENT
N/F	NOW AND FORMERLY
O/C	OIL AND CHIP
PERM	PERMANENT
PVC	POLYVINYL CHLORIDE PIPE
TCE	TEMPORARY CONSTRUCTION EASEMENT
TBA	TO BE ADJUSTED
TBR	TO BE REMOVED
TH	THICK
TYP	TYPICAL
W	WIDTH
Ø	DIAMETER

COMMITMENTS

1. PARCEL NO. 04-15-368-024

CONTRACTOR SHALL MAINTAIN ACCESS TO FRONT DOOR OF BUSINESS AT 128 SOUTH MAIN ST. AT ALL TIMES DURING CONSTRUCTION. CONTACT OWNERS RANDALL PRIOR & LORI PRIOR IN ADVANCE OF ANY WORK THAT DISTURBS THIS ACCESS. PHONE 618-939-1843.

2. PARCEL NO. 04-15-368-025

CONTRACTOR SHALL MAINTAIN ACCESS TO PARKING LOT AT 134 SOUTH MAIN ST. AT ALL TIMES DURING CONSTRUCTION. CONTACT OWNERS MICHAEL BUDDE & VIVIAN BUDDE IN ADVANCE OF ANY WORK THAT DISTURBS THIS ACCESS. PHONE 618-281-5135. EXISTING LANDSCAPING SHALL BE RESTORED UPON COMPLETION OF THE PROJECT.

3. PARCEL NO. 04-15-368-026

CONTRACTOR SHALL PROTECT AND PRESERVE THE EXISTING ORNAMENTAL FENCE & GATE AT 140 SOUTH MAIN ST.

4. PARCEL NO. 04-15-370-010

CONTRACTOR SHALL MAINTAIN ACCESS TO FRONT AND SIDE DOORS AT 123 SOUTH MAIN ST. AT ALL TIMES DURING CONSTRUCTION. CONTACT OWNER RANDALL ECKERT IN ADVANCE OF ANY WORK THAT DISTURBS THIS ACCESS. PHONE 618-476-3037.

FILE NAME = H:\P25040\DWG\PHASE 1\25040- GENERAL NOTES.DWG	USER NAME = ASHLEIGH ENGELMANN	DESIGNED - SLW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - SLW	REVISED -					9302	06-0045-00-SW	MONROE	24	2
	PLOT SCALE = 4 41/64" = 1'	CHECKED - TLC	REVISED -					CONTRACT NO. 97468				
	PLOT DATE = 2011-05-10	DATE - 2010-06-11	REVISED -					SCALE:	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	COLUMBIA	ILLINOIS