BIDDERS NEED NOT RETURN THE ENTIRE PROPOSAL (see instructions inside front cover)

1A

Proposal Submitted By	
Name	
Address	
City/State	9 Digit Zip Code
Telephone No.	Fax No.
Federal Employer Identification No. (FEI	N)
Email Address	

Letting September 23, 2011

NOTICE TO PROSPECTIVE BIDDERS

This proposal can be used for bidding purposes by only those companies that request and receive written AUTHORIZATION TO BID from IDOT's Central Bureau of Construction. (SEE INSTRUCTIONS ON THE INSIDE OF COVER)

Notice to Bidders, Specifications, Proposal, Contract and Contract Bond



Contract No. FA005
Fairfield Airport
Fairfield, Illinois
Wayne County
Illinois Project No. FWC-4105
Federal Project No. 3-17-0043-B12

For engineering information, contact Charles Hagloch of Hanson Professional Services, Inc. at 217-747-9376.

FAA	rules	proh	ibit	the	use	of
escala	ition	clause	es f	or	mater	ials.
Theref	ore, th	ne Divi	sion (of Ae	eronau	ıtics
canno	t off	er aı	ny r	nate	rial (cost
adjust	ment	provis	sions	for	proj	ects
that ut	ilize F	ederal	funds	S.		

PLEASE MARK THE APPROPRIATE BOX BELOW:				
A Bid Bond is included.				
A Cashier's Check or a Certified Check is included.				

INSTRUCTIONS

ABOUT IDOT PROPOSALS: All proposals issued by IDOT are potential bidding proposals. Each proposal contains all Certifications and Affidavits, a Proposal Signature Sheet and a Proposal Bid Bond required for Prime Contractors to submit a bid after written **Authorization to Bid** has been issued by IDOT's Central Bureau of Construction. In addition, this proposal contains new statutory requirements applicable to the use of subcontractors and, in particular, includes the <u>State Required Ethical Standards Governing Subcontractors</u> to be signed and incorporated into all subcontracts.

WHO CAN BID?: Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction. To request authorization, a potential bidder must complete and submit Part B of the Request for Authorization to Bid/or Not For Bid Status form (BDE 124 INT) and submit an original Affidavit of Availability (BC 57).

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?: When a prospective prime bidder submits a "Authorization to Bid or Not for Bid" form, he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued an Authorization to Bid or Not for Bid Report, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Authorization to Bid or Not for Bid Report will indicate the reason for denial. If a contractor has requested to bid but has not received a Authorization to Bid or Not for Bid Report, they should contact the Central Bureau of Construction in advance of the letting date.

WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

ABOUT SUBMITTING BIDS: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

Call

WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

Questions Regarding

Prequalification and/or Authorization to Bid (217)782-3413
Preparation and submittal of bids (217/782-7806)



PROPOSAL

TO THE DEPARTMENT OF TRANSPORTATION

1.	Proposal of	
Tax	xpayer Identification Number (Mandatory)	a

for the improvement identified and advertised for bids in the Invitation for Bids as:

- (a) Fairfield Airport
- (b) The proposed improvement shown in detail on the plans issued by the Department schedule and detail sheets included herein, includes, in general, the following described work:

Replace NAVAIDs and Airfield Lighting

2. The plans for the proposed work are those issued by the Department of Transportation to cover the work described above.

The specifications are those prepared by the Department of Transportation, Division of Aeronautics and designated as "Standard Specifications for Construction of Airports," the "Supplemental Specifications and Recurring Special Provisions," the "Interim Revisions to Supplemental Specifications and Recurring Special Provisions", latest editions located on the IDOT website at http://www.dot.il.gov/aero/airspecs.html, and the "Special Provisions" thereto, adopted and in effect on the date of invitation for bids.

3. COMPLETION TIME/LIQUIDATED DAMAGES. It being understood and agreed that the completion within the time limit is an essential part of the contract, the bidder agrees to complete the work within 31 calendar days, unless additional time is granted by the Engineer in accordance with the provisions of the specifications. In case of failure to complete the work on or before the time named herein, or within such extra time as may have been allowed by extensions, the bidder agrees that the Department of Transportation shall withhold from such sum as may be due him/her under the terms of this contract, the costs, as set forth below, which costs shall be considered and treated not as a penalty but as damages due to the State from the bidder by reason of the failure of the bidder to complete the work within the time specified in the contract. The following Schedule of Deductions supersedes the table given in Section 60-09 of the Division's Standard Specifications for Construction of Airports.

Schedule of Deductions for Each							
	Day of Overrun in Contract Time						
Original Cor	tract Amount	Daily	Charges				
From More Than	To and Including	Calendar Day	Work Day				
\$ 0	\$ 100,000	\$ 475	\$ 675				
100,000	500,000	750	1,050				
500,000	1,000,000	1,025	1,425				
1,000,000	3,000,000	1,275	1,725				
3,000,000	6,000,000	1,425	2,000				
6,000,000	12,000,000	2,300	3,450				
12,000,000	And over	5,800	8,125				

A daily charge shall be made for every day shown on the calendar beyond the specified contract time in calendar days.

- 4. **ASSURANCE OF EXAMINATION AND INSPECTION/WAIVER.** The undersigned further declares that he/she has carefully examined the proposal, plans, specifications, supplemental and applicable recurring special provisions, addenda, form of contract and contract bonds, and special provisions, and that he/she has inspected in detail the site of the proposed work, and that he/she has familiarized themselves with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this proposal he/she waives all right to plead any misunderstanding regarding the same.
- 5. EXECUTION OF CONTRACT AND CONTRACT BONDS. The undersigned further agrees to execute a contract for this work and present the same to the department within fifteen (15) days after the contract has been mailed to him/her. The undersigned further agrees that he/she and his/her surety will execute and present within fifteen (15) days after the contract has been mailed to him/her contract bond satisfactory to and in the form prescribed by the Department of Transportation, in the penal sum of the full amount of the contract, guaranteeing the faithful performance of the work in accordance with the terms of the contract.
- **6. PROPOSAL GUARANTY.** Accompanying this proposal is either a bid bond on the department form, executed by a corporate surety company satisfactory to the department, or a proposal guaranty check consisting of a bank cashier's check or a properly certified check for not less than 5 per cent of the amount bid or for the amount specified in the following schedule:

<u>.</u>	<u>Amount</u>	of Bid	Proposal <u>Guaranty</u>	An	<u>nount</u>	of Bid	Proposal <u>Guaranty</u>
Up to		\$5,000	\$150	\$2,000,000	to	\$3,000,000	\$100,000
\$5,000	to	\$10,000	\$300	\$3,000,000	to	\$5,000,000	\$150,000
\$10,000	to	\$50,000	\$1,000	\$5,000,000	to	\$7,500,000	\$250,000
\$50,000	to	\$100,000	\$3,000	\$7,500,000	to	\$10,000,000	\$400,000
\$100,000	to	\$150,000	\$5,000	\$10,000,000	to	\$15,000,000	\$500,000
\$150,000	to	\$250,000	\$7,500	\$15,000,000	to	\$20,000,000	\$600,000
\$250,000	to	\$500,000	\$12,500	\$20,000,000	to	\$25,000,000	\$700,000
\$500,000	to	\$1,000,000	\$25,000	\$25,000,000	to	\$30,000,000	\$800,000
\$1,000,000	to	\$1,500,000	\$50,000	\$30,000,000	to	\$35,000,000	\$900,000
\$1,500,000	to	\$2,000,000	\$75,000	over		\$35,000,000	\$1,000,000

Bank cashier's checks or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois, when the state is awarding authority; the county treasurer, when a county is the awarding authority; or the city, village, or town treasurer, when a city, village, or town is the awarding authority.

If a combination bid is submitted, the proposal guaranties which accompany the individual proposals making up the combination will be considered as also covering the combination bid.

The amount of the proposal guaranty check is _________\$(). If this proposal is accepted and the undersigned shall fail to execute contract bonds as required herein, it is hereby agreed that the amount of the proposal guaranty shall become the property of the State of Illinois, and shall be considered as payment of damages due to delay and other causes suffered by the State because of the failure to execute said contract and contract bonds; otherwise, the bid bond shall become void or the proposal guaranty check shall be returned to the undersigned.

Attach Cashier's Check or Certified Check Here

In the event that one proposal guaranty check is intended to cover two or more proposals, the amount must be equal to the sum of the proposal guaranties which would be required for each individual proposal. If the guaranty check is placed in another proposal, state below where it may be found.

check is placed in another proposal, state below where it may	e found.	
The proposal guaranty check will be found in the proposal for:	Item _	
	Airport	

Mark the proposal cover sheet as to the type of proposal guaranty submitted.

7. COMBINATION BIDS. The undersigned further agrees that if awarded the contract for the sections contained in the following combination, he/she will perform the work in accordance with the requirements of each individual proposal comprising the combination bid specified in the schedule below, and that the combination bid shall be prorated against each section in proportion to the bid submitted for the same. If an error is found to exist in the gross sum bid for one or more of the individual sections included in a combination, the combination bid shall be corrected as provided below.

A combination bid is a total bid received on 2 or more proposals. No combination bids other than those specifically set up by the Department will be considered. Separate proposal forms will be issued for each project in the combination so bids may be submitted on the combination as well as on separate units of the combination. The Department reserves the right to make awards on combination bids or separate bids to the best advantage of the Department.

If a combination bid is submitted on 2 or more proposals, separate proposals on each individual contract shall also be submitted, and unless separate proposals are so submitted, the combination bid will not be considered. If the bidder desires to submit a combination bid, the bidder shall state, in the place provided in the proposal form, the amount of the combination bid for the entire combination.

If a combination bid is submitted on any stipulated combination, and errors are found to exist in computing the gross sum bid on any one or more of the individual proposals, corrections shall be made, by the Department and the amount of the combination bid shall be corrected so that it will be in the same proportion to the sum of the corrected gross sum bid as the combination bid submitted was to the sum of the gross sum bid submitted.

The following provisions shall govern combination bidding:

- (a) A combination bid which is submitted for 2 or more proposals and awarded on that basis shall have the bid prorated against each proposal in proportion to the bid submitted for each proposal.
- (b) Separate contracts shall be executed for each individual proposal included in the combination.
- (c) The contract time for all contracts awarded on a combination bid shall be the sum of all calendar days contained within each contract included in the combination, unless otherwise provided in the contracts.
- (d) In the event the Contractor fails to complete any or all of the contracts on the combination bid within the contract time, including any authorized extension, the liquidated damages shall be determined from the schedule of deductions shown above in paragraph 3 for each day of overrun in contract time, based on the combination bid total, and shall be computed on the combination and prorated against the 2 or more individual contracts based on the dollar value of each contract.
- (e) The plans and Special Provisions for each separate contract shall be construed separately for all requirements, except as described in paragraphs (a) through (d) listed above.

When a combination bid is submitted, the schedule below must be completed in each proposal comprising the combination.

If alternate bids are submitted for one or more of the sections comprising the combination, a combination bid must be submitted for each alternate.

Schedule of Combination Bids

Combination		Combination	Combination Bid		
No.	Sections Included in Combination	Dollars	Cents		

- 8. SCHEDULE OF PRICES. The undersigned submits herewith, in accordance with the rules and instructions, a schedule of prices for the items of work for which bids are sought. The unit prices bid are in U.S. dollars and cents, and all extensions and summations have been made. The bidder understands that the quantities appearing in the bid schedule are approximate and are provided for the purpose of obtaining a gross sum for the comparison of bids. If there is an error in the extension of the unit prices, the unit prices shall govern. Payment to the contractor awarded the contract will be made only for actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as provided elsewhere in the contract.
- **9. AUTHORITY TO DO BUSINESS IN ILLINOIS.** Section 20-43 of the Illinois Procurement Code (30 ILCS 500/20-43) provides that a person (other than an individual acting as a sole proprietor) must be a legal entity authorized to do business in the State of Illinois prior to submitting the bid.
- 10. The services of a subcontractor will or may be used.

Check box Check box	· • · ·
	subcontractors with subcontracts with an annual value of more than \$25,000, the contract their name, address, and the dollar allocation for each subcontractor.

11. EXECUTION OF CONTRACT. The Department of Transportation will, in accordance with the rules governing Department procurements, execute the contract and shall be the sole entity having the authority to accept performance and make payments under the contract. Execution of the contract by the Chief Procurement Officer or the State Purchasing Officer is for approval of the procurement process and execution of the contract by the Department. Neither the Chief Procurement Officer nor the State Purchasing Officer shall be responsible for administration of the contract or determinations respecting the performance or payment there under except as otherwise permitted in the Illinois Procurement Code.

STATE JOB #-

AR125610 REILS

ILLINOIS DEPARTMENT OF TRANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - FA005

RUN DATE - 08/11/11 RUN TIME - 190101

COUNTY N WAYNE	NAME CODE DIST AIRPO	ORT NAME IPAL		FED PROJECT -17-0043-B12	ILL PROJI FW-C -410	
ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS CENTS	TOTAL PRICE	E
AR106930	REPLACE LIGHT FIXTURE	EACH	2.000	×	=	
AR107408	L-806 WIND CONE-8' LIGHTED	EACH	1.000	X	=	
AR107712	L-807 WIND CONE-12' LIGHTED	EACH	1.000	X	=	
AR107900	REMOVE WIND CONE	EACH	1.000	X	=======================================	
AR108084	1/C #4 XLP-USE	L.F.	1,530.000	X	=	
AR108086	1/C #6 XLP-USE	L.F.	2,100.000	X	=	
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	1,460.000	X	5	
AR108654	3/C #4 600 V UG CABLE IN UD	L.F.	5,050.000	X		
AR108656	3/C #6 600 V UG CABLE IN UD	L.F.	2,100.000	 X	=	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1.000	X	=	
AR110014	4" DIRECTIONAL BORE	L.F.	1,000.000	X	 	
AR110610	ELECTRICAL HANDHOLE	EACH	4.000	X	 =	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	8.000	X	 	
AR125565	SPLICE CAN	EACH	4.000	X	 =	

PAIR

1.000 X

FAIRFIELD MUNICIPAL WAYNE

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - FA005

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 08/11/11 RUN TIME - 190101

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRI DOLLARS	CE	TOTAL PRIC	CTS
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	8.000	A 34 34 34 34 34 34 34 34 34 34 34 34 34	=	DOLLARS	1013
AR125907	REMOVE REILS	PAIR	1.000	- .+			
AR125989	REFURBISH PLASI	EACH	2.000	(=====		
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.000	(
AR150520	MOBILIZATION	L.S.	1.000	(
l	· · · · · · · · · · · · · · · · · · ·			-	.		
				I	OTAL \$		1 1

NOTE:

- 1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
- 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
- 3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
- 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

THE PRECEDING SCHEDULE OF PRICES MUST BE

COMPLETED AND RETURNED.

STATE REQUIRED ETHICAL STANDARDS GOVERNING CONTRACT PROCUREMENT: ASSURANCES, CERTIFICATIONS AND DISCLOSURES

I. GENERAL

- **A.** Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.
- **B.** In order to comply with the provisions of Article 50 and to carry out the duty established therein, all bidders are to adhere to ethical standards established for the procurement process, and to make such assurances, disclosures and certifications required by law. Except as otherwise required in subsection III, paragraphs J-M, by execution of the Proposal Signature Sheet, the bidder indicates that each of the mandated assurances has been read and understood, that each certification is made and understood, and that each disclosure requirement has been understood and completed.
- **C.** In addition to all other remedies provided by law, failure to comply with any assurance, failure to make any disclosure or the making of a false certification shall be grounds for the chief procurement officer to void the contract, or subcontract, and may result in the suspension or debarment of the bidder or subcontractor.

II. ASSURANCES

The assurances hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder.

A. Conflicts of Interest

1. The Illinois Procurement Code provides in pertinent part:

Section 50-13. Conflicts of Interest.

- (a) Prohibition. It is unlawful for any person holding an elective office in this State, holding a seat in the General Assembly, or appointed to or employed in any of the offices or agencies of state government and who receives compensation for such employment in excess of 60% of the salary of the Governor of the State of Illinois, or who is an officer or employee of the Capital Development Board or the Illinois Toll Highway Authority, or who is the spouse or minor child of any such person to have or acquire any contract, or any direct pecuniary interest in any contract therein, whether for stationery, printing, paper, or any services, materials, or supplies, that will be wholly or partially satisfied by the payment of funds appropriated by the General Assembly of the State of Illinois or in any contract of the Capital Development Board or the Illinois Toll Highway authority.
- (b) Interests. It is unlawful for any firm, partnership, association or corporation, in which any person listed in subsection (a) is entitled to receive (i) more than 7 1/2% of the total distributable income or (ii) an amount in excess of the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (c) Combined interests. It is unlawful for any firm, partnership, association, or corporation, in which any person listed in subsection (a) together with his or her spouse or minor children is entitled to receive (i) more than 15%, in the aggregate, of the total distributable income or (ii) an amount in excess of 2 times the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (d) Securities. Nothing in this Section invalidates the provisions of any bond or other security previously offered or to be offered for sale or sold by or for the State of Illinois.
- (e) Prior interests. This Section does not affect the validity of any contract made between the State and an officer or employee of the State or member of the General Assembly, his or her spouse, minor child or any combination of those persons if that contract was in existence before his or her election or employment as an officer, member, or employee. The contract is voidable, however, if it cannot be completed within 365 days after the officer, member, or employee takes office or is employed.

The current salary of the Governor is \$177,412.00. Sixty percent of the salary is \$106,447.20.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-13, or that an effective exemption has been issued by the Board of Ethics to any individual subject to the Section 50-13 prohibitions pursuant to the provisions of Section 50-20 of the Code and Executive Order Number 3 (1998). Information concerning the exemption process is available from the Department upon request.

B. Negotiations

1. The Illinois Procurement Code provides in pertinent part:

Section 50-15. Negotiations.

- (a) It is unlawful for any person employed in or on a continual contractual relationship with any of the offices or agencies of State government to participate in contract negotiations on behalf of that office or agency with any firm, partnership, association, or corporation with whom that person has a contract for future employment or is negotiating concerning possible future employment.
- 2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-15, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

C. Inducements

1. The Illinois Procurement Code provides:

Section 50-25. Inducement. Any person who offers or pays any money or other valuable thing to any person to induce him or her not to bid for a State contract or as recompense for not having bid on a State contract is guilty of a Class 4 felony. Any person who accepts any money or other valuable thing for not bidding for a State contract or who withholds a bid in consideration of the promise for the payment of money or other valuable thing is guilty of a Class 4 felony.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-25, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

D. Revolving Door Prohibition

1. The Illinois Procurement Code provides:

Section 50-30. Revolving door prohibition. Chief procurement officers, State purchasing officers, procurement compliance monitors, their designees whose principal duties are directly related to State procurement, and executive officers confirmed by the Senate are expressly prohibited for a period of 2 years after terminating an affected position from engaging in any procurement activity relating to the State agency most recently employing them in an affected position for a period of at least 6 months. The prohibition includes, but is not limited to: lobbying the procurement process; specifying; bidding; proposing bid, proposal, or contract documents; on their own behalf or on behalf of any firm, partnership, association, or corporation. This Section applies only to persons who terminate an affected position on or after January 15, 1999.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-30, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

E. Reporting Anticompetitive Practices

1. The Illinois Procurement Code provides:

Section 50-40. Reporting anticompetitive practices. When, for any reason, any vendor, bidder, contractor, chief procurement officer, State purchasing officer, designee, elected official, or State employee suspects collusion or other anticompetitive practice among any bidders, offers, contractors, proposers, or employees of the State, a notice of the relevant facts shall be transmitted to the Attorney General and the chief procurement officer.

2. The bidder assures the Department that it has not failed to report any relevant facts concerning the practices addressed in Section 50-40 which may involve the contract for which the bid is submitted.

F. Confidentiality

1. The Illinois Procurement Code provides:

Section 50-45. Confidentiality. Any chief procurement officer, State purchasing officer, designee, or executive officer who willfully uses or allows the use of specifications, competitive bid documents, proprietary competitive information, proposals, contracts, or selection information to compromise the fairness or integrity of the procurement, bidding, or contract process shall be subject to immediate dismissal, regardless of the Personnel code, any contract, or any collective bargaining agreement, and may in addition be subject to criminal prosecution.

2. The bidder assures the Department that it has no knowledge of any fact relevant to the practices addressed in Section 50-45 which may involve the contract for which the bid is submitted.

I. Insider Information

1. The Illinois Procurement Act provides:

Section 50-50. Insider information. It is unlawful for any current or former elected or appointed State official or State employee to knowingly use confidential information available only by virtue of that office or employment for actual or anticipated gain for themselves or another person.

2. The bidder assures the Department that it has no knowledge of any facts relevant to the practices addressed in Section 50-50 which may involve the contract for which the bid is submitted.

III. CERTIFICATIONS

The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. Section 50-2 of the Illinois Procurement Code provides that every person that has entered into a multi-year contract and every subcontractor with a multi-year subcontract shall certify, by July 1 of each fiscal year covered by the contract after the initial fiscal year, to the responsible chief procurement officer whether it continues to satisfy the requirements of Article 50 pertaining to the eligibility for a contract award. If a contractor or subcontractor is not able to truthfully certify that it continues to meet all requirements, it shall provide with its certification a detailed explanation of the circumstances leading to the change in certification status. A contractor or subcontractor that makes a false statement material to any given certification required under Article 50 is, in addition to any other penalties or consequences prescribed by law, subject to liability under the Whistleblower Reward and Protection Act for submission of a false claim.

A. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
 - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
 - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government, or subcontracting under such a contract, as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
 - (1) the business has been finally adjudicated not guilty; or
 - (2) the business demonstrates to the governmental entity with which it seeks to contract, or which is signatory to the contract which the subcontract relates, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State, and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the contractor or the subcontractor, respectively, that the contractor or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any certifications required by this Section are false. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The contractor or subcontractor certifies that it is not barred from being awarded a contract under Section 50.5.

B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any State agency, or enter into a subcontract, from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. Certification. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder or contractor or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any of the certifications required by this Section are false.

C. <u>Debt Delinquency</u>

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency. The contractor or bidder or subcontractor, respectively, certifies that it, or any affiliate, is not barred from being awarded a contract or subcontract under the Procurement Code. Section 50-11 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax. The bidder or contractor or subcontractor, respectively, further acknowledges that the chief procurement officer may declare the related contract void if this certification is false or if the bidder, contractor, or subcontractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

D. Prohibited Bidders, Contractors and Subcontractors

1. The Illinois Procurement Code provides:

Section 50-10.5 and 50-60(c). Prohibited bidders, contractors and subcontractors.

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 or if in violation of Subsection (c) for a period of five years from the date of conviction. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder, contractor, or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer shall declare the related contract void if any of the certifications completed pursuant to this Section are false.

E. Section 42 of the Environmental Protection Act

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-12 that the bidder, contractor, or subcontractor, is not barred from being awarded a contract or entering into a subcontract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency, or entering into any subcontract, that is subject to the Procurement Code by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The bidder or contractor or subcontractor, respectively, acknowledges that the chief procurement officer may declare the contract void if this certification is false.

F. Educational Loan

- 1. Section 3 of the Educational Loan Default Act provides:
- § 3. No State agency shall contract with an individual for goods or services if that individual is in default, as defined in Section 2 of this Act, on an educational loan. Any contract used by any State agency shall include a statement certifying that the individual is not in default on an educational loan as provided in this Section.
- 2. The bidder, if an individual as opposed to a corporation, partnership or other form of business organization, certifies that the bidder is not in default on an educational loan as provided in Section 3 of the Act.

G. Bid-Rigging/Bid Rotating

- 1. Section 33E-11 of the Criminal Code of 1961 provides:
- § 33E-11. (a) Every bid submitted to and public contract executed pursuant to such bid by the State or a unit of local government shall contain a certification by the prime contractor that the prime contractor is not barred from contracting with any unit of State or local government as a result of a violation of either Section 33E-3 or 33E-4 of this Article. The State and units of local government shall provide the appropriate forms for such certification.
- (b) A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

A violation of Section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

2. The bidder certifies that it is not barred from contracting with the Department by reason of a violation of either Section 33E-3 or Section 33E-4.

H. International Anti-Boycott

- 1. Section 5 of the International Anti-Boycott Certification Act provides:
- § 5. State contracts. Every contract entered into by the State of Illinois for the manufacture, furnishing, or purchasing of supplies, material, or equipment or for the furnishing of work, labor, or services, in an amount exceeding the threshold for small purchases according to the purchasing laws of this State or \$10,000.00, whichever is less, shall contain certification, as a material condition of the contract, by which the contractor agrees that neither the contractor nor any substantially-owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the U.S. Export Administration Act of 1979 or the regulations of the U.S. Department of Commerce promulgated under that Act.
- 2. The bidder makes the certification set forth in Section 5 of the Act.

I. Drug Free Workplace

- 1. The Illinois "Drug Free Workplace Act" applies to this contract and it is necessary to comply with the provisions of the "Act" if the contractor is a corporation, partnership, or other entity (including a sole proprietorship) which has 25 or more employees.
- 2. The bidder certifies that if awarded a contract in excess of \$5,000 it will provide a drug free workplace by:
- (a) Publishing a statement notifying employees that the unlawful manufacture, distribution, dispensation, possession or use of a controlled substance, including cannabis, is prohibited in the contractor's workplace; specifying the actions that will be taken against employees for violations of such prohibition; and notifying the employee that, as a condition of employment on such contract, the employee shall abide by the terms of the statement, and notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.
- (b) Establishing a drug free awareness program to inform employees about the dangers of drug abuse in the workplace; the contractor's policy of maintaining a drug free workplace; any available drug counseling, rehabilitation, and employee assistance programs; and the penalties that may be imposed upon employees for drug violations.
- (c) Providing a copy of the statement required by subparagraph (1) to each employee engaged in the performance of the contract and to post the statement in a prominent place in the workplace.
- (d) Notifying the Department within ten (10) days after receiving notice from an employee or otherwise receiving actual notice of the conviction of an employee for a violation of any criminal drug statute occurring in the workplace.
- (e) Imposing or requiring, within 30 days after receiving notice from an employee of a conviction or actual notice of such a conviction, an appropriate personnel action, up to and including termination, or the satisfactory participation in a drug abuse assistance or rehabilitation program approved by a federal, state or local health, law enforcement or other appropriate agency.
- (f) Assisting employees in selecting a course of action in the event drug counseling, treatment, and rehabilitation is required and indicating that a trained referral team is in place.
- (g) Making a good faith effort to continue to maintain a drug free workplace through implementation of the actions and efforts stated in this certification.

J. Disclosure of Business Operations in Iran

Section 50-36 of the Illinois Procurement Code, 30ILCS 500/50-36 provides that each bid, offer, or proposal submitted for a State contract shall include a disclosure of whether or not the Company acting as the bidder, offeror, or proposing entity, or any of its corporate parents or subsidiaries, within the 24 months before submission of the bid, offer, or proposal had business operations that involved contracts with or provision of supplies or services to the Government of Iran, companies in which the Government of Iran has any direct or indirect equity share, consortiums or projects commissioned by the Government of Iran, or companies involved in consortiums or projects commissioned by the Government of Iran and either of the following conditions apply:

- (1) More than 10% of the Company's revenues produced in or assets located in Iran involve oil-related activities or mineral-extraction activities; less than 75% of the Company's revenues produced in or assets located in Iran involve contracts with or provision of oil-related or mineral-extraction products or services to the Government of Iran or a project or consortium created exclusively by that government; and the Company has failed to take substantial action.
- (2) The Company has, on or after August 5, 1996, made an investment of \$20 million or more, or any combination of investments of at least \$10 million each that in the aggregate equals or exceeds \$20 million in any 12-month period, which directly or significantly contributes to the enhancement of Iran's ability to develop petroleum resources of Iran.

The terms "Business operations", "Company", "Mineral-extraction activities", "Oil-related activities", "Petroleum resources", and "Substantial action" are all defined in the Code.


Failure to make the disclosure required by the Code shall cause the bid, offer or proposal to be considered not responsive. The disclosure will be considered when evaluating the bid, offer, or proposal or awarding the contract. The name of each Company disclosed as doing business or having done business in Iran will be provided to the State Comptroller.

Check the appropriate statement:

//	Company has no business operations in Iran to disclose.
//	Company has business operations in Iran as disclosed in the attached document.

K. Apprenticeship and Training Certification (Does not apply to federal aid projects)

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Department, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontracted work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project as reported on the Construction Employee Workforce Projection (Form BC-1256) and returned with the bid is accounted for and listed.



The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

L. Political Contributions and Registration with the State Board of Elections.

Sections 20-160 and 50-37 of the Illinois Procurement Code regulate political contributions from business entities and any affiliated entities or affiliated persons bidding on or contracting with the state. Generally under Section 50-37, any business entity, and any affiliated entity or affiliated person of the business entity, whose current year contracts with all state agencies exceed an awarded value of \$50,000, are prohibited from making any contributions to any political committees established to promote the candidacy of the officeholder responsible for the awarding of the contracts or any other declared candidate for that office for the duration of the term of office of the incumbent officeholder or a period 2 years after the termination of the contract, whichever is longer. Any business entity and affiliated entities or affiliated persons whose state contracts in the current year do not exceed an awarded value of \$50,000, either alone or in combination with contracts not exceeding \$50,000, are prohibited from making any political contributions to any political committee established to promote the candidacy of the officeholder responsible for awarding the pending contract during the period beginning on the date the invitation for bids or request for proposals is issued and ending on the day after the date of award or selection if the entity was not awarded or selected. Section 20-160 requires certification of registration of affected business entities in accordance with procedures found in Section 9-35 of The Election Code

By submission of a bid, the contractor business entity acknowledges and agrees that it has read and understands Sections 20-160 and 50-37 of the Illinois Procurement Code, and that it makes the following certification:

The undersigned business entity certifies that it has registered as a business with the State Board of Elections and acknowledges a continuing duty to update the registration in accordance with the above referenced statutes. A copy of the certificate of registration shall be submitted with the bid. The bidder is cautioned that the Department will not award a contract without submission of the certificate of registration.

These requirements and compliance with the above referenced statutory sections are a material part of the contract, and any breach thereof shall be cause to void the contract under Section 50-06 of the Illinois Procurement Code. These provisions do not apply to Federal-aid contracts.

M. Lobbyist Disclosure

Section 50-38 of the Illinois Procurement Code requires that any bidder or offeror on a State contract that hires a person required to register under the Lobbyist Registration Act to assist in obtaining a contract shall:

- Disclose all costs, fees, compensation, reimbursements, and other remunerations paid or to be paid to the lobbyist related to the contract,
- (ii) Not bill or otherwise cause the State of Illinois to pay for any of the lobbyist's costs, fees, compensation, reimbursements, or other remuneration, and
- (iii) Sign a verification certifying that none of the lobbyist's costs, fees, compensation, reimbursements, or other remuneration were billed to the State.

This information, along with all supporting documents, shall be filed with the agency awarding the contract and with the Secretary of State. The chief procurement officer shall post this information, together with the contract award notice, in the online Procurement Bulletin.

Pursuant to Subsection (c) of this Section, no person or entity shall retain a person or entity to attempt to influence the outcome of a procurement decision made under the Procurement Code for compensation contingent in whole or in part upon the decision or procurement. Any person who violates this subsection is guilty of a business offense and shall be fined not more than \$10,000.

Bidder acknowledges that it is required to disclose the hiring of any person required to register pursuant to the Illinois Lobbyist

Registration Act (25 ILCS 170) in connection with this contract.

Bidder has not hired any person required to register pursuant to the Illinois Lobbyist Registration Act in connection with this contract.

Or

Bidder has hired the following persons required to register pursuant to the Illinois Lobbyist Registration Act in connection with the contract:

Name and address of person:

All costs, fees, compensation, reimbursements and other remuneration paid to said person:

IV. DISCLOSURES

A. The disclosures hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The bidder further certifies that the Department has received the disclosure forms for each bid.

The chief procurement officer may void the bid, contract, or subcontract, respectively, if it is later determined that the bidder or subcontractor rendered a false or erroneous disclosure. A contractor or subcontractor may be suspended or debarred for violations of the Procurement Code. Furthermore, the chief procurement officer may void the contract and the surety providing the performance bond shall be responsible for completion of the contract.

B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that bids of more than \$25,000 shall be accompanied by disclosure of the financial interests of the bidder. This disclosed information for the successful bidder, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act, filed with the Procurement Policy Board, and shall be incorporated as a material term of the contract. Furthermore, pursuant to Section 5-5, the Procurement Policy Board may review a proposal, bid, or contract and issue a recommendation to void a contract or reject a proposal or bid based on any violation of the Procurement Code or the existence of a conflict of interest as provided in subsections (b) and (d) of Section 50-35.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the bidding entity or its parent entity, whichever is less, unless the contractor or bidder is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

The current annual salary of the Governor is \$177,412.00

In addition, all disclosures shall indicate any other current or pending contracts, proposals, leases, or other ongoing procurement relationships the bidding entity has with any other unit of state government and shall clearly identify the unit and the contract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies. **The forms must be included with each bid.**

C. <u>Disclosure Form Instructions</u>

Form A Instructions for Financial Information & Potential Conflicts of Interest

If the bidder is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a bidder is not subject to Federal 10K reporting, the bidder must determine if any individuals are required by law to complete a financial disclosure form. To do this, the bidder should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on Form A must be signed and dated by a person that is authorized to execute contracts for the bidding company. Note: These questions are for assistance only and are not required to be completed.

١.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than 60% of the annual salary of the Governor? YES NO
3.	Does anyone in your organization receive more than 60% of the annual salary of the Governor of the bidding entity's or parent entity's distributive income? (Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.) YESNO
1.	Does anyone in your organization receive greater than 5% of the bidding entity's or parent entity's total distributive income, but which is less than 60% of the annual salary of the Governor? YES NO
	(Note: Only one set of forms needs to be completed <u>per person per bid</u> even if a specific individual would require a yes answer to more than one question.)

A "YES" answer to any of these questions requires the completion of Form A. The bidder must determine each individual in the bidding entity or the bidding entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is authorized to execute contracts for your organization. **Photocopied or stamped signatures are not acceptable**. The person signing can be, but does not have to be, the person for which the form is being completed. The bidder is responsible for the accuracy of any information provided.

If the answer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> of Form A must be signed and dated by a person that is authorized to execute contracts for your company.

Form B: Instructions for Identifying Other Contracts & Procurement Related Information

Disclosure Form B must be completed for each bid submitted by the bidding entity. Note: Checking the <u>NOT APPLICABLE STATEMENT</u> on Form A <u>does not</u> allow the bidder to ignore Form B. Form B must be completed, checked, and dated or the bidder may be considered nonresponsive and the bid will not be accepted.

The Bidder shall identify, by checking Yes or No on Form B, whether it has any pending contracts (including leases), bids, proposals, or other ongoing procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the bidder only needs to complete the check box on the bottom of Form B. If "Yes" is checked, the bidder must do one of the following:

Option I: If the bidder did not submit an Affidavit of Availability to obtain authorization to bid, the bidder must list all non-IDOT State of Illinois agency pending contracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an attached sheet(s). Do not include IDOT contracts. Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts and are not to be included. Contracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development Board must be included. Bidders who submit Affidavits of Availability are suggested to use Option II

Option II: If the bidder is required and has submitted an Affidavit of Availability in order to obtain authorization to bid, the bidder may write or type "See Affidavit of Availability" which indicates that the Affidavit of Availability is incorporated by reference and includes all non-IDOT State of Illinois agency pending contracts, leases, bids, proposals, and other ongoing procurement relationships. For any contracts that are not covered by the Affidavit of Availability, the bidder must identify them on Form B or on an attached sheet(s). These might be such things as leases.

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form A Financial Information & Potential Conflicts of Interest Disclosure

Contractor Nam	e		
Legal Address			
City, State, Zip			
Telephone Num	ber	Email Address	Fax Number (if available)
(30 ILCS 500). Ve potential conflict of available contract t publicly traded co set forth in Form	ndors desiring to enter into interest information as spec ile. This Form A must be	a contract with the State of Illir cified in this Disclosure Form. T completed for bids in excess of disclosure (or equivalent if a astructions.	ection 50-35 of the Illinois Procurement Coonois must disclose the financial information are his information shall become part of the public f \$25,000, and for all open-ended contracts. pplicable) in satisfaction of the requiremen
	DISCLO	SURE OF FINANCIAL INFORM	MATION .
ownership or distri salary of the Gove individual meeting	butive income share in exc	ess of 5%, or an interest which s form as necessary and atta	n interest in the BIDDER (or its parent) in terms of has a value of more than 60% of the annuach a separate Disclosure Form A for each
ADDRESS			
Type of own	ership/distributable inc	ome share:	
stock % or \$ value	sole proprietorship of ownership/distributabl	partnership e income share:	other: (explain on separate sheet)
			cate which, if any, of the following potential lease attach additional pages and describe.
(a) State e	employment, currently or in t	the previous 3 years, including c	contractual employment of services. Yes No
If your	answer is yes, please answ	er each of the following question	
1.			oitol Development Board or the Illinois State To Yes No

your annual salary.

2. Are you currently appointed to or employed by any agency of the State of Illinois? If you are currently appointed to or employed by any agency of the State of Illinois, and your annual salary exceeds 60% of the annual salary of the Governor, provide the name of the State agency for which you are employed and

3.	If you are currently appointed to or employed by any agency salary exceeds 60% of the annual salary of the Governor, 1/2% of the total distributable income of your firm, partners amount in excess of 100% of the annual salary of the Governor.	are you entitled to receive (ship, association or corpora	(i) more than 7 tion, or (ii) an
4.	If you are currently appointed to or employed by any agent salary exceeds 60% of the annual salary of the Governor, entitled to receive (i) more than 15 % in the aggregate of the partnership, association or corporation, or (ii) an amount in Governor?	are you and your spouse of the total distributable income	r minor children e of your firm,
(b) State e	employment of spouse, father, mother, son, or daughter, inclus 2 years.	cluding contractual employer Yes	ment for services in No
If your a	answer is yes, please answer each of the following questions	S.	
1.	Is your spouse or any minor children currently an officer or or the Illinois State Toll Highway Authority?	r employee of the Capital De Yes	
2.	Is your spouse or any minor children currently appointed to Illinois? If your spouse or minor children is/are currently appointed to State of Illinois, and his/her annual salary exceeds 60% of name of your spouse and/or minor children, the name of the and his/her annual salary.	ppointed to or employed by the annual salary of the Go	any agency of the overnor, provide the
3.	If your spouse or any minor children is/are currently appoir of Illinois, and his/her annual salary exceeds 60% of the art to receive (i) more than 7 1/2% of the total distributable incorporation, or (ii) an amount in excess of 100% of the annual salary exceeds 60% of the annual salary exceeds 60	nnual salary of the Governo come of your firm, partnersh	or, are you entitled nip, association or ?
4.	If your spouse or any minor children are currently appointed of Illinois, and his/her annual salary exceeds 60% of the asspouse or minor children entitled to receive (i) more than 1 income of your firm, partnership, association or corporation salary of the Governor?	nnual salary of the Governo 15% in the aggregate of the	or, are you and your total distributable
of local go	e status; the holding of elective office of the State of Illinois, to exernment authorized by the Constitution of the State of r in the previous 3 years.		
(d) Relation	nship to anyone holding elective office currently or in the pro-	evious 2 years; spouse, fat Yes	her, mother, son, or No
America, o State of Illi	tive office; the holding of any appointive government office or any unit of local government authorized by the Constitutions, which office entitles the holder to compensation in excee currently or in the previous 3 years.	on of the State of Illinois o	r the statutes of the
 (f) Relation or daughte	nship to anyone holding appointive office currently or in the per.	revious 2 years; spouse, fa Yes	ther, mother, son,
(g) Employ	ment, currently or in the previous 3 years, as or by any regis	stered lobbyist of the State of Yes	government. No
(h) Relation daughter.	nship to anyone who is or was a registered lobbyist in the pr	revious 2 years; spouse, fat Yes	ther, mother, son, or No
registered	nsated employment, currently or in the previous 3 years, by with the Secretary of State or any county clerk of the Sta with either the Secretary of State or the Federal Board of Ele	ite of Illinois, or any politic	

(j) Relationship to anyone; spouse, father, mother, son, or daughter; who was a compensated employee in the last 2 years by any registered election or re-election committee registered with the Secretary of State or any county clerk of the State of Illinois, or any political action committee registered with either the Secretary of State or the Federal Board of Elections. Yes No
3. Communication Disclosure.
Disclose the name and address of each lobbyist and other agent of the bidder or offeror who is not identified in Section 2 of this form, who has communicated, is communicating, or may communicate with any State officer or employee concerning the bid or offer. This disclosure is a continuing obligation and must be promptly supplemented for accuracy throughout the process and throughout the term of the contract. If no person is identified, enter "None" on the line below:
Name and address of person(s):
4. Debarment Disclosure. For each of the persons identified under Sections 2 and 3 of this form, disclose whether any of the following has occurred within the previous 10 years: debarment from contracting with any governmental entity; professional licensure discipline; bankruptcies; adverse civil judgments and administrative findings; and criminal felony convictions. This disclosure is a continuing obligation and must be promptly supplemented for accuracy throughout the procurement process and term of the contract. If no person is identified, enter "None" on the line below: Name of person(s): Nature of disclosure:
APPLICABLE STATEMENT
This Disclosure Form A is submitted on behalf of the INDIVIDUAL named on previous page. Under penalty of perjury, I certify the contents of this disclosure to be true and accurate to the best of my knowledge.
Completed by:
Signature of Individual or Authorized Officer Date
NOT APPLICABLE STATEMENT
Under penalty of perjury, I have determined that no individuals associated with this organization meet the criteria that would require the completion of this Form A.
This Disclosure Form A is submitted on behalf of the CONTRACTOR listed on the previous page.
Signature of Authorized Officer Date

The bidder has a continuing obligation to supplement these disclosures under Sec. 50-35 of the Procurement Code.

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form B Other Contracts & Procurement Related Information Disclosure

		1				
Contractor Name						
Legal Address						
City, State, Zip						
Telephone Number	Email Address	Fax Number (if available)				
(30 ILCS 500). This information shall become	Disclosure of the information contained in this Form is required by the Section 50-35 of the Illinois Procurement Act (30 ILCS 500). This information shall become part of the publicly available contract file. This Form B must be completed for bids in excess of \$25,000, and for all open-ended contracts.					
DISCLOSURE OF OTHER CO	ONTRACTS AND PROCUREMENT F	RELATED INFORMATION				
Identifying Other Contracts & Procurem contracts (including leases), bids, proposals, o Yes No						
If "No" is checked, the bidder only needs to d	omplete the signature box on the bott	tom of this page.				
If "No" is checked, the bidder only needs to complete the signature box on the bottom of this page. 2. If "Yes" is checked. Identify each such relationship by showing State of Illinois agency name and other descriptive information such as bid or project number (attach additional pages as necessary). SEE DISCLOSURE FORM INSTRUCTIONS:						
THE FOLLOW	NG STATEMENT MUST BE CHE	ECKED				
Się	gnature of Authorized Representative	Date				

SPECIAL NOTICE TO CONTRACTORS

The following requirements of the Illinois Department of Human Rights' Rules and Regulations are applicable to bidders on all construction contracts advertised by the Illinois Department of Transportation:

CONSTRUCTION EMPLOYEE UTILIZATION PROJECTION

- (a) All bidders on construction contracts shall complete and submit, along with and as part of their bids, a Bidder's Employee Utilization Form (Form BC-1256) setting forth a projection and breakdown of the total workforce intended to be hired and/or allocated to such contract work by the bidder including a projection of minority and female employee utilization in all job classifications on the contract project.
- (b) The Department of Transportation shall review the Employee Utilization Form, and workforce projections contained therein, of the contract awardee to determine if such projections reflect an underutilization of minority persons and/or women in any job classification in accordance with the Equal Employment Opportunity Clause and Section 7.2 of the Illinois Department of Human Rights' Rules and Regulations for Public Contracts adopted as amended on September 17, 1980. If it is determined that the contract awardee's projections reflect an underutilization of minority persons and/or women in any job classification, it shall be advised in writing of the manner in which it is underutilizing and such awardee shall be considered to be in breach of the contract unless, prior to commencement of work on the contract project, it submits revised satisfactory projections or an acceptable written affirmative action plan to correct such underutilization including a specific timetable geared to the completion stages of the contract.
- (c) The Department of Transportation shall provide to the Department of Human Rights a copy of the contract awardee's Employee Utilization Form, a copy of any required written affirmative action plan, and any written correspondence related thereto. The Department of Human Rights may review and revise any action taken by the Department of Transportation with respect to these requirements.



Contract No. FA005
Fairfield Airport
Fairfield, Illinois
Wayne County
Illinois Project No. FWC-4105
Federal Project No. 3-17-0043-B12

BC 1256 (Rev. 12/11/07)

PART I. IDENTIFICATION					040 012													
Dept. Human Rights # Duration of Project:																		
Name of Bidder:																		
PART II. WORKFO A. The undersigned which this contract we projection including a	d bidder h	as analyz e perform	ed mir ed, an	d for th d fema	ne locati	ions fro	m whic	h the b	idder re	ecruits	employe	ees, and h	erel	y subm	its the foll	owir con	ng workfo	n orce
		TOTA	AL Wo	rkforce	Projec	tion for	Contra	ıct						(CURRENT TO BE			S
				MINO	ORITY I	EMPLO	YFFS			TR	AINEES				TO CO			
JOB CATEGORIES	EMPL	OYEES		ACK	HISP	ANIC	*OT		TIC	REN- ES	ON T	HE JOB INEES		EMPL	OTAL OYEES			OYEES
OFFICIALS (MANAGERS)	М	F	M	F	M	F	M	F	M	F	M	F		M	F		M	F
SUPERVISORS																		
FOREMEN																		
CLERICAL																		
EQUIPMENT OPERATORS																		
MECHANICS																		
TRUCK DRIVERS																		
IRONWORKERS																		
CARPENTERS																		
CEMENT MASONS																		
ELECTRICIANS																		
PIPEFITTERS, PLUMBERS																		
PAINTERS																		
LABORERS, SEMI-SKILLED																		
LABORERS, UNSKILLED																		
TOTAL																		
	TAI TOTAL Tr	BLE C	niectio	n for C	`ontract				7			FOR	DE	PARTM	IENT US	ΕO	NLY	
EMPLOYEES IN	TO	TAL OYEES		ACK		ANIC		ΓHER NOR.										
TRAINING	М	F	М	F	М	F	М	F	4									
APPRENTICES																		
ON THE JOB TRAINEES																		

Note: See instructions on page 2

Other minorities are defined as Asians (A) or Native Americans (N).

Please specify race of each employee shown in Other Minorities column.

Contract No. FA005
Fairfield Airport
Fairfield, Illinois
Wayne County
Illinois Project No. FWC-4105
Federal Project No. 3-17-0043-B12

PART II. WORKFORCE PROJECTION - continued

	luded in "Total Employees" under Table A event the undersigned bidder is awarded		v hires that would be employed in				
The rec	e undersigned bidder projects that: (numb	per) project is located; and/or (new hires would be number)				
	new hire ncipal office or base of operation is located	es would be recruited from	the area in which the bidder's				
dire	luded in "Total Employees" under Table A ectly by the undersigned bidder as well as ocontractors.						
be	e undersigned bidder estimates that (numb directly employed by the prime contractor ployed by subcontractors.	oer) and that (number)	persons will persons will be				
PART III. A	FFIRMATIVE ACTION PLAN						
em per cor Pla in n	e undersigned bidder understands and agriployee utilization projection included undersons or women in any job category, and intract, he/she will, prior to commencement in including a specific timetable (geared to minority and/or female employee utilization approval by the contracting agency and the	er PART II is determined to in the event that the unders t of work, develop and sub- to the completion stages of in are corrected. Such Affir	be an underutilization of minority signed bidder is awarded this mit a written Affirmative Action the contract) whereby deficiencies mative Action Plan will be subject				
pro	e undersigned bidder understands and agi jection submitted herein, and the goals an uired, are deemed to be part of the contra	nd timetable included unde					
Company		Telephor	ne Number				
Address _							
	NOTICE RI	EGARDING SIGNATURE					
The Biddeneeds to	er's signature on the Proposal Signature Shee be completed if revisions are required.	et will constitute the signing of	f this form. The following signature block				
Signature	:: 🗆	Title:	Date:				
Instructions:	All tables must include subcontractor personnel	I in addition to prime contractor p	personnel.				
Table A -	Include both the number of employees that w employed (Table B) that will be allocated to co Employees" column should include all employed on the contract work.	entract work, and include all appr	entices and on-the-job trainees. The "Total				
Table B -	Include all employees currently employed that job trainees currently employed.	will be allocated to the contract	work including any apprentices and on-the-				
Table C -	Indicate the racial breakdown of the total appre	ntices and on-the-job trainees sh	nown in Table A.				
			BC-1256 (Rev. 12/11/07)				

<u>CERTIFICATIONS REQUIRED BY STATE AND/OR FEDERAL LAW</u>. The bidder is required by State and/or Federal law to make the below certifications and assurances as a part of the proposal and contract upon award. It is understood by the bidder that the certifications and assurances made herein are a part of the contract.

By signing the Proposal Signature Sheet, the bidder certifies that he/she has read and completed each of the following certifications and assurances, that required responses are true and correct and that the certified signature of the Proposal Signature Sheet constitutes an endorsement and execution of each certification and assurance as though each was individually signed:

A. By the execution of this proposal, the signing bidder certifies that the bidding entity has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action, in restraint of free competitive bidding in connection with the submitted bid. This statement made by the undersigned bidder is true and correct under penalty of perjury under the laws of the United States.

B.	CERTIFICATION	, EQUAL EMPL	OYMENT (OPPORTUNITY
----	---------------	--------------	----------	-------------

(a)	Have you participated in any previous contracts or subcontracts subject to the equal opportunity clause? Yes No
(b)	If your answer is yes, have you filed with the Joint Reporting Committee, the Director of OFCC, any Federal agency, or the former President's Committee on Equal Employment Opportunity, all reports due under the applicable filing requirements of those organizations? Yes No

C. BUY AMERICAN - STEEL AND MANUFACTURED PRODUCTS FOR CONSTRUCTION CONTRACTS

- (a) The Aviation Safety and Capacity Expansion Act of 1990 provides that preference be given to steel and manufactured products produced in the United States when funds are expended pursuant to a grant issued under the Airport Improvement Program (AIP).
- (b) Any and all steel products used in the performance of this contract by the Contractor, subcontractors, producers, and suppliers are required to adhere to the Illinois Steel Products Procurement Act, which requires that all steel items be of 100 percent domestic origin and manufacture. Any products listed under the Federal Aviation Administration's (FAA) nationwide approved list of "Equipment Meeting Buy American Requirements" shall be deemed as meeting the requirements of the Illinois Steel Products Procurement Act.
- (c) The successful bidder will be required to assure that only domestic steel and domestically manufactured products will be used by the Contractor, subcontractors, producers, and suppliers in the performance of this contract. The North American Free Trade Agreement (NAFTA) specifically excluded federal grant programs such as the AIP. Therefore, NAFTA does not change the requirement to comply with the Buy American requirement in the Act. Exceptions to this are for products, other than steel, that:
 - (1) the FAA has determined, under the Aviation Safety and Capacity Expansion Act of 1990, are not produced in the United States in sufficient and reasonably available quantities or of a satisfactory quality;
 - (2) the FAA has determined, under the Aviation Safety and Capacity Expansion Act of 1990, that domestic preference would be inconsistent with the public interest;
 - (3) the FAA has determined that inclusion of domestic material will increase the cost of the overall project contract by more than 25 percent; or
 - (4) the FAA has determined, under the Aviation Safety and Capacity Expansion Act of 1990,
 - (i) the cost of components and subcomponents produced in the United States is more than 60 percent of the cost of all components of the facility or equipment, and
 - (ii) final assembly of the facility or equipment has occurred in the United States.

The FAA must grant waivers for any items that are included in these above exceptions. Bidders can review items already approved under the FAA nationwide approved list of "Equipment Meeting Buy American Requirements" on the FAA website, which do not require a specific FAA waiver.

All waivers are the responsibility of the Contractor, must be obtained prior to the Notice to Proceed, and must be submitted to the Division of Aeronautics for review and approval before being forwarded to the FAA. Any products used on the project that cannot meet the domestic requirement, and for which a waiver prior to the Notice to Proceed was not obtained, will be rejected for use and subject to removal and replacement with no additional compensation, and the contractor deemed non-responsive.

D. NPDES CERTIFICATION

In accordance with the provisions of the Illinois Environmental Protection Act, the Illinois Pollution Control Board Rules and Regulations (35 Ill. Adm. Code, Subtitle C, Chapter I), and the Clean Water Act, and the regulations thereunder, this certification is required for all construction contracts that will result in the disturbance of one or more acres total land area.

The undersigned bidder certifies under penalty of law that he/she understands the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit (ILR100000) that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification.

The Airport Owner or its Agent will:

- 1) prepare, sign and submit the Notice of Intent (NOI)
- 2) conduct site inspections and complete and file the inspection reports
- 3) submit Incidence of Non-Compliance (ION) forms
- 4) submit Notice of Termination (NOT) form

Prior to the issuance of the Notice-to-Proceed, for <u>each</u> erosion control measure identified in the Storm Water Pollution Prevention Plan, the contractor or subcontractor responsible for the control measure(s) must sign the above certification (forms to be provided by the Department).

E. NON-APPROPRIATION CLAUSE

By submitting a bid/proposal under this solicitation the offeror certifies that he/she understands that obligations of the State will cease immediately without penalty or further payment being required in any fiscal year the Illinois General Assembly fails to appropriate or otherwise make available sufficient funds for this contract.

F. Contractor is not delinquent in the payment of any debt to the State (or if delinquent has entered into a deferred payment plan to pay the debt), and Contractor acknowledges the contracting state agency may declare the contract void if this certification is false (30 ILCS 500/50-11, effective July 1, 2002).

NOTICE TO BIDDERS

- 1. TIME AND PLACE OF OPENING BIDS. Sealed proposals for the improvement described herein will be received by the Department of Transportation at the Harry R. Hanley Building, 2300 South Dirksen Parkway in Springfield, Illinois until 10:00 o'clock a.m., September 23, 2011. All bids will be gathered, sorted, publicly opened and read in the auditorium at the Department of Transportation's Harry R. Hanley Building shortly after the 10:00 a.m. cut off time.
- 2. **DESCRIPTION OF WORK**. The proposed improvement, shown in detail on the plans issued by the Department includes, in general, the following described work:

Replace NAVAIDs and Airfield Lighting

3. INSTRUCTIONS TO BIDDERS.

- (a) This Notice, the invitation for bids, proposal and award shall, together with all other documents in accordance with Article 10-15 of the Illinois Standard Specifications for Construction of Airports, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
- (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the proposal and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.
- **5. PRE-BID CONFERENCE.** There will be a pre-bid conference held at <u>N/A</u> at the Fairfield Airport administration building. For engineering information, contact Charles Hagloch of Hanson Professional Services, Inc. at 217-747-9376.
- DISADVANTAGED BUSINESS POLICY. The DBE goal for this contract is 3.7%.
- 7. SPECIFICATIONS AND DRAWINGS. The work shall be done in accordance with the Illinois Standard Specifications for Construction of Airports, the Illinois Division of Aeronautics Supplemental Specifications and Recurring Special Provisions, the Special Provisions dated <u>July 1, 2011</u> and the Construction Plans dated <u>July 1, 2011</u> as approved by the Department of Transportation, Division of Aeronautics.
- 8. **INSPECTION OF RECORDS.** The Contractor shall maintain an acceptable cost accounting system. The Sponsor, the FAA, and the Comptroller General of the United States shall have access to any books, documents, paper, and records of the Contractor which are directly pertinent to the specific contract for the purposes of making an audit, examination, excerpts, and transcriptions. The Contractor shall maintain all required records for three years after the Sponsor makes final payment and all other pending matters are closed.
- 9. RIGHTS TO INVENTIONS. All rights to inventions and materials generated under this contract are subject to Illinois law and to regulations issued by the FAA and the Sponsor of the Federal grant under which this contract is executed.

10. TERMINATION OF CONTRACT.

- The Sponsor may, by written notice, terminate this contract in whole or in part at any time, either for the Sponsor's
 convenience or because of failure to fulfill the contract obligations. Upon receipt of such notice services shall be
 immediately discontinued (unless the notice directs otherwise) and all materials as may have been accumulated in
 performing this contract, whether completed or in progress, delivered to the Sponsor.
- 2. If the termination is for the convenience of the Sponsor, an equitable adjustment in the contract price shall be made, but no amount shall be allowed for anticipated profit on unperformed services.
- If the termination is due to failure to fulfill the Contractor's obligations, the Sponsor may take over the work and prosecute the same to completion by contract or otherwise. In such case, the Contractor shall be liable to the Sponsor for any additional cost occasioned to the Sponsor thereby.
- 4. If, after notice of termination for failure to fulfill contract obligations, it is determined that the Contractor had not so failed, the termination shall be deemed to have been effected for the convenience of the Sponsor. In such event, adjustment in the contract price shall be made as provided in paragraph 2 of this clause.
- 5. The rights and remedies of the sponsor provided in this clause are in addition to any other rights and remedies provided by law or under this contract.
- **11. BIDDING REQUIREMENTS AND BASIS OF AWARD.** When alternates are included in the proposal, the following shall apply:
 - a. Additive Alternates
 - (1) Bidders must submit a bid for the Base Bid and for all Additive Alternates.
 - (2) Award of this contract will be made to the lowest responsible qualified bidder computed as follows:

The lowest aggregate amount of (i) the Base Bid plus (ii) any Additive Alternate(s) which the Department elects to award.

The Department may elect not to award any Additive Alternates. In that case, award will be to the lowest responsible qualified bidder of the Base Bid.

b. Optional Alternates

- (1) Bidders must submit a bid for the Base Bid and for either Alternate A or Alternate B or for both Alternate A and Alternate B.
- (2) Award of this contract will be made to the lowest responsible qualified bidder computed as follows:

The lower of the aggregate of either (i) the Base Bid plus Alternate A or (ii) the Base Bid plus Alternate B.

12. CONTRACT TIME. The Contractor shall complete all work within the specified contract time. Any calendar day extension beyond the specified contract time must be fully justified, requested by the Contractor in writing, and approved by the Engineer, or be subject to liquidated damages.

The contract time for this contract is 31 calendar days.

- 13. INDEPENDENT WEIGHT CHECKS. The Department reserves the right to conduct random unannounced independent weight checks on any delivery for bituminous, aggregate or other pay item for which the method of measurement for payment is based on weight. The weight checks will be accomplished by selecting, at random, a loaded truck and obtaining a loaded and empty weight on an independent scale. In addition, the department may perform random weight checks by obtaining loaded and empty truck weights on portable scales operated by department personnel.
- 14. GOOD FAITH COMPLIANCE. The Illinois Department of Transportation has made a good faith effort to include all statements, requirements, and other language required by federal and state law and by various offices within federal and state governments whether that language is required by law or not. If anything of this nature has been left out or if additional language etc. is later required, the bidder/contractor shall cooperate fully with the Department to modify the contract or bid documents to correct the deficiency. If the change results in increased operational costs, the Department shall reimburse the contractor for such costs as it may find to be reasonable.

15. ADDENDA AND REVISIONS: It is the contractor's responsibility to determine which, if any, addenda or revisions pertain to any project they may be bidding. Failure to incorporate all relevant addenda or revisions may cause the bid to be declared unacceptable.

Each addendum will be placed with the contract number. Addenda and revisions will also be placed on the Addendum/Revision Checklist and each subscription service subscriber will be notified by e-mail of each addendum and revision issued.

The Internet is the Department's primary way of doing business. The subscription server e-mails are an added courtesy the Department provides. It is suggested that the bidder check IDOT's website at http://www.dot.il.gov/desenv/delett.html before submitting final bid information.

IDOT IS NOT RESPONSIBLE FOR ANY E-MAIL RELATED FAILURES.

Technical Questions about downloading these files may be directed to Tim Garman (217)524-1624 or Timothy.Garman@illinois.gov.

DBE Utilization Plan



(1) Policy

It is public policy that disadvantaged businesses as defined in 49 CFR Part 26 and the Special Provision shall have the maximum opportunity to participate in the performance of contracts financed in whole or in part with Federal or State funds. Consequently the requirements of 49 CFR Part 26 apply to this contract.

(2) Obligation

The contractor agrees to ensure that disadvantaged businesses as defined in 49 CFR Part 26 and the Special Provision have the maximum opportunity to participate in the performance of contracts or subcontracts financed in whole or in part with Federal or State funds. The contractor shall take all necessary and reasonable steps in accordance with 49 CFR Part 26 and the Special Provision to ensure that said businesses have the maximum opportunity to compete for and perform under this contract. The contractor shall not discriminate on the basis of race, color, national origin or sex in the award and performance of contracts.

(3) Pro	ject and Bid Identification			
Complet	te the following information concerning the project and bid	:		
Route	Fairfield Airport	Total Bid		<u> </u>
Section		Contract DBE Goal	3.7%	(Dallar Amarch)
Project	FWC-4105		(Percent)	(Dollar Amount)
County	Wayne County			
Letting [Date <u>September 23, 2011</u>			
Contrac	t No. <u>FA005</u>			
Letting I	tem No. 1A			
(4) Ass	urance			
	in my capacity as an officer of the undersigned bidder (or my company: (check one)	bidders if a joint venture), hereby	y assure the De	epartment that on this
	Meets or exceeds contract award goals and has provide	ed documented participation as fo	ollows:	
_	Disadvantaged Business Participation pe	ercent		
	Attached are the signed participation statements, forms use of each business participating in this plan and assuri work of the contract.			
	Failed to meet contract award goals and has included go provided participation as follows:	ood faith effort documentation to r	meet the goals	and that my company has
	Disadvantaged Business Participation per	rcent		
	The contract goals should be accordingly modified or was upport of this request including good faith effort. Also a required by the Special Provision evidencing availability business will perform a commercially useful function in the	attached are the signed participal and use of each business participates.	tion statements	, forms SBE 2025,
	Company	The "as read" Low Bidder is re	equired to comply w	ith the Special Provision.
Ву		Submit only one utilization pla		
Title		Bureau of Small Business Ent 2300 South Dirksen Parkway Springfield, Illinois 62764	erprises	Local Let Projects Submit forms to the Local Agency
Date				

The Department of Transportation is requesting disclosure of information that is necessary to accomplish the purpose as outlined under State and Federal law. Disclosure of this information is **REQUIRED**. Failure to provide any information will result in the contract not being awarded. This form has been approved by the State Forms Manager Center.

SBE 2026 (Rev. 11/23/09)



DBE Participation Statement

Subcontract	or Registration	Le	etting September	23, 2011			
Participation	on Statement	Item No. 1A					
(1) Instructi	ons	Co	ontract FA00	5			
be submitted	ust be completed for each disadvantaged business d in accordance with the special provision and will be eded complete an additional form for the firm.						
(2) Work							
Pay Item No.	Description	Quantity	Unit Price	Total			
			Total				
	Payment Items ne above items which are partial pay items, specifica	ally describe the wor		t dollar			
(4) Commitment The undersigned certify that the information included herein is true and correct, and that the DBE firm listed below has agreed to perform a commercially useful function in the work of the contract item(s) listed above and to execute a contract with the prime contractor. The undersigned further understand that no changes to this statement may be made without prior approval from the Department's Bureau of Small Business Enterprises and that complete and accurate information regarding actual work performed on this project and the payment therefore							
	Signature for Prime Contractor	Sign	ature for DBE Firm				
Title		Title					
Date		Date					
Contact		Contact					
Phone		Phone					
Firm Name		Firm Name					
Address _		Address					
City/State/Z	ip	City/State/Zip					
			E				
federal law. Disclosur	ansportation is requesting disclosure of information that is necessary to accomplish the statuto re of this information is REQUIRED . Failure to provide any information will result in the contract Forms Management Center.						

SBE 2025 (Rev. 11/03.09)

Contract No. FA005
Fairfield Airport
Fairfield, Illinois
Wayne County
Illinois Project No. FWC-4105
Federal Project No. 3-17-0043-B12

PROPOSAL SIGNATURE SHEET

The undersigned bidder hereby makes and submits this bid on the subject Proposal, thereby assuring the Department that all requirements of the Invitation for Bids and rules of the Department have been met, that there is no misunderstanding of the requirements of paragraph 4 of this Proposal, and that the contract will be executed in accordance with the rules of the Department if an award is made on this bid.

	Firm Name	
(IF AN INDIVIDUAL)	Signature of Owner	
	Business Address	
	Firm Name	
	Ву	
(IF A CO-PARTNERSHIP)	Business Address	
,		
	Name and Address of	All Members of the Firm:
	Corporate Name	
	,	Signature of Authorized Representative
(IF A CORPORATION)		Typed or printed name and title of Authorized Representative
(IF A JOINT VENTURE, USE THIS	Attest	
SECTION FOR THE MANAGING	Attool	Signature
PARTY AND THE SECOND PARTY SHOULD SIGN BELOW)	Business Address	
	Corporate Name	
	Ву	
	Бу	Signature of Authorized Representative
(IF A JOINT VENTURE)		Typed or printed name and title of Authorized Representative
	Attest	Signature
		Signature
	Business Address	
If more than two parties are in the joint ve	nture please attach addition	onal signature sheet

Return with Bid



Division of Aeronautics Proposal Bid Bond

Sponsor			Item No.
IL Proj. No.	AIP Proj. No.		Letting Date
KNOW ALL MEN BY THESE PRES	SENTS, That We		
as PRINCIPAL, and			
			as SURETY, are
	Guarantee of the Proposal Do	cument, whichever is the	Im of 5 percent of the total bid price, or for the amour the lesser sum, well and truly to be paid unto sai s, successors and assigns.
	State of Illinois, Department of	Transportation, Division	RINCIPAL has submitted a bid proposal to the of Aeronautics, for the improvement designated by the
and as specified in the bidding and the award by AGENT on behalf of S documents, including evidence of the faithful performance of such contract the failure of the PRINCIPAL to ma pays to the SPONSOR the difference	contract documents, submit a ESPONSOR, the PRINCIPAL sha he required insurance coverage ct and for the prompt payment of ke the required DBE submission ce not to exceed the penalty he ract with another party to perform	DBE Utilization Plan that all enter into a contract in as and providing such boof labor and material furing or to enter into such coreof between the amoun	posal of the PRINCIPAL; and if the PRINCIPAL shall is accepted and approved by the AGENT; and if, after accordance with the terms of the bidding and contract and as specified with good and sufficient surrety for the hished in the prosecution thereof; or if, in the event contract and to give the specified bond, the PRINCIPA to specified in the bid proposal and such larger amounts and bid proposal, then this obligation shall be null and
forth in the preceding paragraph, the SURETY does not make full payme	nen SURETY shall pay the pena ent within such period of time, the	al sum to the SPONSOR ne AGENT may bring an	PAL has failed to comply with any requirement as sewithin fifteen (15) days of written demand therefor, action to collect the amount owed. SURETY is liable in any litigation in which SPONSOR or AGENT prevails.
In TESTIMONY WHEREOF,	the said PRINCIPAL and the sa	id SURETY have caused	d this instrument to be signed by
their respective officers	day of		A.D., .
PRINCIPAL		SURETY	
(Company N	ame)	<u> </u>	(Company Name)
Dv		Dv.,	
By(Signatu	ure & Title)	By:	(Signature of Attorney-in-Fact)
	Notary Certificat	ion for Principal and S	urety
STATE OF ILLINOIS, County of			
I,		, a Notary Public	in and for said County, do hereby certify that
		and	
	(Insert names of individuals sig	gning on behalf of PRINC	CIPAL & SURETY)
	this day in person and acknowle		d to the foregoing instrument on behalf of PRINCIPA they signed and delivered said instrument as their fre
Given under my hand and no	tarial seal this	day of	A.D
My commission expires			
,			Notary Public
marking the check box next to the	Signature and Title line below,	the Principal is ensuring	an Electronic Bid Bond. By signing the proposal an the identified electronic bid bond has been execute the conditions of the bid bond as shown above.
Electronic Bid Bond ID#	Company / Bidder Nan	ne	Signature and Title

PROPOSAL ENVELOPE



PROPOSALS

for construction work advertised for bids by the Illinois Department of Transportation

Item No.	Item No.	Item No.

Submitted By:

Name:
Address:
Phone No.

Bidders should use an IDOT proposal envelope or affix this form to the front of a 10" x 13" envelope for the submittal of bids. If proposals are mailed, they should be enclosed in a second or outer envelope addressed to:

Engineer of Design and Environment - Room 326 Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764

NOTICE

Individual bids, including Bid Bond and/or supplemental information if required, should be securely stapled.

CONTRACTOR OFFICE COPY OF CONTRACT SPECIFICATIONS

NOTICE

None of the following material needs to be returned with the bid package unless the special provisions require documentation and/or other information to be submitted.

Contract No. FA005
Fairfield Airport
Fairfield, Illinois
Wayne County
Illinois Project No. FWC-4105
Federal Project No. 3-17-0043-B12



SUBCONTRACTOR DOCUMENTATION

Public Acts 96-0795 and 96-0920, enacted substantial changes to the provisions of the Illinois Procurement Code (30 ILCS 500). Among the changes are provisions affecting subcontractors. The Contractor awarded this contract will be required as a material condition of the contract to implement and enforce the contract requirements applicable to subcontractors approved in accordance with Section 60-01 of the Illinois Standard Specifications for Construction of Airports.

If the Contractor seeks approval of subcontractors to perform a portion of the work, and approval is granted by the Department, the Contractor shall provide a copy of the subcontract to the Chief Procurement Officer within 20 calendar days after execution of the subcontract.

The subcontract shall contain the certifications required to be made by subcontractors pursuant to Article 50 of the Illinois Procurement Code. This Notice to Bidders includes a document incorporating all required subcontractor certifications and disclosures for use by the Contractor in compliance with this mandate. The document is entitled <u>State Required Ethical Standards Governing Subcontractors</u>.

STATE ETHICAL STANDARDS GOVERNING SUBCONTRACTORS

Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.

The certifications hereinafter made by the subcontractor are each a material representation of fact upon which reliance is placed should the Department approve the subcontractor. The chief procurement officer may terminate or void the subcontract approval if it is later determined that the bidder or subcontractor rendered a false or erroneous certification.

Section 50-2 of the Illinois Procurement Code provides that every person that has entered into a multi-year contract and every subcontractor with a multi-year subcontract shall certify, by July 1 of each fiscal year covered by the contract after the initial fiscal year, to the responsible chief procurement officer whether it continues to satisfy the requirements of Article 50 pertaining to the eligibility for a contract award. If a contractor or subcontractor is not able to truthfully certify that it continues to meet all requirements, it shall provide with its certification a detailed explanation of the circumstances leading to the change in certification status. A contractor or subcontractor that makes a false statement material to any given certification required under Article 50 is, in addition to any other penalties or consequences prescribed by law, subject to liability under the Whistleblower Reward and Protection Act for submission of a false claim.

A. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
 - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
 - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government, or subcontracting under such a contract, as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
 - (1) the business has been finally adjudicated not guilty; or
 - (2) the business demonstrates to the governmental entity with which it seeks to contract, or which is signatory to the contract to which the subcontract relates, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State, and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the contractor or the subcontractor, respectively, that the contractor or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any certifications required by this Section are false. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The contractor or subcontractor certifies that it is not barred from being awarded a contract under Section 50.5.

B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any State agency, or enter into a subcontract, from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. Certification. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder or contractor or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer may declare the related contract void if any of the certifications required by this Section are false.

C. <u>Debt Delinquency</u>

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder or subcontractor, respectively, certifies that it, or any affiliate, is not barred from being awarded a contract or subcontract under the Procurement Code. Section 50-11 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency, or entering into a subcontract, if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The bidder or contractor or subcontractor, respectively, further acknowledges that the chief procurement officer may declare the related contract void if this certification is false or if the bidder, contractor, or subcontractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

D. Prohibited Bidders, Contractors and Subcontractors

1. The Illinois Procurement Code provides:

Section 50-10.5 and 50-60(c). Prohibited bidders, contractors and subcontractors.

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 or if in violation of Subsection (c) for a period of five years from the date of conviction. Every bid submitted to and contract executed by the State and every subcontract subject to Section 20-120 of the Procurement Code shall contain a certification by the bidder, contractor, or subcontractor, respectively, that the bidder, contractor, or subcontractor is not barred from being awarded a contract or subcontract under this Section and acknowledges that the chief procurement officer shall declare the related contract void if any of the certifications completed pursuant to this Section are false.

E. Section 42 of the Environmental Protection Act

The bidder or contractor or subcontractor, respectively, certifies in accordance with 30 ILCS 500/50-12 that the bidder, contractor, or subcontractor, is not barred from being awarded a contract or entering into a subcontract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency, or entering into any subcontract, that is subject to the Procurement Code by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The bidder or contractor or subcontractor, respectively, acknowledges that the chief procurement officer may declare the contract void if this certification is false.

The undersigned, on behalf of the subcontracting company, has read and understands the above certifications and makes the certifications as required by law.

Name of Subcontracting Company	
Authorized Officer	Date

SUBCONTRACTOR DISCLOSURES

I. DISCLOSURES

A. The disclosures hereinafter made by the subcontractor are each a material representation of fact upon which reliance is placed. The subcontractor further certifies that the Department has received the disclosure forms for each subcontract.

The chief procurement officer may void the bid, contract, or subcontract, respectively, if it is later determined that the bidder or subcontractor rendered a false or erroneous disclosure. A contractor or subcontractor may be suspended or debarred for violations of the Procurement Code. Furthermore, the chief procurement officer may void the contract or subcontract.

B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that all subcontracts with a total value of \$25,000 or more from subcontractors identified in Section 20-120 of the Illinois Procurement Code shall be accompanied by disclosure of the financial interests of the subcontractor. This disclosed information for the subcontractor, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act, filed with the Procurement Policy Board, and shall be incorporated as a material term of the Prime Contractor's contract. Furthermore, pursuant to this Section, the Procurement Policy Board may recommend to allow or void a contract or subcontract based on a potential conflict of interest.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the subcontracting entity or its parent entity, whichever is less, unless the subcontractor is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a subcontractor is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

The current annual salary of the Governor is \$177,412.00.

In addition, all disclosures shall indicate any other current or pending contracts, subcontracts, proposals, leases, or other ongoing procurement relationships the subcontracting entity has with any other unit of state government and shall clearly identify the unit and the contract, subcontract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies.

C. <u>Disclosure Form Instructions</u>

Form A Instructions for Financial Information & Potential Conflicts of Interest

If the subcontractor is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a subcontractor is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a subcontractor is not subject to Federal 10K reporting, the subcontractor must determine if any individuals are required by law to complete a financial disclosure form. To do this, the subcontractor should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on the second page of Form A must be signed and dated by a person that is authorized to execute contracts for the subcontracting company. Note: These questions are for assistance only and are not required to be completed.

1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than 60% of the annual salary of the Governor? YES NO
3.	Does anyone in your organization receive more than 60% of the annual salary of the Governor of the subcontracting entity's or parent entity's distributive income? (Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.) YES NO
4.	Does anyone in your organization receive greater than 5% of the subcontracting entity's or parent entity's total distributive income, but which is less than 60% of the annual salary of the Governor? YES NO
`	ote: Only one set of forms needs to be completed per person per subcontract even if a specific individual would require a yes answer to more an one question.)

A "YES" answer to any of these questions requires the completion of Form A. The subcontractor must determine each individual in the subcontracting entity or the subcontracting entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is authorized to execute contracts for your organization. **Photocopied or stamped signatures are not acceptable**. The person signing can be, but does not have to be, the person for which the form is being completed. The subcontractor is responsible for the accuracy of any information provided.

If the answer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on page 2 of Form A must be signed and dated by a person that is authorized to execute contracts for your company.

Form B: Instructions for Identifying Other Contracts & Procurement Related Information

Disclosure Form B must be completed for each subcontract submitted by the subcontracting entity. Note: Checking the NOT APPLICABLE STATEMENT on Form A does not allow the subcontractor to ignore Form B. Form B must be completed, checked, and dated or the subcontract will not be approved.

The Subcontractor shall identify, by checking Yes or No on Form B, whether it has any pending contracts, subcontracts, leases, bids, proposals, or other ongoing procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the subcontractor only needs to complete the check box on the bottom of Form B. If "Yes" is checked, the subcontractor must list all non-IDOT State of Illinois agency pending contracts, subcontracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an attached sheet(s). Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts and are not to be included. Contracts or subcontracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development Board must be included.

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form A Subcontractor: Financial Information & Potential Conflicts of Interest Disclosure

Subcontractor Name		
Substitution Number		
Legal Address		
•		
City State 7in		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)
Tolophone Humbol	Linaii / Idai 600	Tax Hamber (il avallable)

Disclosure of the information contained in this Form is required by the Section 50-35 of the Illinois Procurement Code (30 ILCS 500). Subcontractors desiring to enter into a subcontract of a State of Illinois contract must disclose the financial information and potential conflict of interest information as specified in this Disclosure Form. This information shall become part of the publicly available contract file. This Form A must be completed for subcontracts with a total value of \$25,000 or more, from subcontractors identified in Section 20-120 of the Illinois Procurement Code, and for all open-ended contracts. A publicly traded company may submit a 10K disclosure (or equivalent if applicable) in satisfaction of the requirements set forth in Form A. See Disclosure Form Instructions.

The current annual salary of the Governor is \$177,412.00.

DISCLOSURE OF FINANCIAL INFORMATION

1. Disclosure of Financial Information. The individual named below has an interest in the SUBCONTRACTOR (or its parent) in terms of ownership or distributive income share in excess of 5%, or an interest which has a value of more than 60% of the annual salary of the Governor. (Make copies of this form as necessary and attach a separate Disclosure Form A for each individual meeting these requirements)

FOR INDIVIDUAL (type or print information)		
NAME:			
ADDRESS			
Type of owner	rship/distributable income share:		
stock	sole proprietorship	Partnership	other: (explain on separate sheet):
% or \$ value of	ownership/distributable income shar	e:	
	interest relationships apply. If the		indicate which, if any, of the following tion is "Yes", please attach additional
(a) State employme	ent, currently or in the previous 3		ctual employment of services. s No
If your answer i	s yes, please answer each of the	following questions.	
-	currently an officer or employee nway Authority?	of either the Capitol De	evelopment Board or the Illinois State Yes No

	2.	appointed to or employed by any agency of the State of Illinois? If you are currently appointed to or employed by any agency of the State of Illinois, and your annual salary exceeds 60% of the annual salary of the Governor, provide the name the State agency for which you are employed and your annual salary
	3.	If you are currently appointed to or employed by any agency of the State of Illinois, and your annual salary exceeds 60% of the annual salary of the Governor, are you entitled to receive (i) more than 7 1/2% of the total distributable income of your firm, partnership, association or corporation, or (ii) an amount in excess of 100% of the annual salary of the Governor? Yes No
	4.	If you are currently appointed to or employed by any agency of the State of Illinois, and your annual salary exceeds 60% of the annual salary of the Governor, are you and your spouse or minor children entitled to receive (i) more than 15 % in the aggregate of the total distributable income of your firm, partnership, association or corporation, or (ii) an amount in excess of two times the salary of the Governor? Yes No
(b)		employment of spouse, father, mother, son, or daughter, including contractual employment services in evious 2 years. Yes No
	If your	answer is yes, please answer each of the following questions.
	1.	Is your spouse or any minor children currently an officer or employee of the Capitol Development Board or the Illinois State Toll Highway Authority? Yes No
	2.	Is your spouse or any minor children currently appointed to or employed by any agency of the State of Illinois? If your spouse or minor children is/are currently appointed to or employed by any agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, provide the name of your spouse and/or minor children, the name of the State agency for which he/she is employed and his/her annual salary
	3.	If your spouse or any minor children is/are currently appointed to or employed by any agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are you entitled to receive (i) more than 7 1/2% of the total distributable income of your firm, partnership, association or corporation, or (ii) an amount in excess of the salary of the Governor? Yes No
	4.	If your spouse or any minor children are currently appointed to or employed by any agency of the State of Illinois, and his/her annual salary exceeds 60% of the annual salary of the Governor, are you and your spouse or minor children entitled to receive (i) more than 15 % in the aggregate of the total distributable income of your firm, partnership, association or corporation, or (ii) an amount in excess of 2 times the salary of the Governor? Yes No
(c)	unit of	ve status; the holding of elective office of the State of Illinois, the government of the United States, any f local government authorized by the Constitution of the State of Illinois or the statutes of the State of currently or in the previous 3 years. Yes No
(d)		onship to anyone holding elective office currently or in the previous 2 years; spouse, father, mother, or daughter. Yes No
(e)	Ameri of the	ntive office; the holding of any appointive government office of the State of Illinois, the United States of ca, or any unit of local government authorized by the Constitution of the State of Illinois or the statutes State of Illinois, which office entitles the holder to compensation in excess of the expenses incurred in scharge of that office currently or in the previous 3 years. Yes No
(f)		onship to anyone holding appointive office currently or in the previous 2 years; spouse, father, mother, or daughter. Yes No

(g)	Employment, currently or in the previous 3 years, as or by any registered lobbyist of the State government. Yes No
(h)	Relationship to anyone who is or was a registered lobbyist in the previous 2 years; spouse, father, mother, son, or daughter. Yes No
(i)	Compensated employment, currently or in the previous 3 years, by any registered election or reelection committee registered with the Secretary of State or any county clerk of the State of Illinois, or any political action committee registered with either the Secretary of State or the Federal Board of Elections. Yes No
(j)	Relationship to anyone; spouse, father, mother, son, or daughter; who was a compensated employee in the last 2 years by any registered election or re-election committee registered with the Secretary of State or any county clerk of the State of Illinois, or any political action committee registered with either the Secretary of State or the Federal Board of Elections. Yes No
3.	Communication Disclosure.
this bid	sclose the name and address of each lobbyist and other agent of the bidder or offeror who is not identified in Section 2 of s form, who has communicated, is communicating, or may communicate with any State officer or employee concerning the or offer. This disclosure is a continuing obligation and must be promptly supplemented for accuracy throughout the cess and throughout the term of the contract. If no person is identified, enter "None" on the line below:
٨	Name and address of person(s):
_	
pro con	following has occurred within the previous 10 years: debarment from contracting with any governmental entity; if essional licensure discipline; bankruptcies; adverse civil judgments and administrative findings; and criminal felony exictions. This disclosure is a continuing obligation and must be promptly supplemented for accuracy throughout the ecurement process and term of the contract. If no person is identified, enter "None" on the line below: Name of person(s): Nature of disclosure:
	APPLICABLE STATEMENT
pe	is Disclosure Form A is submitted on behalf of the INDIVIDUAL named on previous page. Under nalty of perjury, I certify the contents of this disclosure to be true and accurate to the best of my owledge.
C	ompleted by:
	Signature of Individual or Authorized Officer Date
	NOT APPLICABLE STATEMENT Ider penalty of perjury, I have determined that no individuals associated with this organization meet excriteria that would require the completion of this Form A.
Th	is Disclosure Form A is submitted on behalf of the SUBCONTRACTOR listed on the previous page.
	Signature of Authorized Officer Date

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form B Subcontractor: Other Contracts & Procurement Related Information Disclosure

Subcontractor Name			
Legal Address			
City, State, Zip			
Telephone Number	Email Address	Fax Number (if available)	
Disclosure of the information contained in this Form is required by the Section 50-35 of the Illinois Procurement Act (30 ILCS 500). This information shall become part of the publicly available contract file. This Form B must be completed for subcontracts with a total value of \$25,000 or more, from subcontractors identified in Section 20-120 of the Illinois Procurement Code,, and for all open-ended contracts.			
DISCLOSURE OF OTHER CONTRACTS,	SUBCONTRACTS, AND PROCUR	EMENT RELATED INFORMATION	
1. Identifying Other Contracts & Proc whether it has any pending contracts, s procurement relationship with any other Sta	subcontracts, including leases, b		
If "No" is checked, the subcontractor only	needs to complete the signature bo	x on the bottom of this page.	
2. If "Yes" is checked. Identify each su descriptive information such as bid or DISCLOSURE FORM INSTRUCTIONS:			
THE FOLLOWING STATEMENT MUST BE CHECKED			
5	Signature of Authorized Officer	Date	

ILLINOIS DEPARTMENT OF TRANSPORTATION

DIVISION OF AERONAUTICS

FEDERAL CONTRACT PROVISIONS

The work in this contract is included in the federal FAA Airport Improvement Program and is being undertaken and accomplished by the Illinois Department of Transportation, Division of Aeronautics and the Municipality, hereinafter called the Co-Sponsors, in accordance with the terms and conditions of a Grant Agreement between the Co-Sponsors and the United States, under the Airport and Airway Improvement Act of 1982 (Public Law 97-248; Title V, Section 501 et seq., September 3, 1982; 96 Stat. 671; codified at 49 U.S.C Section 2201 et seq.) and Part 152 of the Federal Aviation Regulations (14 CFR Part 152), pursuant to which the United States has agreed to pay a certain percentage of the costs of the Project that are determined to be allowable Project costs under the Act. The United States is not a party to this contract and no reference in this contract to FAA or representative thereof, or to any rights granted to the FAA or any representative thereof, or the United States, by the contract, makes the United States a party to this contract.

Consent of Assignment. The Contractor shall obtain the prior written consent of the Co-Sponsors to any proposed assignment of any interest in or part of this contract.

AIRPORT AND AIRWAY IMPROVEMENT ACT OF 1982, SECTION 520 - GENERAL CIVIL RIGHTS PROVISIONS

The contractor assures that it will comply with pertinent statutes, Executive orders and such rules as are promulgated to assure that no person shall, on the grounds of race, creed, color, national origin, sex, age, or handicap be excluded from participating in any activity conducted with or benefiting from Federal assistance. This provision obligates the tenant/concessionaire/lessee or its transferee for the period during which Federal assistance is extended to the airport a program, except where Federal assistance is to provide, or is in the form of personal property or real property or interest therein or structures or improvements thereon. In these cases the provision obligates the party or any transferee for the longer of the following periods: (a) the period during which the property is used by the airport sponsor or any transferee for a purpose for which Federal assistance is extended, or for another purpose involving the provision of similar services or benefits or (b) the period during which the airport sponsor or any transferee retains ownership or possession of the property. In the case of contractors, this provision binds the contractors from the bid solicitation period through the completion of the contract. This provision is in addition to that required of Title VI of the Civil Rights Act of 1964.

LOBBYING AND INFLUENCING FEDERAL EMPLOYEES

The undersigned bidder certifies, to the best of his or her knowledge and belief, that:

- (1) No Federal appropriated funds have paid or will be paid, by or behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an Officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- (2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying", in accordance with its instructions.
- (3) The undersigned shall require that the language of this certification be included in the award documents for all subawards at all tiers (including subcontracts, subgrants, and contracts under grants, loans, and cooperative agreements) and that all subrecipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by Section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

TRADE RESTRICTION CLAUSE

The Contractor or subcontractor, by submission of an offer and/or execution of a contract, certifies that it:

- a. is not owned or controlled by one or more citizens or nationals of a foreign country included in the list of countries that discriminate against U.S. firms published by the Office of the United States Trade Representative (USTR);
- b. has not knowingly entered into any contract or subcontract for this project with a Contractor that is a citizen or national of a foreign country on said list, or is owned or controlled directly or indirectly by one or more citizens or nationals of a foreign country on said list.
- c. has not procured any product nor subcontracted for the supply of any product for use on the project that is produced in a foreign country on said list.

Unless the restrictions of this clause are waived by the Secretary of Transportation in accordance with 49 CFR 30.17, no contract shall be awarded to a Contractor or subcontractor who is unable to certify to the above. If the Contractor knowingly procures or subcontracts for the supply of any product or service of a foreign country on the said list for use on the project, the Federal Aviation Administration may direct, through the sponsor, cancellation of the contract at no cost to the Government.

Further, the Contractor agrees that, if awarded a contract resulting from this solicitation, it will incorporate this provision for certification without modification in each contract and in all lower tier subcontracts. The Contractor may rely upon the certification of a prospective subcontractor unless it has knowledge that the certification is erroneous.

The Contractor shall provide immediate written notice to the sponsor if the Contractor learns that its certification or that of a subcontractor was erroneous when submitted or has become erroneous by reason of changed circumstances. The subcontractor agrees to provide immediate written notice to the Contractor, if at any time it learns that its certification was erroneous by reason of changed circumstances.

This certification is a material representation of fact upon which reliance was placed when making the award. If it is later determined that the Contractor or subcontractor knowingly rendered an erroneous certification, the Federal Aviation Administration may direct, through this sponsor, cancellation of the contract or subcontract for default at no cost to the Government.

Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by this provision. The knowledge and information of a Contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

This certification concerns a matter within the jurisdiction of an agency of the United States of America and the making of false, fictitious, or fraudulent certification may render the maker subject to prosecution under Title 18, United States Code, Section 1001.

CERTIFICATION OF NONSEGREGATED FACILITIES - 41 CFR PART 60-1.8

The federally-assisted construction contractor certifies that she or he does not maintain or provide, for his employees, any segregated facilities at any of his establishments and that she or he does not permit his employees to perform their services at any location, under his control, where segregated facilities are maintained. The federally-assisted construction contractor certifies that she or he will not maintain or provide, for his employees, segregated facilities at any of his establishments and that she or he will not permit his employees to perform their services at any location under his control where segregated facilities are maintained. The federally-assisted construction contractor agrees that a breach of this certification is a violation of the Equal Opportunity Clause in this contract.

As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms, and washrooms, restaurants and other eating areas, timeclocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directives or are, in fact, segregated on the basis of race, color, religion, or national origin because of habit, local custom, or any other reason. The federally-assisted construction contractor agrees that (except where she or he has obtained identical certifications from proposed subcontractors for specific time periods) she or he will obtain identical certifications from proposed subcontractors prior to the award of subcontracts exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity Clause and that she or he will retain such certifications in his files.

VETERAN'S PREFERENCE

In the employment of labor (except in executive, administrative, and supervisory positions), preference shall be given to Veterans of the Vietnam era and disabled veterans as defined in Section 515(c)(1) and (2) of the Airport and Airway Improvement Act of 1982. However, this preference shall apply only where the individuals are available and qualified to perform the work to which the employment relates.

ACCESS TO RECORDS AND REPORTS

The Contractor shall maintain an acceptable cost accounting system. The Sponsor, the FAA, and the Comptroller General of the United States shall have access to any books, documents, paper, and records of the Contractor which are directly pertinent to the specific contract for the purposes of making an audit, examination, excerpts, and transcriptions. The Contractor shall maintain all required records for https://example.com/thee-years after the Sponsor makes final payment and all other pending matters are closed.

RIGHTS TO INVENTIONS

All rights to inventions and materials generated under this contract are subject to Illinois law and to regulations issued by the FAA and the Sponsor of the Federal grant under which this contract is executed.

ENERGY CONSERVATION REQUIREMENTS

The contractor agrees to comply with mandatory standards and policies relating to energy efficiency that are contained in the state energy conservation plan issued in compliance with the Energy Policy and Conservation Act (Public Law 94-163)

CLEAN AIR AND WATER POLLUTION CONTROL

In connection with the administration of the Clean Air Act and the Water Pollution Control Act with respect to Federal Grants, specific requirements have been imposed of any contract which is not exempt under the provisions of 40 CFR 15.5.

- (1) Any facility listed on the EPA List of Violating Facilities pursuant to Paragraph 15.20 of 40 CFR as of the date of the contract award will not be utilized in the performance of any non-exempt contract or subcontract.
- (2) The Contractor shall comply with all the requirements of Section 114 of the Clean Air Act, as amended, 42 USC 1857 et seq. and Section 308 of the Federal Water Pollution Control Act, as amended, 33 USC 1251 et seq. relating to inspection, monitoring, entry, reports and information, as well as all other requirements specified in Section 114 and Section 308 of the Air Act and Water Act, respectively, and all regulations and guidelines issued thereunder after the award of the contract.
- (3) Prompt notification shall be required prior to contract award to the awarding official by the Contractor who will receive the award of the receipt of any communication from the Director, Office of Federal Activities, U.S. Environmental Protection Agency, indicating that a facility to be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
- (4) The Contractor shall include or cause to be included the criteria and requirements in paragraphs 1 through 4 in any non-exempt subcontract and will take such action as the Government may direct as a means of enforcing such provisions.

NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION

- 1. The Offeror's or Bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth herein.
- 2. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

APPENDIX A

The following goal for female utilization in each construction craft and trade shall apply to all Contractors holding Federal and federally assisted construction contracts and subcontracts in excess of \$10,000. The goal is applicable to the Contractor's total on-site construction workforce, regardless of whether or not part of that workforce is performing work on a Federal, federally assisted or nonfederally related construction contact or subcontract.

AREA COVERED (STATEWIDE)

Goals for Women apply nationwide.

GOAL

	Goal (percent)
Female Utilization	6.9

APPENDIX B

Until further notice, the following goals for minority utilization in each construction craft and trade shall apply to all Contractors holding Federal and federally-assisted construction contracts and subcontracts in excess of \$10,000. to be performed in the respective geographical areas. The goals are applicable to the Contractor's total on-site construction workforce, regardless of whether or not part of that workforce is performing work on a Federal, federally-assisted or nonfederally related construction contract or subcontract.

Economic Area	Goal (percent)
056 Paducah, KY: Non-SMSA Counties - IL - Hardin, Massac, Pope KY - Ballard, Caldwell, Calloway, Carlisle, Crittenden, Fulton, Graves, Hickman, Livingston, Lyon, McCracken, Marshall	5.2
080 Evansville, IN: Non-SMSA Counties - IL - Edwards, Gallatin, Hamilton, Lawrence, Saline, Wabash, White IN - Dubois, Knox, Perry, Pike, Spencer KY - Hancock, Hopkins, McLean, Mublenberg, Ohio, Union, Webster	3.5
081 Terre Haute, IN: Non-SMSA Counties - IL - Clark, Crawford IN - Parke	2.5
083 Chicago, IL: SMSA Counties: 1600 Chicago, IL - IL - Cook, DuPage, Kane, Lake, McHenry, Will	19.6
3740 Kankakee, IL - IL - Kankakee	9.1
Non-SMSA Counties IL - Bureau, DeKalb, Grundy, Iroquois, Kendall, LaSalle, Livingston, Putnam IN - Jasper, Laporte, Newton, Pulaski, Starke	18.4

APPENDIX B (CONTINUED)

Economic Area	Goal (percent)
084 Champaign - Urbana, IL: SMSA Counties: 1400 Champaign - Urbana - Rantoul, IL - IL - Champaign	7.8
Non-SMSA Counties - IL - Coles, Cumberland, Douglas, Edgar, Ford, Piatt, Vermilion	4.8
085 Springfield - Decatur, IL: SMSA Counties: 2040 Decatur, IL - IL - Macon	7.6
7880 Springfield, IL - IL - Mendard, Sangamon	4.5
Non-SMSA Counties IL - Cass, Christian, Dewitt, Logan, Morgan, Moultrie, Scott, Shelby	4.0
086 Quincy, IL: Non-SMSA Counties	3.1
IL - Adams, Brown, Pike MO - Lewis, Marion, Pike, Ralls	
087 Peoria, IL: SMSA Counties: 1040 Bloomington - Normal, IL - IL - McLean	2.5
6120 Peoria, IL - IL - Peoria, Tazewell, Woodford	4.4
Non-SMSA Counties - IL - Fulton, Knox, McDonough, Marshall, Mason, Schuyler, Stark, Warren	3.3
088 Rockford, IL: SMSA Counties: 6880 Rockford, IL - IL - Boone, Winnebago	6.3
Non-SMSA Counties - IL - Lee, Ogle, Stephenson	4.6
098 Dubuque, IA: Non-SMSA Counties - IL - JoDaviess IA - Atlamakee, Clayton, Delaware, Jackson, Winnesheik WI - Crawford, Grant, Lafayette	0.5
099 Davenport, Rock Island, Moline, IA - IL: SMSA Counties: 1960 Davenport, Rock Island, Moline, IA - IL - IL - Henry, Rock Island IA - Scott	4.6
Non-SMSA Counties - IL - Carroll, Hancock, Henderson, Mercer, Whiteside IA - Clinton, DesMoines, Henry, Lee, Louisa, Muscatine MO - Clark	3.4

APPENDIX B (CONTINUED)

Economic Area	Goal (percent)
107 St. Louis, MO: SMSA Counties: 7040 St. Louis, MO - IL - IL - Clinton, Madison, Monroe, St. Clair MO - Franklin, Jefferson, St. Charles, St. Louis, St. Louis City	14.7
 Non-SMSA Counties - IL - Alexander, Bond, Calhoun, Clay, Effingham, Fayette, Franklin, Greene, Jackson, Jasper, Jefferson, Jersey, Johnson, Macoupin, Marion, Montgomery, Perry, Pulaski, Randolph, Richland, Union, Washington, Wayne, Williamson MO - Bollinger, Butler, Cape Girardeau, Carter, Crawford, Dent, Gasconade, Iron, Lincoln, Madison, Maries, Mississippi, Montgomery, Perry, Phelps, Reynolds, Ripley, St. Francois, St. Genevieve, Scott, Stoddard, Warren, Washington, Wayne 	11.4

These goals are applicable to all the Contractor's construction work (whether or not it is Federal or federally assisted) performed in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the Contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The Contractor's compliance with Executive Order and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the provisions and specifications set forth in its federally assisted contracts, and its efforts to meet the goals established for the geographical area where the contract resulting from this solicitation is to be performed. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, the Executive Order and the regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

- 3. The Illinois Division of Aeronautics will provide written notification to the Director of the Office of Federal Contract Compliance Programs within 10 working days of award of any construction contract and/or subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. This notification will list the name, address and telephone number of the subcontractor; employer identification number; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the contract is to be performed.
- 4. As used in this Notice, and in the contract resulting from this solicitation, the "covered area" is the entire State of Illinois for the goal set forth in APPENDIX A and the county or counties in which the work is located for the goals set forth in APPENDIX B.

DISADVANTAGED BUSINESS POLICY

NOTICE: This proposal contains the special provision entitled "Required Disadvantaged Business Participation." Inclusion of this Special Provision in this contract satisfies the obligations of the Department of Transportation under federal law as implemented by 49 CFR 23 and under the Illinois "Minority and Female Business Enterprise Act."

<u>POLICY</u>: It is public policy that the businesses defined in 49 CFR Part 23 shall have the maximum opportunity to participate in the performance of contracts financed in whole or in part with State or Federal funds. Consequently, the requirements of 49 CFR Part 23 apply to this contract.

<u>OBLIGATION</u>: The Contractor agrees to ensure that the businesses defined in 49 CFR Part 23 have the maximum opportunity to participate in the performance of this contract. In this regard, the Contractor shall take all necessary and reasonable steps, in accordance with 49 CFR Part 23, to ensure that the said businesses have the maximum opportunity to compete for and perform portions of this contract. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the selection and retention of subcontractors, including procurement of materials and leases of equipment.

The Contractor shall include the above Policy and Obligation statements of this Special Provision in every subcontract, including procurement of materials and leases of equipment.

<u>DBE/WBE CONTRACTOR FINANCE PROGRAM:</u> On contracts where a loan has been obtained through the DBE/WBE Contractor Finance Program, the Contractor shall cooperate with the Department by making all payments due to the DBE/WBE Contractor by means of a two-payee check payable to the Lender (Bank) and the Borrower (DBE/WBE Contractor).

<u>BREACH OF CONTRACT:</u> Failure to carry out the requirements set forth above and in the Special Provision shall constitute a breach of contract and may result in termination of the contract or liquidated damages as provided in the special provision.

DISADVANTAGED BUSINESS ENTERPRISES

Contract Assurance (§26.13) - The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy, as the recipient deems appropriate.

CIVIL RIGHTS ACT OF 1964, TITLE VI - CONTRACTOR CONTRACTUAL REQUIREMENTS

During the performance of this contract, the contractor, for itself, its assignees and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

- 1.1 Compliance with Regulations. The contractor shall comply with the Regulations relative to nondiscrimination in federally assisted programs of the Department of Transportation (hereinafter, "DOT") Title 49, Code of Federal Regulations, Part 21, as they may be amended from time to time (hereinafter referred to as the Regulations), which are herein incorporated by reference and made a part of this contract.
- 1.2 Nondiscrimination. The contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor shall not participate either directly or indirectly in the discrimination prohibited by section 21.5 of the Regulations, including employment practices when the contract covers a program set forth in Appendix B of the Regulations.
- 1.3 Solicitations for Subcontracts, Including Procurements of Materials and Equipment. In all solicitations either by competitive bidding or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials or leases of equipment, each potential subcontractor or supplier shall be notified by the contractor of the contractor's obligations under this contract and the Regulations relative to nondiscrimination on the grounds of race, color, or national origin.
- 1.4 Information and Reports. The contractor shall provide all information and reports required by the Regulations or directives issued pursuant thereto and shall permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Sponsor or the Federal Aviation Administration (FAA) to be pertinent to ascertain compliance with such Regulations, orders, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish this information, the contractor shall so certify to the sponsor or the FAA, as appropriate, and shall set forth what efforts it has made to obtain the information.
- 1.5 Sanctions for Noncompliance. In the event of the contractor's noncompliance with the nondiscrimination provisions of this contract, the sponsor shall impose such contract sanctions as it or the FAA may determine to be appropriate, including, but not limited to:
 - a. Withholding of payments to the contractor under the contract until the contractor complies, and/or
 - b. Cancellation, termination, or suspension of the contract, in whole or in part.
- 1.6 Incorporation of Provisions. The contractor shall include the provisions of paragraphs 1 through 5 in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Regulations or directives issued pursuant thereto. The contractor shall take such action with respect to any subcontract or procurement as the sponsor or the FAA may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, however, that in the event a contractor becomes involved in, or is threatened with, litigation with a subcontractor or supplier as a result of such direction, the contractor may request the Sponsor to enter into such litigation to protect the interests of the sponsor and, in addition, the contractor may request the United States to enter into such litigation to protect the interests of the United States.

DAVIS BACON LABOR PROVISIONS

- (1) Minimum Wages.
 - (i) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR Part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provision of paragraph (a)(1)(iv) of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraph 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: *Provided*, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph (a)(1)(ii) of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

- (ii)(A) The contracting officer shall require that any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:
 - (1)The work to be performed by the classification requested is not performed by a classification in the wage determination; and
 - (2) The classification is utilized in the area by the construction industry; and
 - (3) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
- (B) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, D.C. 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (C) In the event the Contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (D) The wage rate (including fringe benefits where appropriate) determined pursuant to subparagraphs (1)(ii) (B) or (C) of this paragraph, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- (iii) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the Contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- (iv) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, *Provided*, That the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

(2) Withholding.

The Federal Aviation Administration shall upon its own action or written request of an authorized representative of the Department of Labor withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same prime Contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime Contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the (Agency) may, after written notice to the Contractor, sponsor, applicant, or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

(3) Payrolls and basic records.

- (i) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such work, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the Contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.
- (ii)(A) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Federal Aviation Administration if the agency is a party to the contract, but if the agency is not such a party, the Contractor will submit the payrolls to the applicant, sponsor, or owner, as the case may be, for transmission to the Federal Aviation Administration. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under paragraph 5.5(a)(3)(i) of Regulations, 29 CFR Part 5. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal Stock Number 029-005-00014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime Contractor is responsible for the submission of copies of payrolls by all subcontractors.
- (B) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor, or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
 - (1) That the payroll for the payroll period contains the information required to be maintained under paragraph (3)(i) above and that such information is correct and complete;
 - (2) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR Part 3;
 - (3) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed as specified in the applicable wage determination incorporated into the contract.
- (C) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph (3)(ii)(B) of this section.
- (D) The falsification of any of the above certifications may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 231 of Title 31 of the United States Code.
- (iii) The Contractor or subcontractor shall make the records required under paragraph (3)(i) of this section available for inspection, copying, or transcription by authorized representatives of the (write the name of the agency) or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit the required records or to make them available, the Federal agency may, after written

notice to the Contractor, sponsor, applicant, or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

(4) Apprentices and Trainees

- (i) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State Apprenticeship Agency recognized by the Bureau, or if a person is employed in his or her first 90 days of probationary employment as a apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the Contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a Contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Bureau of Apprenticeship and Training, or a State Apprenticeship Agency recognized by the Bureau, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.
- (ii) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ration permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the contract will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.
- (iii) Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.
- (5) Compliance with Copeland Act Requirements.

The Contractor shall comply with the requirements of 29 CFR Part 3, which are incorporated by reference in this contract.

(6) Subcontracts.

The Contractor or subcontractor shall insert in any subcontracts the clauses contained in 29 CFR Part 5.5(a)(1) through (10) and such other clauses as the Federal Aviation Administration may by appropriate instructions require, and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime Contractor shall be responsible for the compliance by an subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR Part 5.5.

(7) Contract Termination: Debarment.

A breach of these contract clauses paragraphs (1) through (10) of this section may be grounds for termination of the contract and for debarment as a Contractor and a subcontractor as provided in 29 CFR Part 5.12.

(8) Compliance with Davis-Bacon and Related Act Requirements.

All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are herein incorporated by referenced in this contract.

(9) Disputes Concerning Labor Standards.

Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR Parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

(10) Certification of Eligibility.

- (i) By entering into this contract, the Contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the Contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- (ii) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
 - (iii) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

CONTRACT WORKHOURS AND SAFETY STANDARDS ACT REQUIREMENTS

(1) Overtime requirements:

No Contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen or guards (including apprentices and trainees described in paragraphs 5 and 6 above) shall require or permit any laborer, mechanic, watchman or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman or guard receives compensation at a rate not less than one and one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

(2) Violations: Liability for Unpaid Wages; Liquidated Damages:

In the event of any violation of the clause set forth in paragraph (1) above, the Contractor and any subcontractor responsible therefore shall be liable for the unpaid wages. In addition, such Contractor and subcontractor shall be liable to the United States (in case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1) above, in the sum of \$10.00 for each calendar day on which such employee was required or permitted to work in excess of the standard workweek of 40 hours without payment of the overtime wages required by the clause set forth in paragraph (1) above.

(3) Withholding for Unpaid Wages and Liquidated Damages.

The Federal Aviation Administration or the Sponsor shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the Contractor or subcontractor under any such contract or any other Federal contract with the same prime Contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime Contractor, such sums as may be determined to be necessary to satisfy any liabilities of such Contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2) above.

(4) Subcontracts.

The Contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1) through (4) and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime Contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1) through (4) of this section.

(5) Working Conditions.

No Contractor or subcontractor may require any laborer or mechanic employed in the performance of any contract to work in surroundings or under working conditions that are unsanitary, hazardous, or dangerous to his health or safety as determined under construction safety and health standards (29 CFR 1926) issued by Department of Labor.

EQUAL EMPLOYMENT OPPORTUNITY - 41 CFR PART 60-1.4(b)

During the performance of this contract, the contractor agrees as follows:

- 1. The contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. The contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex, or national origin. Such action shall include, but not be limited to the following: Employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- 2. The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive considerations for employment without regard to race, color, religion, sex, or national origin.
- 3. The contractor will send to each labor union or representative of workers with which s/he has a collective bargaining agreement or other contract or understanding, a notice to be provided advising the said labor union or workers' representatives of the contractor's commitments under this section, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- 4. The contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, as amended, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- 5. The contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the administering agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- 6. In the event of the contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations, or orders, this contract may be canceled, terminated or suspended in whole or in part and the contractor may be declared ineligible for further Government contracts or federally assisted construction contracts in accordance with procedure authorized in Executive Order 11246 of September 24, 1965, and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law.
- 7. The contractor will include the portion of the sentence immediately preceding paragraph (1) and the provisions of paragraphs (1) through (7) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to section 204 of Executive Order 11246 of September 24, 1965, so that such provisions will be binding upon each subcontractor or vendor. The contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as a means of enforcing such provision, including sanctions for noncompliance: *Provided, however,* that in the event a contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of such direction by the administering agency the contractor may request the United States to enter into such litigation to protect the interests of the United States.

EQUAL EMPLOYMENT OPPORTUNITY SPECIFICATION

- 1. As used in these specifications:
 - a) "Covered area" means the geographical area described in the solicitation from which this contract resulted;
 - b) "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority;
 - "Employer identification number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941;
 - d) "Minority" includes:
 - (i) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);
 - (ii) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American or other Spanish Culture or origin, regardless of race);

- (iii) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and
- (iv) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).
- Whenever the Contractor, or any Subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000. the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitations from which this contract resulted.
- 3. If the Contractor is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or Subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractors or Subcontractors toward a goal in an approved Plan does not excuse any covered Contractor's or Subcontractor's failure to take good faith efforts to achieve the Plan goals and timetables.
- 4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through p of these specifications. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. Covered Construction Contractors performing construction work in geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical area where the work is being performed. Goals are published periodically in the Federal Register in notice form, and such notices may be obtained from any Office of Federal Contract Compliance Programs office or from Federal procurement contracting officers. The Contractor is expected to make substantially uniform progress toward its goals in each craft during the period specified.
- 5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.
- 6. In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.
- 7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:
 - a) Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working as such sites or in such facilities.
 - b) Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.
 - c) Maintain a current file of the names, addresses and telephone numbers of each minority and female off-thestreet applicant and minority or female referral from a union, a recruitment source or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefor, along with whatever additional actions the Contractors may have taken.
 - d) Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the

Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

- e) Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.
- f) Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreements; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.
- g) Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination or other employment decisions including specific review of these items with onsite supervisory personnel such as Superintendents, General Foreman, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
- h) Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractors and Subcontractors with whom the Contractor does or anticipates doing business.
- i) Direct its recruitment efforts, both oral and written, to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship of other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.
- j) Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer and vacation employment to minority and female youth both on the site and in other areas of a Contractor's workforce.
- k) Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.
- Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.
- m) Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
- n) Ensure that all facilities and company activities are nonsegregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
- Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction Contractors and suppliers, including circulation of solicitations to minority and female Contractor associations and other business associations.
- p) Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligations.
- 8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through p). The efforts of a Contractor association, joint Contractor-union, Contractor-community, or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under 7a through p of these Specifications provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female workforce participation makes a good faith effort to meet its individual goals

and timetables, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

- 9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specified minority group of women is underutilized).
- 10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.
- 11. The Contractor shall not enter into any Subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.
- 12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termination and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.
- 13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.8.
- 14. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the Government and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy his requirement, Contractors shall not be required to maintain separate records.
- 15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

ANNUAL EEO-1 REPORT TO JOINT REPORTING COMMITTEE AS REQUIRED AT 41 CFR 60-1.7(a)

Any Contractor having a Federal contract of \$50,000 or more and 50 or more employees is required to file annual compliance reports on Standard Form 100 (EEO-1) with the Joint Reporting Committee in accordance with the instructions provided with the form. The Contractor will provide a copy of such a report to the contracting agency within 30 days after the award of a contract.

The Contractor shall require its subcontractors to file an SF 100 within 30 days after award of the subcontract if (1) it is not exempt from the provisions of these regulations in accordance with 60-1.5, (2) has 50 or more employees, (3) first tier subcontractor, and (4) has a subcontract amounting to \$50,000 or more.

Subcontractors below the first tier which perform construction work at the site of construction shall be required to file such a report if (1) it is not exempt from the provisions of these regulations in accordance with 60-1.5, (2) has 50 or more employees and has a subcontract amounting to \$50,000 or more.

The SF 100 is available at the following address:

Joint Reports Committee EEOC - Survey Division 1801 "L" Street N.W. Washington, D.C. 20750

Phone (202) 663-4968

CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION - Title 49 CFR Part 29

Instructions for Certification

- 1. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- 4. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if at any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction" "debarred" "suspended" "ineligible" "lower tier covered transaction" "participant" "person" "primary covered transaction" "principal" "proposal" and "voluntarily excluded" as used in this clause have the meaning set out in the Definitions and Coverage sections of the rules implementing Executive Order 12540. You may contact the department or agency to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective primary participant agrees by submitting this proposal that should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction unless authorized by the department or agency entering into this transaction.
- 7. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion Lower Tier Transaction", provided by the department or agency entering into this covered transaction without modification in all lower covered transactions and in all solicitations for lower covered transactions.
- 8. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to check the Nonprocurement List (Tel. #).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 8 of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion Primary Covered Transactions

- 1. The prospective primary participant certifies to the best of its knowledge and belief that it and its principals:
 - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by an Federal department or agency;
 - b. Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain or performing a public (Federal, State or Local) transaction or contract under a public transaction: violation of Federal or

State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction or destruction of records, making false statements, or receiving stolen property;

- c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (1)(b) of this certification; and
- d. Have not within a three-period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- 2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

EACH PRIME CONTRACTOR SHALL INSERT IN EACH SUBCONTRACT THE CERTIFICATION IN APPENDIX B, AND FURTHER, SHALL REQUIRE ITS INCLUSION IN ANY LOWER TIER SUBCONTRACT, PURCHASE ORDER, OR TRANSACTION THAT MAY IN TURN BE MADE.

Appendix B of 49 CFR Part 29

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions

This certification applies to subcontractors, material suppliers, vendors and other lower tier participants.

Instructions for Certification

- 1. By signing and submitting this proposal, the prospective lower tier participant is providing the certification set out below.
- 2. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- 3. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 4. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction, "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- 5. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- 6. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- 7. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- 8. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 9. Except for transactions authorized under paragraph 5 of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal

Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

<u>Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion</u> Lower Tier Covered Transactions

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

MINIMUM WAGES FOR FEDERAL AND FEDERALLY ASSISTED CONSTRUCTION CONTRACTS

This project is funded, in part, with Federal-aid funds and, as such, is subject to the provisions of the Davis-Bacon Act of March 3, 1931, as amended (46 Sta. 1494, as amended, 40 U.S.C. 276a) and of other Federal statutes referred to in a 29 CFR Part 1, Appendix A, as well as such additional statutes as may from time to time be enacted containing provisions for the payment of wages determined to be prevailing by the Secretary of Labor in accordance with the Davis-Bacon Act and pursuant to the provisions of 29 CFR Part 1. The prevailing rates and fringe benefits shown in the General Wage Determination Decisions issued by the U.S. Department of Labor shall, in accordance with the provisions of the foregoing statutes, constitute the minimum wages payable on Federal and federally assisted construction projects to laborers and mechanics of the specified classes engaged on contract work of the character and in the localities described therein.

General Wage Determination Decisions, modifications and supersedes decisions thereto are to be used in accordance with the provisions of 29 CFR Parts 1 and 5. Accordingly, the applicable decision, together with any modifications issued, must be made a part of every contract for performance of the described work within the geographic area indicated as required by an applicable DBRA Federal prevailing wage law and 29 CFR Part 5. The wage rates and fringe benefits contained in the General Wage Determination Decision shall be the minimum paid by contractors and subcontractors to laborers and mechanics.

NOTICE

The most current **General Wage Determination Decisions** (wage rates) are available on the IDOT web site. They are located on the Letting and Bidding page at http://www.dot.state.il.us/desenv/delett.html.

In addition, ten (10) days prior to the letting, the applicable Federal wage rates will be e-mailed to subscribers. It is recommended that all contractors subscribe to the Federal Wage Rates List or the Contractor's Packet through IDOT's subscription service.

PLEASE NOTE: if you have already subscribed to the Contractor's Packet you will automatically receive the Federal Wage Rates.

The instructions for subscribing are at http://www.dot.state.il.us/desenv/subsc.html.

If you have any questions concerning the wage rates, please contact IDOT's Chief Contract Official at 217-782-7806.

ILLINOIS DEPARTMENT OF TRANSPORTATION

DIVISION OF AERONAUTICS

STATE REQUIRED CONTRACT PROVISIONS

The following provisions are State of Illinois requirements and are in addition to the Federal requirements contained in the FAA Airport Improvement Program.

SPECIAL PROVISION FOR DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION

Effective: September 1, 2000 Revised: January 1, 2010

<u>FEDERAL OBLIGATION:</u> The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR part 26 and listed in the Illinois Unified Certification Program (IL UCP) DBE Directory

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

<u>CONTRACTOR ASSURANCE:</u> The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor:

The Contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

OVERALL GOAL SET FOR THE DEPARTMENT: As a requirement of compliance with 49 CFR part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE companies performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR: This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. This determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates that, in the absence of unlawful discrimination, and in an arena of fair and open competition, DBE companies can be expected to perform 3.7% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will only award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for award consideration if either of the following is done in accordance with the procedures set forth in this Special Provision:

- (a) The bidder documents that enough DBE participation has been obtained to meet the goal; or
- (b) The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

<u>DBE LOCATOR REFERENCES:</u> Bidders may consult the IL UCP DBE Directory as a reference source for DBE-certified companies. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning

DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217)785-4611, or by visiting the Department's web site at www.dot.il.gov.

<u>BIDDING PROCEDURES.</u> Compliance with this Special Provision is a material bidding requirement. The failure of the bidder to comply will render the bid not responsive.

- (a) The bidder shall submit a Disadvantaged Business Utilization Plan on Department forms SBE 2025 and 2026 with the bid.
- (b) The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number and telefax number of a responsible official of the bidder designated for purposes of notification of plan approval or disapproval under the procedures of this Special Provision.
- (c) The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. For bidding purposes, submission of the completed SBE 2025 forms, signed by the DBEs and faxed to the bidder will be acceptable as long as the original is available and provided upon request. All elements of information indicated on the said form shall be provided, including but not limited to the following:
 - (1) The name and address of DBE firms that will participate in the contract;
 - (2) A description, including pay item numbers, of the work each DBE will perform;
 - (3) The dollar amount of the participation of each DBE firm participating. The dollar amount of participation for identified work shall specifically state the quantity, unit price and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
 - (4) DBE Participation Commitment Statements, form SBE 2025, signed by the bidder and each participating DBE firm documenting the commitment to use the DBE subcontractors whose participation is submitted to meet the contract goal;
 - (5) If the bidder is a joint venture comprised of DBE companies and non-DBE companies, the plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s); and,
 - (6) If the contract goal is not met, evidence of good faith efforts.

GOOD FAITH EFFORT PROCEDURE. The contract will not be awarded until the Utilization Plan submitted by the apparent successful bidder is approved. All information submitted by the bidder must be complete, accurate and adequately document that enough DBE participation has been obtained or document the good faith efforts of the bidder, in the event enough DBE participation has not been obtained, before the Department will commit to the performance of the contract by the bidder. The Utilization Plan will be approved by the Department if the Utilization Plan commits sufficient commercially useful DBE work performance to meet the contract goal or the bidder submits sufficient documentation of a good faith effort to meet the contract goal pursuant to 49 CFR part 26, Appendix A.

The Utilization Plan will not be approved by the Department if the Utilization Plan does not commit sufficient DBE participation to meet the contract goal unless the apparent successful bidder documented in the Utilization Plan that it made a good faith effort to meet the goal. This means that the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which, by their scope, intensity and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not successful. The Department will consider the quality, quantity, and intensity of the kinds of efforts that the bidder has made. Mere *pro forma* efforts, in other words, efforts done as a matter of form, are not good faith efforts; rather, the bidder is expected to have taken genuine efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

- (a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.
 - (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.

- (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime Contractor might otherwise prefer to perform these work items with its own forces.
- (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
- (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
 - b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable.

Also, the ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable.

- (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.
- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- (b) If the Department determines that the apparent successful bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that the bidder has failed to meet the requirements of this Special Provision and that a good faith effort has not been made, the Department will notify the responsible company official designated in the Utilization Plan that the bid is not responsive. The notification shall include a statement of reasons why good faith efforts have not been found.
- (c) The bidder may request administrative reconsideration of a determination adverse to the bidder within the five working days after receipt of the notification date of the determination by delivering the request to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The determination shall become final if a request is not made and delivered. A request may provide additional written documentation and/or argument concerning the issues raised in the determination statement of reasons, provided the documentation and arguments address efforts made prior to submitting the bid. The request will be forwarded to the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the prime Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE does not count toward the DBE goal.
- (d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contact. Credit will be given for the following:
 - (1) The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
 - (2) The DBE may also lease trucks from a non-DBE firm, including from an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement.
- (e) DBE as a material supplier:
 - (1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
 - (2) 100 percent goal credit for the cost of materials or supplies obtained from a DBE manufacturer.
 - (3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a regular dealer or manufacturer.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Utilization Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal.

- (a) No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764. Telephone number (217) 785-4611. Telefax number (217) 785-1524.
- (b) The Contractor must notify and obtain written approval from the Department's Bureau of Small Business Enterprises prior to replacing a DBE or making any change in the participation of a DBE. Approval for replacement will be granted only if it is demonstrated that the DBE is unable or unwilling to perform. The Contractor must make every good faith effort to find another certified DBE subcontractor to substitute for the original DBE. The good faith efforts shall be directed at finding another DBE to perform at least the same amount of work under the contract as the original DBE, to the extent needed to meet the contract goal.
- (c) Any deviation from the DBE condition-of-award or contract specifications must be approved, in writing, by the Department. The Contractor shall notify affected DBEs in writing of any changes in the scope of work which result in a reduction in the dollar amount condition-of-award to the contract.

- (d) In addition to the above requirements for reductions in the condition of award, additional requirements apply to the two cases of Contractor-initiated work substitution proposals. Where the contract allows alternate work methods which serve to delete or create underruns in condition of award DBE work, and the Contractor selects that alternate method or, where the Contractor proposes a substitute work method or material that serves to diminish or delete work committed to a DBE and replace it with other work, then the Contractor must demonstrate one of the following:
 - (1) That the replacement work will be performed by the same DBE (as long as the DBE is certified in the respective item of work) in a modification of the condition of award; or
 - (2) That the DBE is aware that its work will be deleted or will experience underruns and has agreed in writing to the change. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so; or
 - (3) That the DBE is not capable of performing the replacement work or has declined to perform the work at a reasonably competitive price. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so.
- (e) Where the revision includes work committed to a new DBE subcontractor, not previously involved in the project, then a Request for Approval of Subcontractor, Department form BC 260A, must be signed and submitted.
- (f) If the commitment of work is in the form of additional tasks assigned to an existing subcontract, than a new Request for Approval of Subcontractor shall not be required. However, the Contractor must document efforts to assure that the existing DBE subcontractor is capable of performing the additional work and has agreed in writing to the change.
- (g) All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the Participation Statement. The Contractor shall not terminate for convenience a DBE listed in the Utilization Plan and then perform the work of the terminated DBE with its own forces, those of an affiliate or those of another subcontractor, whether DBE or not, without first obtaining the written consent of the Bureau of Small Business Enterprises to amend the Utilization Plan. The Contractor shall notify the Bureau of Small Business Enterprises of any termination for reasons other than convenience, and shall obtain approval for inclusion of the substitute DBE in the Utilization Plan. If good faith efforts following a termination of a DBE for cause are not successful, the Contractor shall contact the Bureau of Small Business Enterprises and provide a full accounting of the efforts undertaken to obtain substitute DBE participation. The Bureau of Small Business Enterprises will evaluate the good faith efforts in light of all circumstances surrounding the performance status of the contract, and determine whether the contract goal should be amended.
- (h) The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request. After the performance of the final item of work or delivery of material by a DBE and final payment therefore to the DBE by the Contractor, but not later than thirty calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Agreement on Department form SBE 2115 to the Regional Engineer. If full and final payment has not been made to the DBE, the DBE Payment Agreement shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Utilization Plan and after good faith efforts are reviewed, the Department may deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages. The Contractor may request an administrative reconsideration of any amount deducted as damages pursuant to subsection (i) of this part.
- (i) The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (j) Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor may request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department.

SPECIAL PROVISION FOR SUBCONTRACTOR MOBILIZATION PAYMENTS

Effective: April 2, 2005 Revised: April 1, 2011 To account for the preparatory work and the operations necessary for the movement of subcontractor personnel, equipment, supplies, and incidentals to the project site and for all other work or operations that must be performed or costs incurred when beginning work approved for subcontracting according to Section 60-01 of the Standard Specifications, the Contractor shall make a mobilization payment to each subcontractor.

This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be equal to 3 percent of the amount of the subcontract reported on form AER 260A submitted for the approval of the subcontractor's work.

The mobilization payment to the subcontractor is an advance payment of the reported amount of the subcontract and is not a payment in addition to the amount of the subcontract; therefore, the amount of the advance payment will be deducted from future progress payments.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department

EQUAL EMPLOYMENT OPPORTUNITY

In the event of the Contractor's noncompliance with any provisions of this Equal Employment Opportunity Clause, the Illinois Fair Employment Practices Act or the Fair Employment Practices Commission's Rules and Regulations for Public Contracts, the Contractor may be declared nonresponsible and therefore ineligible for future contracts or subcontracts with the State of Illinois or any of its political subdivisions or municipal corporations, and the contract may be canceled or avoided in whole or in part, and such other sanctions or penalties may be imposed or remedies invoked as provided by statute or regulation.

During the performance of this contract, the Contractor agrees as follows:

- (1) That it will not discriminate against any employee or applicant for employment because of race, color, religion, sex, national origin or ancestry; and further that it will examine all job classifications to determine if minority persons or women are underutilized and will take appropriate affirmative action to rectify any such underutilization.
- (2) That, if it hires additional employees in order to perform this contract or any portion hereof, it will determine the availability (in accordance with the Commission's Rules and Regulations for Public Contracts) of minorities and women in the area(s) from which it may reasonably recruit and it will hire for each job classification for which employees are hired in such a way that minorities and women are not underutilized.
- (3) That, in all solicitations or advertisements for employees placed by it or on its behalf, it will state that all applicants will be afforded equal opportunity without discrimination because of race, color, religion, sex, national origin or ancestry.
- (4) That it will send to each labor organization or representative of workers with which it has or is bound by a collective bargaining or other agreement or understanding, a notice advising such labor organization or representative of the Contractors obligations under the Illinois Fair Employment Practices Act and the Commission's Rules and Regulations for Public Contracts. If any such labor organization or representative fails or refuses to cooperate with the Contractor in its efforts to comply with such Act and Rules and Regulations, the Contractor will promptly so notify the Illinois Fair Employment Practices Commission and the contracting agency and will recruit employees from other sources when necessary to fulfill its obligations thereunder.
- (5) That it will submit reports as required by the Illinois Fair Employment Practices Commission's Rules and Regulations for Public Contracts, furnish all relevant information as may from time to time be requested by the Commission or the contracting agency, and in all respects comply with the Illinois Fair Employment Practices Act and the Commission's Rules and Regulations for Public Contracts.
- (6) That it will permit access to all relevant books, records, accounts and work sites by personnel of the contracting agency and the Illinois Fair Employment Practices Commission for purposes of investigation to ascertain compliance with the Illinois Fair Employment Practices Act and the Commission's Rules and Regulations for Public Contracts.
- (7) That it will include verbatim or by reference the provisions of paragraphs 1 through 7 of this clause in every performance subcontract as defined in Section 2.10(b) of the Commission's Rules and Regulations for Public Contracts so that such provisions will be binding upon every subcontractor; and that it will also so include the provisions or paragraphs 1, 5, 6 and 7 in every supply subcontract as defined in Section 2.10(a) of the Commission's Rules and Regulations for Public Contracts so that such provisions will be binding upon every such subcontractor. In the same manner as with other provisions of this contract, the Contractor will be liable for compliance with applicable provisions of this clause by all its subcontractors; and further it will promptly notify the contracting agency and the Illinois Fair Employment Practices Commission in the event any subcontractor fails or refuses to comply therewith. In addition, no Contractor will utilize any subcontractor declared by the Commission to be nonresponsible and therefore ineligible for contracts or subcontracts with the State of Illinois or any of its political subdivisions or municipal corporations.

CONSTRUCTION CONTRACT PROCUREMENT POLICIES

TABLE OF CONTENTS

SECTION 1

Proposal Requirements and Conditions

SUB-SECTION	
1-01 ADVERTISEMENT (Notice to Bidders)	68
1-02 PREQUALIFICATION OF BIDDERS	68
1-03 CONTENTS OF PROPOSAL FORMS	68
1-04 ISSUANCE OF PROPOSAL FORMS	69
1-05 INTERPRETATION OF QUANTITIES IN BID SCHEDULE	69
1-06 EXAMINATION OF PLANS, SPECIFICATIONS, AND SITE	69
1-07 PREPARATION OF THE PROPOSAL	
1-08 REJECTION OF PROPOSALS	70
1-09 PROPOSAL GUARANTY	
1-10 DELIVERY OF PROPOSALS	70
1-11 WITHDRAWAL OF PROPOSALS	70
1-12 PUBLIC OPENING OF PROPOSALS	70
1-13 DISQUALIFICATION OF BIDDERS	
1-14 WORKER'S COMPENSATION INSURANCE	70
SECTION 2	
Award and Execution of Contract	
Award and Excedition of Contract	
<u>SUB-SECTION</u>	
2-01 CONSIDERATION OF PROPOSALS	71
2-02 AWARD OF CONTRACT	
2-03 CANCELLATION OF AWARD	
2-04 RETURN OF PROPOSAL GUARANTY	
2-05 REQUIREMENT OF PERFORMANCE AND PAYMENT BONDS .	
2-06 EXECUTION OF CONTRACT	
2-07 APPROVAL OF CONTRACT	
2-08 FAILURE TO EXECUTE CONTRACT	72

SECTION 1

PROPOSAL REQUIREMENTS AND CONDITIONS

1-01 ADVERTISEMENT (Notice to Bidders) { TC "1-01 ADVERTISEMENT (Notice to Bidders)" \f C \l "1" }. The State of Illinois shall publish the advertisement at such places and at such times as are required by local law or ordinances. The published advertisement shall state the time and place for submitting sealed proposals; a description of the proposed work; instructions to bidders as to obtaining proposal forms, plans, and specifications; proposal guaranty required; and the Owner's right to reject any and all bids.

For Federally assisted contracts the advertisement shall conform to the requirements of local laws and ordinances pertaining to letting of contracts and, in addition, shall conform to the requirements of the appropriate parts of the Federal Aviation Regulations applicable to the particular contract being advertised.

1-02 PREQUALIFICATION OF BIDDERS{ TC "1-02 PREQUALIFICATION OF BIDDERS" \f C \l "1" }.

(a) When the awarding authority is the State of Illinois, each prospective bidder, prior to being considered for issuance of any proposal forms will be required to file, on forms furnished by the Department, an experience questionnaire and a confidential financial statement in accordance with the Department's Instructions for Prequalification of Contractors. The Statement shall include a complete report of the prospective bidder's financial resources and liabilities, equipment, past record and personnel, and must be submitted at least thirty (30) days prior to the scheduled opening of bids in which the Contractor is interested.

After the Department has analyzed the submitted "Contractor's Statement of Experience and Financial Condition" and related information and has determined appropriate ratings, the Department will issue to the Contractor a "Certificate of Eligibility". The Certificate will permit the Contractor to obtain proposal forms and plans for any Department of Transportation letting on work which is within the limits of the Contractor's potential as indicated on his "Certificate of Eligibility", subject to any limitations due to present work under contract or pending award as determined from the Contractor's submitted "Affidavit of Availability". Bidders intending to consistently submit proposals shall submit a "Contractor's Statement of Experience and Financial Condition" at least once a year. However, prequalification may be changed during that period upon the submission of additional favorable reports or upon reports of unsatisfactory performance.

Before a proposal is issued, the prospective bidder will be required to furnish an "Affidavit of Availability" indicating the location and amount of all uncompleted work under contract, or pending award, either as principal or subcontractor, as well as a listing of all subcontractors and value of work sublet to others. The prospective bidder may be requested to file a statement showing the amount and condition of equipment which will be available.

Before an award is made, the bidder may be required to furnish an outline of his plans for conducting the work.

(b) When the awarding authority for contract construction work is the County Board of a county; the Council, the City Council, or the President and Board of Trustees of a city, village or town, each prospective bidder, in evidence of his competence, shall furnish the awarding authority as a prerequisite to the release of proposal forms by the awarding authority, a certified or photostatic copy of a "Certificate of Eligibility" issued by the Department of Transportation, in accordance with Section 1-02(a).

The two low bidders must file within 24 hours after the letting a sworn affidavit, in triplicate, showing all uncompleted contracts awarded to them and all low bids pending award for Federal, State, County, Municipal and private work, using the blank form made available for this affidavit. One copy shall be filed with the awarding authority and two copies with the District Highway Office.

1-03 CONTENTS OF PROPOSAL FORMS{ TC "1-03 CONTENTS OF PROPOSAL FORMS" \f C \l "1" }. Upon request, the Department will furnish the prequalified bidders a proposal form. This form will state the location and description of the contemplated construction and will show the estimate of the various quantities and kinds of work to be performed or materials to be furnished, and will have a schedule of items for which unit bid prices are invited. The proposal form will state the time in which work must be completed, the amount of the proposal guaranty, labor requirements, and date, time and place of the opening of proposals. The form will also include any special provisions or requirements which vary from or are not contained in these specifications.

All papers bound with or attached to the proposal form are considered a part thereof and must not be detached or altered when the proposal is submitted. Any addenda officially issued by the Department, will be considered a part of the proposal whether attached or not.

For Federally assisted contracts, the proposal shall conform to the requirements of local laws and ordinances pertaining to letting of contracts and, in addition, shall conform to the requirements of the appropriate parts of the Federal Aviation Regulations pertaining to the particular contract being let.

1-04 ISSUANCE OF PROPOSAL FORMS{ TC "1-04 ISSUANCE OF PROPOSAL FORMS" \f C \l "1" }. The Department shall refuse to issue a proposal form for any of the following reasons:

- (a) Lack of competency and adequate machinery, plant and other equipment, as revealed by the financial statement and experience questionnaires required under Section 1-02(a).
- (b) Uncompleted work which, in the judgment of the Department, might hinder or prevent the prompt completion of additional work if awarded.
- (c) False information provided on a bidder's "Affidavit of Availability".
- (d) Failure to pay, or satisfactorily settle, all bills due for labor and material on former contracts in force at the time of issuance of proposal forms.
- (e) Failure to comply with any pregualification regulations of the Department.
- (f) Default under previous contracts.
- (g) Unsatisfactory performance record as shown by past work for the Department, judged from the standpoint of workmanship and progress.
- (h) When the Contractor is suspended from eligibility to bid at a public letting where the contract is awarded by, or require approval of, the Department.
- (i) When any agent, servant, or employee of the prospective bidder currently serves as a member, employee, or agent of a governmental body that is financially involved in the proposed work.
- (j) When any agent, servant, or employee of the prospective bidder has participated in the preparation of plans or specifications for the proposed work.

1-05 INTERPRETATION OF QUANTITIES IN BID SCHEDULE{ TC "1-05 INTERPRETATION OF QUANTITIES IN BID SCHEDULE" \f C \l "1"}. An estimate of quantities of work to be done and materials to be furnished under these specifications is given in the proposal. It is the result of careful calculations and is believed to be correct. It is given only as a basis for comparison of proposals and the award of the contract. The Owner does not expressly or by implication agree that the actual quantities involved will correspond exactly therewith; nor shall the bidder plead misunderstanding or deception because of such estimates of quantities, or of the character, location, or other conditions pertaining to the work. Payment to the Contractor will be made only for the actual quantities of work performed or materials furnished in accordance with the plans and specifications. It is understood that the quantities may be increased or decreased as provided in the subsection titled ALTERATION OF WORK AND QUANTITIES of Section 20 of the Illinois Standard Specifications for Construction of Airports without in any way invalidating the unit bid prices.

1-06 EXAMINATION OF PLANS, SPECIFICATIONS, AND SITE{ TC "1-06 EXAMINATION OF PLANS, SPECIFICATIONS, AND SITE" \f C \l "1" \}. The bidder is expected to carefully examine the site of the proposed work, the proposal, plans, specifications, and contract forms. He shall satisfy himself as to the character, quality, and quantities of work to be performed, materials to be furnished, and as to the requirements of the proposed contract. The submission of a proposal shall be prima facie evidence that the bidder has made such examination and is satisfied as to the conditions to be encountered in performing the work and as to the requirements of the proposed contract, plans, and specifications.

Boring logs, underground utilities and other records of subsurface investigations and tests are available for inspection of bidders. It is understood and agreed that such subsurface information, whether included in the plans, specifications, or otherwise made available to the bidder, was obtained and is intended for the Owner's design and estimating purposes only. Such information has been made available for the convenience of all bidders. It is further understood and agreed that each bidder is solely responsible for all assumptions, deductions, or conclusions which he may make or obtain from his examination of the boring logs and other records of subsurface investigations and tests that are furnished by the Owner.

1-07 PREPARATION OF THE PROPOSAL{ TC "1-07 PREPARATION OF THE PROPOSAL" \f C \l "1" }. The bidder shall submit his proposal on the form furnished by the Department. The proposal shall be executed property, and bids shall be made for all items indicated in the proposal form, except that when alternate bids are asked, a bid on more than one alternate for each item is not required, unless otherwise provided. The bidder shall indicate, in figures, a unit price for each of the separate items called for in the proposal; he shall show the products of the respective quantities and unit prices in the column provided for that purpose, and the gross sum shown in the place indicated in the proposal shall be the summation of said products. All writing shall be with ink or typewriter, except the signature of the bidder which shall be written with ink.

If the proposal is made by an individual, his name and business address shall be shown. If made by a firm or partnership, the name and business address of each member of the firm or partnership shall be shown. If made by a corporation, the proposal shall show the names, titles, and business address of the president, secretary, and treasurer, and the seal of the corporation shall be affixed and attested by the secretary.

The proposal shall be issued to a prequalified bidder in the same name and style as the financial statement used for prequalification and shall be submitted in like manner.

- 1-08 REJECTION OF PROPOSALS{ TC "1-08 REJECTION OF PROPOSALS" \f C \l "1" }. The Department reserves the right to reject proposals for any of the conditions in Article 1-04 or for any of the following reasons:
 - (a) More than one proposal for the same work from an individual, firm, partnership, or corporation under the same or different names.
 - (b) Evidence of collusion among bidders.
 - (c) Unbalanced proposals in which the prices for some items are obviously out of proportion to the prices for other items.
 - (d) If the proposal does not contain a unit price for each pay item listed except in the case of authorized alternate pay items or lump sum pay items.
 - (e) If the proposal is other than that furnished by the Department; or if the form is altered or any part thereof is detached.
 - (f) If there are omissions, erasures, alterations, unauthorized additions, conditional or alternate bids, or irregularities of any kind which may tend to make the proposal incomplete, indefinite, or ambiguous as to its meaning.
 - (g) If the bidder adds any provisions reserving the right to accept or reject an award, or to enter into a contract pursuant to an award.
 - (h) If the proposal is not accompanied by the proper proposal guaranty.
 - (i) If the proposal is prepared with other than ink or typewriter.
 - (j) If the proposal is submitted in any other name other than that to whom it was issued by the Department.
- 1-09 PROPOSAL GUARANTY{ TC "1-09 PROPOSAL GUARANTY" \f C \l "1" }. Each Proposal shall be accompanied by either a bid bond on the Department of Transportation, Division of Aeronautics form contained in the proposal, executed by a corporate surety company satisfactory to the Department or by a bank cashier's check or a properly certified check for not less than 5 percent of the amount bid.

Bank cashier's checks, or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois.

- 1-10 DELIVERY OF PROPOSALS{ TC "1-10 DELIVERY OF PROPOSALS" \f C \l "1" \}. Each proposal should be submitted in a special envelope furnished by the Department. The blank spaces on the envelope shall be filled in correctly to clearly indicate its contents. When an envelope other than the special one furnished by the Department is used, it shall be of the same general size and shape and be similarly marked to clearly indicate its contents. When sent by mail, the sealed proposal shall be addressed to the Department at the address and in care of the official in whose office the bids are to be received. All proposals shall be filled prior to the time and place specified in the Notice to Bidders. Proposals received after the time for opening of bids will be returned to the bidder unopened.
- 1-11 WITHDRAWAL OF PROPOSALS{ TC "1-11 WITHDRAWAL OF PROPOSALS" \f C \l "1" }. Permission will be given a bidder to withdraw a proposal if he makes his request in writing or by telegram before the time for opening proposals. If a proposal is withdrawn, the bidder will not be permitted to resubmit this proposal at the same letting. With the approval of the Engineer, a bidder may withdraw a proposal and substitute a new proposal prior to the time of opening bids.
- 1-12 PUBLIC OPENING OF PROPOSALS{ TC "1-12 PUBLIC OPENING OF PROPOSALS" \f C \l "1" }. Proposals will be opened and read publicly at the time and place specified in the Notice to Bidders. Bidders, their authorized agents, and other interested parties are invited to be present.
- 1-13 DISQUALIFICATION OF BIDDERS{ TC "1-13 DISQUALIFICATION OF BIDDERS" \f C \l "1" }. A bidder shall be considered disqualified for any of the following reasons:
 - (a) Submitting more than one proposal from the same partnership, firm, or corporation under the same or different name.
 - (b) Evidence of collusion among bidders. Bidders participating in such collusion shall be disqualified as bidders for any future work of the Owner.
 - (c) If the bidder is considered to be in "default" for any reason specified in the Subsection 1-04 titled ISSUANCE OF PROPOSAL FORMS of this section.
- 1-14 WORKER'S COMPENSATION INSURANCE{ TC "1-14 WORKER'S COMPENSATION INSURANCE" \f C \l "1" }. Prior to the approval of his contract by the Division, the Contractor shall furnish to the Division certificates of insurance covering Worker's Compensation, or satisfactory evidence that this liability is otherwise taken care of in accordance with Section 4.(a) of the "Worker's Compensation Act of the State of Illinois" as amended.

Such insurance, or other means of protection as herein provided, shall be kept in force until all work to be performed under the terms of the contract has been completed and accepted in accordance with the specifications, and it is hereby understood and agreed that the maintenance of such insurance or other protection, until acceptance of the work by the Division is a part of the contract. Failure to maintain such insurance, cancellation by the Industrial Commission of its approval of such other means of protection as might have been elected, or any other act which results in lack of protection under the said "Workers' Compensation Act" may be considered as a breach of the contract.

SECTION 2

AWARD AND EXECUTION OF CONTRACT

2-01 CONSIDERATION OF PROPOSALS{ TC "2-01 CONSIDERATION OF PROPOSALS" \f C \l "1" }. After the proposals are publicly opened and read, they will be compared on the basis of the summation of the products obtained by multiplying the estimated quantities shown in the proposal by the unit bid prices. In the event of a discrepancy between unit bid prices and extensions, the unit bid price shall govern.

Until the award of a contract is made, the Owner reserves the right to reject a bidder's proposal for any of the following reasons:

- (a) If the proposal is irregular as specified in the subsection titled REJECTION OF PROPOSALS of Section 1.
- (b) If the bidder is disqualified for any of the reasons specified in the subsection titled DISQUALIFICATION OF BIDDERS of Section 1.

In addition, until the award of a contract is made, the Owner reserves the right to reject any or all proposals; waive technicalities, if such waiver is in the best interest of the Owner and is in conformance with applicable State and Local laws or regulations pertaining to the letting of construction contracts; advertise for new proposals; or proceed with the work otherwise.

2-02 AWARD OF CONTRACT{ TC "2-02 AWARD OF CONTRACT" \f C \l "1" \}. The award of contract will be made within 60 calendar days after the opening of proposals to the lowest responsible and qualified bidder whose proposal complies with all the requirements prescribed. The successful bidder will be notified by letter, that his bid has been accepted, and that he has been awarded the contract.

If a contract is not awarded within 60 days after the opening of proposals, a bidder may file a written request with the Division for the withdrawal of his bid and the Division will permit such withdrawal.

For Federally assisted contracts, unless otherwise specified in this subsection, no award shall be made until the Division has concurred in the Owner's recommendation to make such award and has approved the Owner's proposal contract to the extent that such concurrence and approval are required by Federal Regulations.

- 2-03 CANCELLATION OF AWARD{ TC "2-03 CANCELLATION OF AWARD" \f C \l "1" }. The Division reserves the right to cancel the award without liability to the bidder at any time before a contract has been fully executed by all parties and is approved by the Owner in accordance with the subsection titled APPROVAL OF CONTRACT of this section. The Division at the time of cancellation will return the proposal guaranty.
- 2-04 RETURN OF PROPOSAL GUARANTY{ TC "2-04 RETURN OF PROPOSAL GUARANTY" \f C \l "1" }. The proposal guaranties of all except the two lowest bidders will be returned promptly after the proposals have been checked, tabulated, and the relation of the proposals established. Proposal guaranties of the two lowest bidders will be returned as soon as the Construction Contract, Performance Bonds, and Payment Bonds of the successful bidder have been properly executed and approved.

If any other form of proposal guaranty is used, other than a bid bond, a bid bond may be substituted at the Contractor's option.

- 2-05 REQUIREMENT OF PERFORMANCE AND PAYMENT BONDS{ TC "2-05 REQUIREMENT OF PERFORMANCE AND PAYMENT BONDS" \f C \l "1" \}. The successful bidder for a contract, at the time of the execution of the contract, shall deposit with the Division separate performance and payment bonds each for the full amount of the contract. The form of the bonds shall be that furnished by the Division, and the sureties shall be acceptable to the Division.
- 2-06 EXECUTION OF CONTRACT{ TC "2-06 EXECUTION OF CONTRACT" \f C \l "1" \}. The successful bidder shall sign (execute) the Contract and shall return the signed Contract to the Owner (Sponsor) for signature (execution) and subsequently return all copies to the Division. The fully executed surety bonds specified in the subsection title REQUIREMENTS OF PERFORMANCE AND PAYMENT BONDS of this section will be forwarded to the Division within 15 days of the date mailed or otherwise delivered to the successful bidder. If the Contract and Bonds are mailed, special handling is recommended.

If the bidder to whom award is to be made is a corporation organized under the laws of a State other than Illinois, the bidder shall furnish the Division a copy of the corporation's certificate of authority to do business in the State of Illinois, or provide evidence of the same, with the return of the executed contract and bond. Failure to furnish such evidence of a certificate of authority within the time required will be considered as just cause for the annulment of the award and the forfeiture of the proposal guaranty to the State, not as a penalty, but in payment of liquidated damages sustained as a result of such failure.

2-07 APPROVAL OF CONTRACT{ TC "2-07 APPROVAL OF CONTRACT" \f C \l "1" }. Upon receipt of the contract and bonds that have been executed by the successful bidder, the Owner shall complete the execution of the contract in

accordance with local laws or ordinances, and return the contract to the Division for approval and execution by the Division. Delivery of the fully executed contract to the Contractor shall constitute the Department's approval to be bound by the successful bidder's proposal and the terms of the contract.

2-08 FAILURE TO EXECUTE CONTRACT{ TC "2-08 FAILURE TO EXECUTE CONTRACT" \f C \l "1" }. If the contract is not executed by the Division within 15 days following receipt from the bidder of the properly executed contracts and bonds, the bidder shall have the right to withdraw his bid without penalty.

Failure of the successful bidder to execute the contract and file acceptable bonds within 15 days after the contract has been mailed to him shall be just cause for the cancellation of the award and the forfeiture of the proposal guaranty which shall become the property of the State, not as a penalty, but as liquidation of damages sustained.

1A FA005

SECTION III

FAIRFIELD MUNICIPAL AIRPORT FAIRFIELD, ILLINOIS

REPLACE NAVAIDS AND AIRFIELD LIGHTING

ILLINOIS PROJECT NO.: FWC-4105 A.I.P. PROJECT NO.: 3-17-0043-B12

Prepared By:



Hanson Professional Services Inc.

July1, 2011

Revised July 26, 2011

INDEX

ITEM NO.	DESCRIPTION	PAGE
	Foreword	1
106	Replace Light Fixture	6
107	Installation of Airport 8-Foot and 12-Foot Wind Cones	
AR107900	Remove Wind Cone	19
108	Installation of Underground Cable for Airports	21
109	Installation of Airport Transformer Vault and Vault Equipment	29
110	Installation of Airport Underground Electrical Duct	47
AR110610	Electrical Handhole	52
125	Installation of Airport Lighting Systems	54
AR125610	REILS	60
AR125907	Remove REILS	66
AR125989	Refurbish PLASI	68

Copyright © 2002 by Hanson Professional Services Inc. All rights reserved. This document is intended solely for the use of the individual or the entity to which it is addressed. The information contained in this document shall not be duplicated, stored electronically, or distributed, in whole or in part, without the express written permission of Hanson Professional Services Inc., 1525 S. Sixth St., Springfield, IL 62703, (217) 788-2450, www.hanson-inc.com. Unauthorized reproduction or transmission of any part of this document is a violation of federal law.

Illinois Project: FWC-4105

FOREWORD

These Special Provisions, together with applicable Standard Specifications, Rules and Regulations, Contract Requirements for Airport Improvement Projects, Payroll Requirements and Minimum Wage Rates, which are hereto attached or which by reference are herein incorporated, cover the requirements of the State of Illinois, Department of Transportation (IDOT), Division of Aeronautics (Division) for the following improvement project at the Fairfield Municipal Airport located in Fairfield, Illinois including:

SCOPE OF WORK

This work shall consist of replacement of the REIL's on the Runway 9 end, refurbishment of the PLASI systems on both runway ends 9 and 27, replacement of the L-807 primary wind cone, replacement of the Runway 27 L-861E threshold lights with L-861SE enhanced threshold lights, replacement of the apron light fixtures, installing a supplemental L-806 wind cone for the Runway 9 End, and the associated cabling, duct work, and vault work.

GOVERNING SPECIFICATIONS AND RULES AND REGULATIONS

The <u>Standard Specifications for Construction of Airport</u>, Illinois Department of Transportation, Division of Aeronautics, adopted November 2, 2009, shall govern the project, except as otherwise revised or noted in these Special Provisions. All references to IDOT Specifications refer to <u>Standard Specifications for Road and Bridge Construction</u>, Illinois Department of Transportation, adopted January 1, 2007, as revised. In the event of inconsistencies between the Standard Specifications and the Special Provisions, the Special Provisions shall govern.

DIVISION I

SECTION 50 LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC

<u>50-10 Barricades, Warning Signs, and Hazard Markings.</u> Add the following paragraphs to this section:

"Runway 18-36 will be closed only during the construction day. The Contractor will close the runway at the start of the construction day and re-open the runway when all construction activities have been completed at the end of the construction day. The Contractor, Resident Engineer and Airport Manager shall visually inspect the runway and its' lighting circuit prior to re-opening the runway.

Runway 9-27 will be closed whenever construction activities are within 200 ft of the active runway centerline. To limit the inconvenience to the Airport, the Contractor will

Illinois Project: FWC-4105

limit the number and length of closures. He will accomplish the required work as quickly as possible, and withdraw a sufficient distance that will allow opening the runway.

The Contractor will notify the Airport Manager seven (7) days in advance of the commencement of work, which would necessitate the closing of a runway. It will be the responsibility of the Contractor to properly mark the closed runway, and when the runway is reopened, to remove the marking. The appropriate marking for a closed runway is a cross at both ends of the runway. The legs of the cross will be 60 ft in length and 10 ft in width. The crosses will be constructed of any suitable, locally available materials, such as fabric, plywood, or other similar material. They will be held in place in a manner locally determined to be suitable. The Contractor will be responsible for placing and removing the crosses as the runways are closed and opened. The Contractor will provide the Engineer with a proposed schedule of when and length of time for all closures. The Project Engineer must review and approve this schedule before any construction begins.

When Runway 18-36 is closed and Runway 9-27 is open an aircraft having a wingspan of 49' to 78' could desire to land or take off on Runway 9-27. To reach the runway or apron the aircraft would have to taxi on a portion of Runway 18-36. If the Contractor is working on Runway 18-36 within the area the aircraft will have to taxi, then the Contractor will be required to move his equipment a sufficient distance from the edge of the pavement to allow the aircraft to pass. The airplane pilot will contact the airport at least 2 hours before landing or taking off to allow the Contractor sufficient time to move his equipment.

When the Contractor's vehicles are on Airport property, they shall be properly marked. The markings shall consist of a 3-ft square flag consisting of a checkered pattern of international orange and white squares of not less than 1 ft on each side displayed in full view above the vehicle. Contractor vehicles engaged in continuous hauling operations will not be required to display a flag.

The Contractor will be responsible for placing barricades and/or traffic cones at the locations shown on the Construction Plans, or as directed by the Airport Manager. It will be the Contractor's responsibility to furnish and maintain the barricades equipped with red flashing or red, steady-burn lights and 20-in. square orange flags throughout the duration of this project.

The barricades and their maintenance will be considered as an incidental item to the contract, and no additional compensation will be allowed. Any cost of labor and equipment, which is necessary to insure safety at the Airport during the duration of the project, will be considered incidental to the contract, and no additional reimbursement for these items of work will be received."

Illinois Project: FWC-4105

SCHEDULING OF OPERATIONS

The Contractor shall coordinate all work on this project with the Project Engineer and the Airport Manager to insure that the construction will cause the least amount of inconvenience possible to normal Airport activity. The Resident Engineer shall coordinate all Notices to Airmen (NOTAMs) with the Airport Manager.

The Contractor will be required to submit a work schedule to the Division and to the Resident Engineer showing proposed sequences of work.

In the event that other construction projects are in progress at the Airport at the same time as this project, the Contractor will be required to cooperate with all other Contractors and the Airport Manager in the coordination of the work.

The Airport Manager will, at all times, have jurisdiction over the safety of air traffic during construction. Whenever the safety of air traffic during construction is concerned, his decision as to methods, procedures, and measures used shall be final, and any and all Contractors performing work must be governed by such decisions.

The Contractor shall not be entitled to any extra compensation due to delays or inconveniences caused by said necessary methods, procedures, and measures to protect air traffic.

PROPOSED HAUL ROUTE

The Contractor will use only the designated haul route and equipment parking area shown on Sheet No. 3 of the Construction Plans. The Contractor's men and equipment shall not traverse outside the designated work areas to other locations on the Airport. The designated haul route will be the only vehicular access to the construction site. The Contractor will be required to be in two-way radio contact (123.05 MHz) with the Airport's UNICOM system. This will keep the Contractor in contact with Airport personnel and enable the Airport personnel to immediately contact the Contactor in case of an aeronautical emergency that would require action by the Contractor and/or his personnel. The Contractor will restore the haul route and equipment parking area upon completion of the project. Restoration of the equipment parking and material storage area will be considered incidental to the Project and no additional compensation will be allowed. Failure to use the prescribed haul route and equipment parking area or adhere to the safety requirements will result in the suspension of work.

EMPLOYEE PARKING

The Contractor's employees shall park their personal vehicles in the proposed equipment parking area. The Contractor will transport his employees/workers from this area to the proposed construction area. No employee vehicle will be allowed onto the proposed construction site. Only Contractor vehicles will be allowed outside of the proposed equipment storage and parking areas.

Illinois Project: FWC-4105

EQUIPMENT PARKING AND MATERIAL STORAGE

The Contractor will use the designated equipment parking and material storage area as shown on Sheet No. 3 of the Construction Plans. This area will be maintained throughout the duration of the construction project. At the conclusion of the project the Contractor will return this area to its original condition. The area will be seeded and mulched in accordance with items 901 and 908. The restoration of this area will be considered as incidental to the contract and no additional compensation will be allowed.

CONTRACTOR IDENTIFICATION

The Contractor shall be responsible for providing the workers with some type of tag or garment to identify the person as being part of the construction crew.

AIRPORT SECURITY NOTES

Airport security will be maintained at all times. The Contractor will access the proposed job site through an existing gate. The Contractor will be required to close and secure this gate after he has gone through it. It will be the Contractor's responsibility to escort all material vehicles to the location on the airport where their designated material is needed. Once the material has been delivered the Contractor will escort the vehicle back to the access gate.

MAINTAINING OPERATION OF AIRFIELD LIGHTING AND NAVAIDS

This project will require the Contractor to shut down the runway lighting circuits, taxiway lighting circuit, and/or Navaids on Runways 9-27 and 18-36 as the Contractor works on the REIL, PLASI systems, Wind Cones, and runway edge lighting on Runway 9-27 and/or Runway 18-36. The runway and taxiway circuits will be re-activated at the end of each construction day. Shut down of a runway or taxiway lighting circuit shall occur when construction activities are within 200' of a runway centerline or 85' of a taxiway centerline. The Contractor shall provide temporary connections and any manual operations of airfield lighting to keep them in operation over night. The contractor shall secure, identify, and place temporary exposed wiring in conduit, duct, or unit duct to prevent electrocution and fire ignition sources in conformance with the requirements of FAA AC 150/5370-2E "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".

Illinois Project: FWC-4105

SITE INSPECTION

The Contractor shall be responsible for an on-site inspection prior to submitting a bid on this project. <u>Upon receipt of a bid, it shall be assumed that the Contractor is fully familiar with the construction site.</u>

Illinois Project: FWC-4105

ITEM AR106930 – REPLACE LIGHT FIXTURE

DESCRIPTION

106930-1.1 Item AR106930 Replace Light Fixture shall consist of removing the existing Apron Flood Light fixtures and replacing them with new Apron Flood Light fixtures complete, in place, in accordance with the details shown on the construction Plans. Included in this item shall be all high pressure sodium light fixtures, ballasts, lamps, mounting bracket and interface hardware, connections and ground wire, all wiring from the pole base to the respective light fixtures, and fusing, the making of all electrical connections, the testing of the installation, and all other incidentals necessary to place the lights in operation to the satisfaction of the Resident Engineer.

<u>106930-1.2 REFERENCES</u>

- A. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 Fittings Rigid Metal Conduit and EMT.
- C. ASTM Specification B3 Standard Specification for Soft or Annealed Copper Wire.
- D. ASTM Specification B8 Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft.
- E. FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- F. Federal Specification A-A-59544 Cable and Wire, Electrical (Power, Fixed Installation).
- G. NEMA TC-2 Electrical Plastic Tubing and Conduit.
- H. NEMA TC-3 Fittings Rigid PVC Conduit and Tubing.
- I. NFPA 70 National Electrical Code (most current issue in force).
- J. NFPA 70E Standard for Electrical Safety in the Workplace.
- K. OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.
- L. UL Standard 6 Rigid Metal Conduit.
- M. UL Standard 44 Thermoset-Insulated Wires and Cables.
- N. UL Standard 83 Thermoplastic-Insulated Wires and Cables.

Illinois Project: FWC-4105

Illinois Project: FWC-4105 Fairfield Municipal Airport A.I.P. Project: 3-17-0043-B12

O. UL Standard 651 – Schedule 40 and 80 Rigid PVC Conduit.

106930-1.3 SHOP DRAWINGS: The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for the apron lighting equipment and materials. Shop drawings shall be clear and legible. Copies that are illegible will be rejected. Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:

- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Shop drawings shall include cut sheets, specifications, manufacturer part numbers for the apron light fixtures and associated materials.

EQUIPMENT AND MATERIALS

106930-2.1 APRON FLOOD LIGHT FIXTURES: Each replacement luminaire shall include appropriate adapters/mast fitters to mount on the existing pole top mounting tenon. Contractor shall confirm pole top mounting on the existing poles to ensure each replacement luminaire will be compatible with the respective existing pole. Luminaires shall be 400 Watt High Pressure Sodium with a quad-voltage (120/208/240/277 VAC) ballast. Each luminaire shall have Type C diffused reflector very wide and shall have a dark bronze finish. Luminaires shall be UL Listed and suitable for use in wet locations. Luminaires shall additionally be UL 1598A Marine Wet Location Listed. Luminaires shall be Phillips Wide-Lite F Series Industrial Floodlight Cat. No. MFS-400-C-QV-TDB, or an approved equal. Each luminaire's ballast shall have individual fuse kits installed at the base of the pole. Fuses shall be the size and type as recommended by the respective luminaire manufacturer. All luminaires will be equipped with all hardware necessary for mounting to the existing poles. Luminaires shall include a five year warranty. The luminaires will be aimed at night and coordinated with the Airport Manager and the Resident Engineer.

106930-2.2 LAMPS: All lamps shall be 400 Watt High Pressure Sodium as detailed on the Plans. One spare lamp shall be provided for each luminaire. Lamps shall be installed by the Contractor, just prior to testing the system, to reduce the possibility of breakage. Broken lamps shall be replaced at no additional cost to the contract. Spare lamps shall be turned over to the Airport Manager.

<u>106930-2.3 BALLASTS</u>: Ballasts shall be operable at 120/208/240/277 VAC, 1 phase, 60 Hz, and be capable of starting the lamps indicated herein down to a temperature of -20 degrees Fahrenheit. Ballasts shall be of the high power factor constant wattage autotransformer type. Ballasts shall be an integral but easily replaceable part of the luminaire.

<u>106930-2.4 LUMINAIRE FUSING:</u> Luminaire fusing shall be provided at the handhole at the base of the light pole. Fuses shall be the size and type as recommended by the luminaire manufacturer for the respective light fixture, and shall be installed in double pole in-line fuse holders, Bussmann HEY, or equivalent. Each luminaire shall be provided with separate individual fusing. Wiring runs from the base of the pole to the fixtures shall be #10 AWG minimum THWN or XHHW stranded copper.

<u>106930-2.5 SURGE ARRESTER FOR APRON LIGHTS</u>: An AC surge protector shall be furnished and installed in the base of each light pole, and wired in series with each respective light fixture's circuit. Surge protectors shall be suitable for use on a 120 VAC, 1 phase, 2 wire system, with ground. Surge protectors shall be Edco, Inc. of Florida Model SHA 1203, Ditek Model DTK-DL120, or approved equal. Install per manufacturer's directions.

106930-2.6 THWN WIRE: Cable shall comply with Underwriters' Laboratories Standard UL-83 and Federal Specification A-A-59544. Conductor shall be soft-annealed, uncoated copper and shall comply with ASTM B3 and B8. Insulation shall be rated for 600-Volts. Insulation shall be polyvinyl-chloride conforming to Underwriters' Laboratories requirements for Type THW. The outer covering shall be nylon-conforming to Underwriters' Laboratories for type THHN or THWN. Cable shall be UL-listed and marked THWN. Power and control wiring shall be Superior Essex or Southwire Company Type THWN, or approved equal.

106930-2.7 XHHW WIRE: Cable shall comply with UL Standard 44, ICEA S-95-658/NEMA WC70, and Federal Specification A-A-59544. Conductors shall be Class B-stranded, annealed, uncoated copper per UL Standard 44. Insulation shall be rated for 600-Volts. Insulation shall be cross-linked polyethylene complying with the physical and electrical requirements of UL Standard 44 for Type XHHW-2. Cable shall be UL-listed and marked XHHW-2. Service conductors shall be Service Wire Company or Southwire Company, Type XHHW-2, or approved equal.

CONSTRUCTION METHODS

<u>106930-3.1 GENERAL</u>: The Contractor shall furnish and install all equipment and materials necessary for complete installation of the apron lights, as stipulated in this Special Provision and as shown on the Plans.

A. The complete installation and wiring shall be done in a neat, workmanlike manner. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of the National Electrical Code (most current issue in force) and all other applicable local codes, laws, ordinances, and requirements in force. Electrical equipment shall be installed in conformance with the respective manufacturer's

Illinois Project: FWC-4105

Illinois Project: FWC-4105 A.I.P. Project: 3-17-0043-B12

directions and recommendations for the respective application. Any installations, which void the UL listing, ETL listing, (or other third party listing) and/or the manufacturer's warranty of a device, will not be permitted.

- B. Contractor shall keep a copy of the latest NEC in force on site at all times during construction for use as a reference.
- C. Contractor shall keep a copy of the Plans, Special Provision Specifications including any addenda, and copies of any change orders on site at all times during construction.
- D. The Contractor should examine the proposed site to evaluate the complexity of the work.
- E. Contractor shall coordinate work and any power outages with the Airport Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).
- F. Contractor shall comply with the requirements of FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- G. Contractor shall comply with the applicable requirements of NFPA 70E Standard for Electrical Safety in the Workplace.

106930-3.2 INSTALLATION OF APRON FLOOD LIGHTS: Installation of the Apron flood lights shall be as detailed on the Plans, in accordance with the respective equipment manufacturer's recommendations and as specified herein.

- A. The Contractor shall furnish and install all necessary wire to make electrical connections between the light fixtures and the ballast terminals, and the ballast terminal and the feeder cables.
- B. The equipment ground wire run with power conductors to the pole shall be bonded to the pole. Include a #10 THWN equipment ground wire with the branch circuit conductors from the base of the pole to each light fixture.
- C. The installation shall be tested in operation as a completed unit prior to acceptance. Tests shall include resistance, voltage and current readings, as required by the Resident Engineer. The contractor shall furnish all testing equipment. Tests shall be conducted as directed by the Resident Engineer and shall be to his satisfaction. The Contractor shall be responsible for all equipment and materials furnished under this contract and for equipment and conduit in

Illinois Project: FWC-4105 A.I.P. Project: 3-17-0043-B12

place, which will be connected to the new equipment, and any equipment or materials found to be defective or damaged shall be replaced by the Contractor at his own expense.

BASIS OF PAYMENT

106930-4.1 Item AR106930 Replace Light Fixture will be paid for at the contract unit price bid per each, which price and payment shall constitute full compensation for removing the existing light fixtures and for furnishing and installing replacement apron lighting luminaires with lamps, ballasts, brackets, and mounting hardware; for furnishing and installing fusing, for all wiring (except "feeder" cable), and grounding; for making all electrical connections; for testing the installation; and for all other incidentals necessary to place the lights in operation to the satisfaction of the Resident Engineer.

Payment will be made under:

Item AR106930 Replace Light Fixture per each

END OF ITEM AR106930

ITEM 107 INTALLATION OF AIRPORT 8-FOOT AND 12-FOOT WIND CONES

DESCRIPTION

107-1.1. Revise this section to read as follows:

"Item AR107408 shall consist of furnishing and installing an L-806 Supplemental Wind Cone at each location shown on the Plans and in accordance with these Special Provisions. The work shall include the furnishing and installation of a support for mounting the wind cone and a concrete foundation. This item shall include wind cone manufacturer's cable, connections, splice cans, series circuit transformer, conduit and conduit fittings, lamps, ground rod and ground connection, and all associated equipment, materials, labor, tools, testing, and all incidentals necessary to place each wind cone in operation as a completed unit to the satisfaction of the Engineer.

Item AR107712 L-807 Wind Cone-12' Lighted shall consist of furnishing and installing a 12-ft lighted wind cone with obstruction light at the location shown on the Plans, and in accordance with the details and notes on the Plans and these Special Provisions. The work shall include the furnishing and installation of a support for mounting the wind cone and a concrete foundation. This item shall include wind cone manufacturer's cable, connections, splice cans, series circuit transformer, conduit and conduit fittings, lamps, ground rod and ground connection, and all associated equipment, materials, labor, tools, testing, and all incidentals necessary to place each wind cone in operation as a completed unit to the satisfaction of the Engineer.

Per FAA AC No. 150/5340-30E "Design and Installation Details for Airport Visual Aids" Part 6.3 Wind Cones, Paragraph b, a primary wind cone is needed at any airport without a 24-hour ATCT (Air Traffic Control Tower). Airport Certification Information Bulletin Number 08-10 and FAA AC 150/5370-10E Standards for Specifying Construction of Airports both state the following:

"The illuminated wind cone must present a constant brightness to the pilot. As a result, the source of power for the wind cone circuit must be identified. Where a constant voltage is available, the wind cone may be connected directly to the constant voltage circuit. Where the series lighting circuit is used as a power source to the wind cone, a power adapter that converts current to constant voltage must be specified. An additional requirement for the power adapter is the output voltage must remain constant regardless of the input current. The manufacturer of the power adapter must be consulted to verify the additional load imposed on the series circuit by the power adapter.

The engineer should specify the wind cone and power adapter combination recommended by the manufacturer when the power source for the wind cone circuit will be the constant current series lighting circuit.""

Illinois Project: FWC-4105

Illinois Project: FWC-4105 A.I.P. Project: 3-17-0043-B12

107-1.2 REFERENCES

- A. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 Fittings Rigid Metal Conduit and EMT.
- C. FAA AC No. 150/5340-30E "DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS", (or most current issue in force).
- D. FAA AC No. 150/5345-27D "SPECIFICATION FOR WIND CONE ASSEMBLIES" (or most current issue in force).
- E. FAA AC No. 150/5345-43F "SPECIFICATION FOR OBSTRUCTION LIGHTING EQUIPMENT" (or most current issue in force).
- F. FAA AC No. 150/5345-53 "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM" (most current issue) and AC150/5345-53C, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum.
- G. UL Standard 6 Rigid Metal Conduit.
- H. UL Standard 514B Conduit, Tubing and Cable Fittings.
- <u>107-1.3 SHOP DRAWINGS.</u> The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for wind cones and materials to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:
- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Cut sheets with part number and specifications for each wind cone.
- D. Concrete mix design.

ground rods.

E. Provide cut sheets with manufacturer's name, catalog number, dimensions, material and UL listing for each type and size ground rod. Include certification of 100% domestic steel for

F. Provide cut sheets for all types of conduit used with the wind cones (for example galvanized rigid steel conduit). Include certification that steel conduits are made with 100 percent domestic steel.

EQUIPMENT AND MATERIALS

107-2.2 WIND CONES. Add the following:

"L-806 wind cones shall be manufactured to Federal Aviation Administration (FAA) Specification AC 150/5345-27D (or current edition in force) and shall be FAA-approved (ETL-Certified). Wind cone shall be a Type L-806, Style I externally lighted, Size 1 (18 in. by 8 ft) orange nylon windsock, 6.6 Amp series circuit power, mounted on a frangible base pole. Pole and support structure shall be factory-painted "Aviation Orange". Wind cone shall be equipped with an L-810 obstruction light mounted on the top of the mast. Overall height of wind cone and support assembly shall not exceed 10 ft. Wind cone lighting shall provide constant-brightness series circuit power adapter suitable for operation on a three step (4.8 Amp, 5.5 Amp, and 6.6 Amp) series circuit. Include a series circuit isolation transformer rated for the respective wind cone and compatible with the respective series circuit power. Note: The constant current regulator powering the series circuit for the wind cones has been sized for the respective runway lighting loads and wind cones that have a load of less than 150 VA and do not require a series isolation transformer larger than a 300 Watt rating. In the event that a wind cone is proposed that exceeds this rating, the Contractor shall be responsible to ensure that the respective constant current regulator is properly sized for the total series circuit load. Where a wind cone is proposed that requires loads that exceed the rating of the respective constant current regulator, the Contractor shall be responsible for all adjustments including providing a larger constant current regulator and all associated circuit breakers, conduits, wiring and vault work as applicable to accommodate the respective series circuit load with the wind cones. Contractor shall confirm part number and special options with the respective manufacturer for compliance with these Special Provisions. Include sufficient slack cable with the wind cone to allow connection to the respective series transformer in an adjacent splice can. Include manufacturer's specified anchor bolts."

L-807 wind cone and assemblies shall be manufactured to Federal Aviation Administration (FAA) Specification AC 150/5345-27D (or current edition in force) and shall be FAA-approved (ETL-Certified). Wind cone shall be a Type L-807, Style I-B (internally lighted), Size 2 – (36-inch diameter by 12-feet long for use with Type L-807 assemblies), 6.6 Amp series circuit power. Color of wind sock shall be orange. Wind cone shall be mounted on a 16-ft center hinged steel pole complying with the requirements of FAA AC 150/5345-27. Pole shall include a positive locking anti-slip brake winch for ease of lowering the basket, changing the windsock, and changing the

Illinois Project: FWC-4105

lamps. Wind cone shall be equipped with an FAA approved L-810 obstruction light on the top of the mast. Wind cone lighting shall provide constant-brightness series circuit power adapter suitable for operation on a three step (4.8 Amp, 5.5 Amp, and 6.6 Amp) series circuit. Include a series circuit isolation transformer rated for the respective wind cone and compatible with the respective series circuit power. Note: The constant current regulator powering the series circuit for the wind cones has been sized for the respective runway lighting loads and wind cones that have a load of less than 200 VA and do not require a series isolation transformer larger than a 300 Watt rating. In the event that a wind cone is proposed that exceeds this rating, the Contractor shall be responsible to ensure that the respective constant current regulator is properly sized for the total series circuit load. Where a wind cone is proposed that requires loads that exceed the rating of the respective constant current regulator, the Contractor shall be responsible for all adjustments including providing a larger constant current regulator and all associated circuit breakers, conduits, wiring and vault work as applicable to accommodate the respective series circuit load with the wind cone. Contractor shall confirm part number and special options with the respective manufacturer for compliance with these Special Provisions. Include sufficient slack cable with the wind cone to allow connection to the respective series transformer in an adjacent splice can. Include manufacturer's specified anchor bolts"

<u>107-2.3 WIRE.</u> Revise this section to read as follows:

"Cable and wiring associated with the wind cone installations shall be as detailed on the Plans, as specified herein, and shall also comply with Item 108.

Cable in unit duct from the point of connection to the respective power source to the point of connection to the respective wind cone installation is not included with this item, and shall be paid for separately under Item 108."

107-2.4 CONDUIT. Revise this section at follows:

"Rigid Steel Conduit and fittings shall be hot-dipped, galvanized, UL-listed, and produced in accordance with UL Standard 6 – Rigid Metal Conduit and ANSI C80.1 – Rigid Steel Conduit, Zinc Coated. Couplings, connectors, and fittings for rigid steel conduit shall be threaded, galvanized steel or galvanized, malleable iron, specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 – Fittings Rigid Metal Conduit and EMT and UL 514B – Conduit, Tubing, and Cable Fittings. Set screw type fittings are not acceptable. Steel used to manufacture conduits shall be 100 percent domestic steel. Contractor shall provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.

Conduit for grounding electrode conductors shall be Schedule 40 PVC conduit, and shall comply with Item 110 and the following: Conduit shall be Schedule 40 PVC, 90°C, ULrated, or approved equal. Material shall comply with NEMA Specification TC-2 (Conduit),

Illinois Project: FWC-4105

(Fittings UL-514), and UL-651 (Standard for rigid, non-metallic conduit)."

<u>107-2.5 CONCRETE</u>. Add the following:

"Foundation for the L-806 wind cone shall be 24-in. diameter by 60-in. deep (minimum). Coordinate the installation of a 2-in. GRSC/elbow into the foundation for the power wiring. Coordinate the installation of a 1-in. Schedule 40 PVC conduit/elbow into the foundation for the grounding electrode conductor. Include reinforcing steel, as detailed on the Plans. Coordinate installation of the wind cone foundation with the concrete pad that surrounds the foundation and associated L-867 splice can."

Foundation for the L-807 wind cone shall be 24 in. diameter by 84 in. deep (minimum). Coordinate the installation of a 2-inch, galvanized, rigid steel conduit (GRSC)/elbow into the foundation for the power wiring. Coordinate the installation of a 3/4-inch Schedule 40 PVC conduit/elbow into the foundation for the grounding electrode conductor. Include reinforcing steel, as detailed on the Plans. Steel used to manufacture rebar shall be 100 percent domestic steel."

107-2.7 SPLICE CANS. Splice cans shall conform to the requirements of FAA AC 150/5345-42D for Type L-867, Class IA, Size B (12-in. nominal diameter), 24 in. deep. Splice cans shall have galvanized steel covers, 3/8-in. minimum thick, with stainless steel bolts. Splice cans shall include internal and external ground lugs. A splice can shall be provided to house the series circuit isolation transformer and cable connections, and shall be located adjacent to the wind cone foundation. Larger size splice cans shall be provided, where necessary, to accommodate the respective series circuit isolation transformer(s) and cable connections. This splice can shall be bonded to the respective ground rod located at the wind cone foundation with a #6 AWG bare copper conductor. Splice cans shall not be used as a base for the wind cone.

<u>107-2.8 SERIES CIRCUIT TRANSFORMER.</u> Series circuit isolation transformers for the wind cones shall be manufactured to FAA Specification AC 150/5345-47B (or current edition in force), and shall be FAA-approved (ETL-Certified). Series circuit transformer shall be properly sized for the respective wind cone lighting loads, and shall be as recommended by the respective wind cone manufacturer. Confirm proper transformer selection and sizing with the respective wind cone manufacturer.

<u>107-2.9 GROUND RODS.</u> Ground rods shall be 3/4-in. diameter, 10 ft long, UL-listed, copper-clad with 10-mil. minimum copper coating. Steel used to manufacture ground rods shall be 100% domestic steel.

CONSTRUCTION METHODS

107-3.1 INSTALLATION. Add the following:

"The support pole shall be installed on a concrete foundation, as detailed on the Plans. The Contractor shall furnish and install all electrical materials necessary for complete and

Illinois Project: FWC-4105

operational installation of each wind cone, as detailed herein and in accordance with the manufacturer's instructions. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of NFPA 70 - National Electrical Code (NEC), most current issue in force. Wind cones shall be installed in conformance with the respective manufacturer's directions and recommendations for the respective application. Any installations which void the UL listing, ETL listing (or other third party listing), and/or the manufacturer's warranty of a device will not be permitted.

The Contractor shall keep a copy of the latest NEC in force on site at all times during construction for use as a reference.

The Contractor should examine the proposed site to evaluate the complexity of the work.

Contractor shall coordinate work and any power outages to airfield lighting systems, buildings or facilities located on the Airport with the Airport Manager. Where FAA facilities are affected, the Contractor shall coordinate work and any power outages with the Airport Manager and the respective FAA personnel. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures, including, but not limited to, 29 CFR Section 1910.147 The Control of Hazardous Energy (lockout/tagout).

The Contractor shall be responsible for furnishing and setting all anchor bolts required to install his equipment.

Where concrete mounting pads, foundations, or piers are required for equipment mounting, the Contractor shall furnish all concreting and form work necessary to complete the installation. Concrete shall conform to Item 610 Structural Portland Cement Concrete of the Standard Specifications."

<u>107-3.2.</u> COUNTERWEIGHT. Delete this section.

<u>107-3.3 ELECTRICAL CONNECTION.</u> Add the following:

"Splices in conductors will be allowed only within the specified junction boxes, splice cans, or electrical handholes. Circuit conductors for power wiring shall be continuous from source of power to connected device, unless otherwise approved by the Resident Engineer. Spliced connections of the wind cone conductors to the cable in unit duct feeder conductors shall be installed at the handhole access at the base of the wind cone pole or in an L-867 base/splice can."

107-3.5 GROUND CONNECTION AND GROUND ROD. Revise this section as follows:

Illinois Project: FWC-4105

"The Contractor shall furnish and install a ground rod, grounding electrode conductor cable, ground clamps/connectors, and exothermic weld connections for grounding the wind cone pole support near the base. The ground rod shall be 3/4- in. diameter by 10 ft long, UL-listed, copper-clad with 10-mil. minimum copper coating. The ground rod shall be driven into the ground adjacent to the concrete foundation so that the top of the rod is at least 30-in. below grade. Buried or concealed ground systems shall be observed by the Resident Engineer before backfilling or covering. The grounding electrode conductor shall consist of No. 6 AWG bare-stranded copper wire or larger. All connections to ground rods and/or buried grounding electrode conductors shall be made with exothermic weld-type connectors, Cadweld by Erico Products, Inc., Solon, Ohio, (Phone: 800-248-9353), Thermoweld by Continental Industries, Inc., Tulsa, Oklahoma (Phone: 918-663-1440) or Ultraweld by Harger, Grayslake, Illinois (Phone: 800-842-7437), or approved Exothermic weld connections shall be installed in conformance with the respective manufacturer's directions using molds as required for each respective application. Bolted connections will not be permitted at ground rods. The other end of the grounding electrode conductor shall be securely attached to the base of the wind cone pipe support with a UL-listed grounding connector or pipe clamp suitable for the respective application. Metallic surfaces to be joined shall be prepared by the removal of all non-conductive material (including paint) per 2008 NEC, Article 250-12. All bolted or mechanical connections shall be coated with a corrosion preventative compound before joining, Sanchem Inc. "NO-OX-ID "A-Special" compound, Burndy Penetrox E, or equal. Coordinate the installation of a 3/4-in. Schedule 40 PVC conduit into the wind cone foundation to accommodate the grounding electrode conductor. The resistance to ground shall not exceed 25 Ohms. Contractor shall test the made electrode ground rod installation with an instrument specifically designed for testing ground field systems. If ground resistance exceeds 25 Ohms, contact the Resident Engineer for further direction. Copies of ground rod test results shall be furnished to the Resident Engineer."

107-3.6 PAINTING. Add the following:

"The pole, and any support structure and the exposed, non-stainless components of the wind cone shall be **factory painted – aviation orange**."

107-3.7 LAMPS. Revise this section as follows:

"The Contractor shall furnish and install all lamps required as per manufacturer's recommendation."

107-3.8 CHAIN AND PADLOCK. Delete this section.

<u>107-3.9 RESTORATION.</u> All turf areas disturbed by the installation of the wind cone and associated work shall be restored, graded, and seeded to establish a stand of grass to the satisfaction of the Engineer and will be considered as incidental to the installation of each wind cone.

Illinois Project: FWC-4105

Fairfield Municipal Airport

A.I.P. Project: 3-17-0043-B12

107-3.10 INSTRUCTION OF AIRPORT STAFF. Contractor shall provide instruction to airport staff in regard to the operation and maintenance of the wind cones and associated equipment.

Contractor shall demonstrate operating procedures, lamp changing procedures, and items requiring maintenance. Contractor shall furnish operation and maintenance manuals for wind

cones and associated equipment.

METHOD OF MEASUREMENT

107-4.1. Add the following:

"L-867 splice cans associated with the wind cone installations shall be incidental to the respective wind cone pay item and no additional compensation will be made."

BASIS OF PAYMENT

<u>107-5.1.</u> Payment will be made at the contract unit price per each unit installed and accepted by the Engineer. This price shall be full compensation for furnishing all materials, preparation, assembly, and installation of these materials; and for all labor, equipment, tools, and incidentals necessary to complete this Item. The quantity of cable in unit duct from the respective power source, to the respective wind cone shall be paid for separately under Item 108.

Payment will be made under:

Item AR107408 L-806 Wind Cone-8' Lighted - per each Item AR107712 L-807 Wind Cone-12' Lighted - per each

END OF ITEM 107

Illinois Project: FWC-4105

ITEM AR107900 REMOVE WIND CONE

DESCRIPTION

<u>107900-1.1.</u> This item of work shall consist of the removal of the existing primary wind cone including the support pole and base/foundation.

107900-1.2 REFERENCES.

- A. FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- B. NFPA 70E Standard for Electrical Safety in the Workplace
- C. OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures

CONSTRUCTION

107900-2.1 REMOVAL OF WIND CONE.

- A. Contractor shall examine the site to determine the extent of the work.
- B. Contractor shall coordinate work and any power outages with the Airport Manager or respective Airport personnel. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures, including, but not limited to, 29 CFR Section 1910.147 The Control of Hazardous Energy (lockout/tagout).
- C. Contractor shall comply with the requirements of FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- D. Contractor shall comply with the applicable requirements of NFPA 70E Standard for Electrical Safety in the Workplace.
- E. Power for each respective wind cone shall be disconnected at the respective power source prior to removing the respective wind cone. Power for the existing primary wind cone is understood to be powered from the Airport Electrical Vault. Contractor shall field verify to confirm the respective power source for each wind cone.

Illinois Project: FWC-4105

F. The Contractor shall coordinate the removal of the existing wind cone with the installation of the new lighted wind cone to minimize the time when the airport is without a wind cone. The Contractor shall also coordinate with and notify the Airport Manager and the Resident Engineer and provide a schedule for the wind cone removal and the new wind cone installation. The Contractor will turn the wind cone and support pole over to the Airport Manager. The concrete base/foundation will be disposed of off the airport site, in a legal manner, at the expense of the Contractor.

G. The holes left from the base/foundation removal will be filled with earth material. The earth material will be compacted to prevent any future settlement. The earth material will be obtained from off the airport site. The disturbed area will be limed, fertilized, and seeded in accordance with item 901. The liming, fertilizing, and seeding will be considered as an incidental item to the removal of the wind cone.

BASIS OF PAYMENT

107900-3.1. This work will be paid for at the contract unit bid price per each for Wind Cone Removal. Said price and payment shall constitute full compensation for removing the existing wind cone, support pole, base/foundation; for all excavating and backfilling, for furnishing all earth materials, labor, tools, equipment, and incidentals necessary to complete this item of work.

Payment will be made under:

Item AR107900 Remove Wind Cone - per each

END OF ITEM AR107900

Illinois Project: FWC-4105

ITEM 108 INSTALLATION OF UNDERGROUND CABLE FOR AIRPORTS

DESCRIPTION

108-1.1. Add the following to this section:

"This Item of work shall consist of the installation (plowing, trenching, directional-boring, or installing in ducts or raceways) of cable for airfield lighting circuits and/or navaid circuits on the runways, taxiways, aprons, and the associated homeruns at the locations shown on the Plans and in accordance with these Specifications. This Item shall include cable in unit duct where noted on the Plans and specified herein.

In areas where there is a congestion of buried cable or where the proposed cable crosses an existing cable, the Contractor will be required to trench the proposed cable into place. In all other areas, the Contractor has the option to either trench or plow the proposed cable in unit duct into place.

When crossing existing circuits, the Contractor will be required to hand dig the trenches for the proposed cable."

108-1.2 REFERENCES.

- A. ASTM Specification B3 Standard Specification for Soft or Annealed Copper Wire.
- B. ASTM Specification B8 Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft.
- C. FAA Advisory Circular 150/5345-7E, (or latest edition) "SPECIFICATIONS FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS.
- D. FAA AC No. 150/5345-53 "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM" (most current issue) and AC150/5345-53C, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum.
- E. FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- F. Federal Specification A-A-59544 Cable and Wire, Electrical (Power, Fixed Installation).
- G. NFPA 70 National Electrical Code (most current issue in force).
- H. NFPA 70E Standard for Electrical Safety in the Workplace.
- I. OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.

Illinois Project: FWC-4105

- J. UL Standard 44 Thermoset-Insulated Wires and Cables.
- K. UL Standard 83 Thermoplastic-Insulated Wires and Cables.
- L. UL Standard 854 Service Entrance Cables.
- <u>108-1.3 SHOP DRAWINGS.</u> The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for each wire, conductor, and/or cable type to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:
- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials, the Contractor shall furnish complete statements to the Project Engineer as to the origin, composition, and manufacturer of all material to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials.
- C. Indicate the pay item number for each respective cable and/or cable in unit duct.
- D. Shop drawings shall include wire/conductor/cable cut sheets with type, size, specifications, ETL or UL listing, manufacturer, and catalog or part number.
- E. Shop drawings for cable in unit duct items shall include cut sheets with type, size, specifications, ETL or UL listing, manufacturer, and catalog or part number for the respective unit duct.
- F. Where cable is required to have colored coded insulation, provide information on the color coding for the respective conductors.

EQUIPMENT AND MATERIALS

108-2.1 GENERAL. Add the following.

"All cable shall be FAA approved or UL-listed as suitable for installed application. Cable furnished on this project shall comply with the requirements of the "Buy American Act". All conductors shall be copper.

<u>108-2.2 CABLE.</u> Revise this section to read as follows:

Illinois Project: FWC-4105

"L-824 Cable – L-824 cable shall be FAA L-824, Type C and shall conform to the requirements of FAA Advisory Circular 150/5345-7E, (or latest edition) "SPECIFICATIONS FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS". L-824 cable shall be FAA approved and listed in the current AC150/5345-53C, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum. Circuits for use with constant current regulator outputs (runway or taxiway lighting circuits) shall use 5000-Volt rated cable.

Cable for use with airfield lighting series circuits (including runway lighting, taxiway lighting and taxi guidance signs) shall be one conductor No. 8, 5,000-Volt, FAA L-824, Type C, stranded.

Item AR108158, 1/C #8 5KV UG Cable in UD shall be one conductor No. 8, 5,000-Volt, FAA L-824, Type C, stranded, in unit duct (3/4-in.).

XLP-USE Wire. Cable shall comply with UL Standard 44, UL Standard 854, and Federal Specification A-A-59544. Conductor shall be concentric-strand, soft copper, conforming to ASTM B8 and Underwriters' Laboratories Standard UL44 for Rubber Insulated Wires. Insulation shall be rated for 600-Volt. Insulation shall be cross-linked polyethylene conforming to Underwriter's Laboratories Requirements for Type USE-2 insulation. Cable shall be UL-listed and marked USE-2. Cable shall be Service Wire Company Type USE-2, or approved equal.

Item AR108084 1/C #4 XLP-USE shall consist of 1/C #4 AWG, XLP-USE, 600-Volt cable installed in conduit, ducts, handholes, and manholes from the Vault to the respective handhole/manhole, and between handholes/manholes that are connected through a duct bank. Conductor insulation for 120/240 VAC, single-phase, 3-wire with ground circuits shall be color-coded: Phase A – Black, Phase B – Red, Neutral – White, and Ground – Green.

Item AR108086 1/C #6 XLP-USE shall consist of 1/C #6 AWG, XLP-USE, 600-Volt cable installed in conduit, ducts, handholes, and manholes from the Vault to the respective handhole/manhole, and between handholes/manholes that are connected through a duct bank. Conductor insulation for 120/240 VAC, single-phase, 3-wire with ground circuits shall be color-coded: Phase A – Black, Phase B – Red, Neutral – White, and Ground – Green.

Item AR108654, 3/C #4 600 V UG Cable In UD shall consist of 3-1/C #4 AWG, XLP-USE, 600 volt cable in unit duct (1.25-inch or sized larger as required per NEC). Conductor insulation for 120 VAC, 1 phase, 2-wire with ground circuits shall be color-coded: Phase A – Black, (Note for Phase B – Cable insulation shall be Red or Black with red tape at points of access), Neutral - White, and Ground – Green.

Item AR108656, 3/C #6 600 V UG Cable In UD shall consist of 3-1/C #6 AWG, XLP-USE, 600 volt cable in unit duct (1.25-inch or sized larger as required per NEC). Conductor insulation for 120 VAC, 1 phase, 2-wire with ground circuits shall be

Illinois Project: FWC-4105

color-coded: Phase A – Black, (Note for Phase B – Cable insulation shall be Red or Black with red tape at points of access), Neutral - White, and Ground – Green.

<u>Color-coding:</u> Color-code phase and neutral conductor insulation for No. 6 AWG or smaller. Provide colored marking tape or colored insulation for phase and neutral conductors for No. 4 AWG and larger. **Insulated ground conductors shall have green colored insulation for all conductor sizes (AWG and/or KCMIL) to comply with NEC 250.119.** Neutral conductors shall have white colored insulation for No. 6 AWG and smaller to meet the requirements of NEC 200.6. Standard colors for power wiring and branch circuits for 120/240 VAC, 1-Phase, 3-Wire system shall be Phase A – Black, Phase B – Red, Neutral – White, and Ground – Green. Standard colors for power wiring and branch circuits for 480 VAC (line to neutral or grounded conductor), 1-Phase, 3-Wire system shall be Phase A – Black (with Brown tape at points of access) Neutral or Grounded Conductor—White or Gray, and Ground – Green.

The wiring associated with the airport electrical vault work will be paid for under Item AR109200 Install Electrical Equipment - per lump sum."

108-2.3 BARE COPPER WIRE (COUNTERPOISE). Revise this section to read:

"Bare copper counterpoise wire will not be required on this project under Item 108."

<u>108-2.4 CABLE CONNECTIONS.</u> Add the following to this section:

"The Contractor will use a cable stripper/penciller whenever cable connections are made."

All breaks in the unit duct shall be sealed by shrink kits.

All below grade splices shall be installed in splice cans, handholes, or manholes. Splice cans shall be L-867, Class IA, Size B (12 in. diameter), 24 in. deep, with ½ in. thick, galvanized steel cover and stainless steel bolts. Larger size splice cans shall be provided, as applicable, for specific equipment applications or manufacturer's recommendations, and/or where detailed on the Plans. Splice cans located in areas subject to heavy aircraft or vehicle loading shall be L-868 type. The Engineer shall approve all splice locations before work commences. The furnishing and installing of splice cans for new homerun cables shall be incidental to the respective cable pay item, and no additional compensation will be allowed."

108-2.12 LINE MARKING TAPE. Delete this section.

108-2.13 UNIT DUCT. Add the following:

"Standard sizes of smooth wall polyethylene duct shall conform to the dimensional requirements specified below:

Illinois Project: FWC-4105

	Nominal	Nominal	Nominal
Nominal	Inside	Standard	Outside
Duct Size	Diameter	Wall	Diameter*
3/4"	0.910"	0.070"	1.050"
1"	1.145"	0.085"	1.315"
1-1/4"	1.440"	0.110"	1.660"
1-1/2"	1.650"	0.125"	1.900"
2"	2.065"	0.155"	2.375"
2-1/2"	2.449"	0.213"	2.875"
3"	3.048"	0.226"	3.500"
4"	4.000"	0.250"	4.500"

^{*} Dimensions include allowance for duct eccentricity."

CONSTRUCTION METHODS

108-3.1 GENERAL. Add the following to this section:

"The cable quantities as shown on the Construction plans are based on straight-line measurement. All other cable lengths, such as slack or waste, will not be measured for payment.

If the Contractor wishes to lay cable on a line other than that shown on the Plans, he shall obtain approval of the Resident Engineer before doing so. Any additional cable needed because of such change will be at the Contractor's expense.

Only cable in unit duct may be plowed or directional-bored.

The Contractor shall identify all existing underground utilities located within the area where the proposed cables are being installed, and will take all precautions to protect these utilities from damage. Care shall be taken so as not to damage any existing circuits. Any existing circuits damaged shall be immediately repaired to the satisfaction of the Engineer and/or the respective utility or owner where applicable. Any underground utility damaged will be repaired or replaced at the Contractor's own expense. Any repairs of existing cables will be considered incidental to the contract, and no additional compensation will be allowed.

Contractor shall coordinate work and any power outages with the Airport Manager or respective Airport personnel. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures, including, but not limited to, 29 CFR Section 1910.147 The Control of Hazardous Energy (lockout/tagout).

Illinois Project: FWC-4105

Contractor shall comply with the requirements of FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".

Contractor shall comply with the applicable requirements of NFPA 70E – Standard for Electrical Safety in the Workplace.

All temporary installations shall comply with National Electrical Code Article 590 – "Temporary Installations". The contractor shall secure, identify, and place temporary exposed wiring in conduit, duct, or unit duct to prevent electrocution and fire ignition sources in conformance with the requirements of FAA AC 150/5370-2E, Part 3-6, c.

All cables installed by the Contractor shall be properly labeled and tagged at all points of access (handholes, manholes, terminal panels, control panels, and the respective wireway in the vault).

All changes to the airfield lighting system shall be documented by the Contractor and provided to the Airport Representative."

108-3.2 INSTALLATION IN DUCT OR CONDUIT. Add the following to this section:

"The unit duct will be run continuous through all ducts and conduits."

Where cable in unit duct enters a handhole with a continuous duct bank system to the termination point (such as from a handhole to the vault or between handholes) the unit duct will not be required for the respective cable."

108-3.3 TRENCHING. Add the following to this section:

- "F. Cable installed in cultivated fields shall be installed a minimum of 42 in. below grade.
- G. Any and all trenches will be backfilled to a smooth grade to the satisfaction of the Engineer. All trench settlement shall be corrected for a period of one year. Restoration, grading, and seeding of areas disturbed during the installation of the proposed cable will be incidental to the respective 108 Pay Item."

108-3.5 SPLICING. Add the following:

"In-line connections for existing cables cut during construction shall be repaired with a cast splice kit. The Contractor shall have a minimum of two splice kits on the job site at all times for emergency repairs. Cast splice kits shall be specified in paragraph (a) of Item 108-2.4. Splice cans shall be provided for existing cables cut and repaired for each splice in cables not to be abandoned. Where a splice can is not readily available at the time of the cable damage, splice markers shall be temporarily

Illinois Project: FWC-4105

installed over each splice in cables not to be abandoned, then these splices shall later be replaced with new splices in an L-867 splice can.

There shall be no splices between series lighting circuit isolation transformers. In the event that a series lighting circuit cable is cut between isolation transformers, the entire length of cable between these isolation transformers shall be replaced."

108-3.6 BARE COUNTERPOISE WIRE INSTALLATION AND GROUNDING FOR LIGHTNING PROTECTION. Revise this section to read as follows:

"Bare copper counterpoise wire will not be required on this project under Item 108."

108-3.8 TESTING. Add the following.

"K. Prior to beginning cable installation all existing series circuit cables shall be Megger tested and recorded at the vault. All existing series circuit cable loops shall have the resistance tested and recorded for each circuit at the vault."

108-3.12 LOCATING OF EXISTING UNDERGROUND UTILITIES AND CABLES. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor's responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans, and shall obtain, from the respective utility companies, detailed information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner's Representative and/or the Resident Engineer shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract.

All utility cables and lines shall be located by the respective utility. Contact JULIE (Joint Utility Location Information for Excavators) for utility information, phone: 1-800-892-0123. Contact the FAA (Federal Aviation Administration) for assistance in locating FAA cables and utilities. Location of FAA power, control, and communication cables shall be coordinated with and/or located by the FAA. Also contact Airport Director/Manager and Airport Personnel for assistance in locating underground Airport cables and/or utilities. Also coordinate work with all aboveground utilities.

Payment for locating and marking underground utilities and cables will not be paid for separately, but shall be considered incidental to the plowing/trenching/boring of cable and cable in unit duct.

Illinois Project: FWC-4105

108-3.13 SEPARATION OF HIGH-VOLTAGE AND LOW-VOLTAGE WIRING. Low-voltage wiring shall maintain separation from high-voltage wiring. Low-voltage wiring and high-voltage wiring shall not be installed in the same raceway, handhole, or junction box. Where necessary provide split flexible duct around low voltage cables located in a handhole with high voltage cables, to isolate the cables from possible contact with each other.

METHOD OF MEASUREMENT

<u>108-4.2.</u> Revise this section to read as follows:

"The footage of cable installed in duct, conduit, or raceway to be paid for shall be the number of linear feet of cable installed in duct, conduit, or raceway measured in place by direct measurement, completed, ready for operation and accepted as satisfactory with no allowance being made for overrun due to slack, turns, splices, etc. Slack cable required to perform cable splices outside of the respective splice cans, handholes, or manholes, shall be incidental to the respective cable pay item and no additional measurement for payment will be made. Cable will be measured for payment from the respective termination or splice point in the field up to the vault. Cable or cable in unit duct installed inside or below the vault shall be incidental to Item AR109200 and no additional measurement for payment will be made."

BASIS OF PAYMENT

<u>108-5.1.</u> Payment will be made at the contract unit price per lin. ft of cable completed and accepted by the Engineer. This price shall be full compensation for furnishing all materials, and for all preparation, assembly, and installation of these materials; for all plowing, trenching, directional-boring, coring of manholes or handholes, installation in ducts, raceways, conduits, splice cans, handholes, or manholes, and for all excavation and backfilling; for all site restoration (topsoiling, grading, seeding, mulching) and pavement restoration; and for all labor, equipment, tools, and incidentals necessary to complete this Item.

Payment will be made under:

Item AR108084 1/C #4 XLP-USE - per linear foot
Item AR108086 1/C #6 XLP-USE - per linear foot
Item AR108158, 1/C #8 5KV UG Cable in UD - per linear foot
Item AR108654, 3/C #4 600 V UG Cable in UD - per linear foot
Item AR108656, 3/C #6 600 V UG Cable in UD - per linear foot

END OF ITEM 108

Illinois Project: FWC-4105

ITEM 109 INSTALLATION OF AIRPORT TRANSFORMER VAULT AND VAULT EQUIPMENT

DESCRIPTION

109-1.2. Item AR109200 "Install Electrical Equipment" shall consist of furnishing and installing electrical equipment inside the vault to perform the vault upgrades as detailed on the Plans and specified herein. This item shall include all labor, materials, transportation, equipment, wiring, raceways, grounding, warranties, tools, coordination, relocations, operational instructions, labeling, testing, and all incidentals required to place the vault and associated equipment into proper working order as a completed unit to the satisfaction of the Owner and Engineer.

Included under this item shall be the following:

- A. Field verification of existing site conditions to determine complexity of the proposed work.
- B. Coordinating all work with the Airport Manager, the designated Airport Maintenance Staff, and the Resident Engineer.
- C. Furnishing and installing all associated electrical equipment, support hardware, raceways, conduits, cable, wiring, grounding, and accessories as detailed on the Plans and specified herein.
- D. Furnishing and installing all pull boxes, junction boxes, wireways, raceways, conduits, conduit fittings, and ducts within or at the vault.
- E. Furnishing and installing all necessary cable and wiring within or at the vault, as detailed on the Plans and specified herein.
- F. Furnishing and installing all grounding and surge protection as detailed on the Plans and specified herein.
- G. Locating, identifying, relocating, and/or replacing existing airfield lighting cables, power cables, and control wiring, as necessary to disconnect these respective cables and wiring from the existing equipment and reconnect, replace and/or interface these respective cables to the new or relocated equipment. All work shall be coordinated with the Airport Manager and shall be coordinated to minimize down time to the respective airfield systems.
- H. Removal and/or relocation of existing equipment and/or materials.
- I. Identifying and labeling all control wiring associated with the control circuit upgrades.
- J. Furnishing shop drawings for new equipment and materials.

Illinois Project: FWC-4105

- Illinois Project: FWC-4105 A.I.P. Project: 3-17-0043-B12
- K. Testing, adjusting, and retesting (where applicable) all new equipment and modifications to existing systems for proper operation.
- L. Labeling all electrical equipment and incidentals necessary to place all of the equipment in operation as a complete unit acceptable to the Owner and Engineer.
- M. Furnishing operation, maintenance, and installation manuals for all new equipment.

109-1.3 REFERENCES

- A. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 Fittings Rigid Metal Conduit and EMT.
- C. ANSI Z535.4-2002 American National Standard for Product Safety Signs and Labels.
- D. ASTM Specification B3 Standard Specification for Soft or Annealed Copper Wire.
- E. ASTM Specification B8 Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft.
- F. Federal Specification A-A-59544 Cable and Wire, Electrical (Power, Fixed Installation).
- G. FAA AC No. 150/5340-26B "MAINTENANCE OF AIRPORT VISUAL AID FACILITIES".
- H. FAA AC No. 150/5340-30E "DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS".
- I. FAA AC No. 150/5345-7E, (or latest edition) "SPECIFICATIONS FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS.
- J. FAA AC No. 150/5345-53 "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM" (most current issue) and AC150/5345-53C, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum.
- K. FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- L. FAA-STD-019d dated August 9, 2002, Department of Transportation, Federal Aviation Administration Standard, LIGHTNING AND SURGE PROTECTION, GROUNDING, BONDING, AND SHIELDING REQUIREMENTS FOR FACILITIES AND ELECTRONIC EQUIPMENT.
- M. FAA-STD-019e, December 22, 2005, Department of Transportation, Federal Aviation Administration Standard, LIGHTNING AND SURGE PROTECTION, GROUNDING,

BONDING AND SHIELDING REQUIREMENTS FOR FACILITIES AND ELECTRONIC EQUIPMENT.

- N. NFPA 70 National Electrical Code (most current issue in force).
- O. NFPA 70E Standard for Electrical Safety in the Workplace.
- P. OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.
- Q. UL Standard 6 Rigid Metal Conduit.
- R. UL Standard 44 Thermoset-Insulated Wires and Cables.
- S. UL Standard 83 Thermoplastic-Insulated Wires and Cables.
- T. UL Standard 467 Grounding and Bonding Equipment.
- U. UL Standard 486A-486B Wire Connectors.
- V. UL Standard 514B Conduit, Tubing and Cable Fittings.

109-1.4 SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for vault equipment and materials to be used on the project. Shop drawings shall be clear and legible. Copies that are illegible will be rejected. Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop Drawings shall clearly indicate proposed items, capacities, characteristics, and details in conformance with the Plans and Specifications. The respective manufacturer shall certify capacities, dimensions, special features, etc. When a submittal is marked "Revise and Resubmit", "Rejected", and/or "Not Approved", do not proceed with that part of the work covered by the submittal, including purchasing, fabrication, delivery, or other activity. Revise or prepare a new submittal in accordance with the notations, resubmit, and repeat if necessary to obtain a different action mark such as "No Exceptions Taken" or "Furnish as Corrected". Contractor is responsible for compliance with the specified characteristics. Contractor's responsibility for error and omissions in submittals is not relieved by the Engineer's review of submittals. Accompany each submittal with a transmittal letter that includes the date, project title and number, Contractor's name and address, the number of Shop Drawings, product data and/or samples submitted, notification of any deviations from the Contract, and any other pertinent information. Shop drawings shall include the following information:

A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.

Illinois Project: FWC-4105

- Illinois Project: FWC-4105 A.I.P. Project: 3-17-0043-B12
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Furnish shop drawings for the Lighting Contactor Control Panel for the Airport Navaids and airfield lighting systems at the Vault. Shop drawings shall include panel layout, bill of materials, cut sheets for lighting contactors and materials, terminal block arrangement, and wiring diagram for the panel.
- D. Cut sheets with part number and specification for surge protective device.
- E. Provide cut sheets for all types of conduit used in the vault (for example galvanized rigid steel conduit and UL listed liquid tight flexible metal conduit). Include certification that steel conduits are made with 100 percent domestic steel.
- F. Provide cut sheets for the power and control circuit conductors.
- G. Provide cut sheets for the fire extinguishers.

EQUIPMENT AND MATERIALS

109-2.1 GENERAL. Add the following to this section:

- "C. FAA approval of airport lighting equipment and subsequent inclusion in Advisory Circular 150/5345-1 "Approved Airport Equipment", and/or Advisory Circular 150/5345-53 "Airport Lighting Equipment Certification Program" only means that the test data satisfied the applicable Specification requirements. This does not insure that the approved equipment will satisfactorily operate when connected power-wise and/or control-wise to other approved airport lighting equipment or "off the shelf" equipment not requiring FAA approval.
- D. The Contractor shall ascertain that all lighting system components furnished by him (including FAA-approved equipment) are compatible in all respects with each other and the remainder of the new system. Any non-compatible components furnished by the Contractor shall be replaced by him, at no additional cost to the Airport Sponsor, with a similar unit approved by the Engineer (different model or different manufacturer) that is compatible with the remainder of the airport lighting system.
- E. Except as specified otherwise, all new equipment shall be provided by the Contractor and shall be tested for Specification conformance as part of the Aviation Lighting Equipment Certification Program. Certification of

conformance, as tested by the respective testing laboratory, shall be provided by the manufacturer for all items submitted for approval.

Illinois Project: FWC-4105

A.I.P. Project: 3-17-0043-B12

109-2.4 BRICK. Delete this section.

109-2.5 RIGID STEEL CONDUIT. Add the following:

"GRSC shall be heavy wall, hot-dipped, galvanized steel pipe bearing the UL label and conforming to UL-6 and ANSI Specification C80.1. Couplings, connectors, and fittings for rigid steel conduit shall be threaded, galvanized steel, or galvanized malleable iron specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 and UL-514B. Set screw type fittings are not acceptable. Steel used to manufacture conduits shall be 100 percent domestic steel. Contractor shall provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.

Where noted on the Plans Polyvinylchloride (PVC) coated, galvanized rigid steel conduit shall be furnished and installed for additional corrosion protection. PVC coated, galvanized rigid steel conduit and fittings shall be as manufactured by Robroy Industries, Inc., Conduit Division, 1100 US Highway 271 South, Gilmer, Texas 75644, Phone 903-843-5591, Sales Department Fax: 903-843-2516, or approved equivalent. The conduit and fittings, prior to coating, shall be new, unused material, and shall conform to UL 6, Standard for Safety for Rigid Metal Conduit and UL 514B Standard for Safety, Fittings for Conduit and Outlet Boxes. An exterior PVC coating of a nominal 40 mils (.040 in.) shall be applied to the conduit and conduit couplings. The PVC coating shall conform to all applicable requirements of NEMA RN-1, Standard for PVC Coated Conduit. A red urethane coating of 2 mils (.002 in.) shall be uniformly and consistently applied to the interior of conduit and conduit couplings. Conduit or fittings having areas of thin or no interior coating shall be unacceptable. The PVC exterior and urethane interior coatings applied to conduit shall have sufficient flexibility to permit field bending without cracking or flaking at temperatures above 30°F, (-1°C). All male threads on conduit, elbows, and nipples, and all female threads on conduit couplings and fitting shall be protected by application of urethane coating."

109-2.16 POTHEADS. Delete this section.

109-2.17 PRE-FABRICATED METAL HOUSING. Delete this section.

109-2.19 OTHER ELECTRICAL EQUIPMENT. Add the following:

"Switches, cutouts, relays, lighting contactors, terminal blocks, circuit breakers, and all other regularly used commercial items of electrical equipment not covered by FAA equipment specifications shall conform to the applicable rulings and standards of the institute of Electrical and Electronic Engineers or the National Electrical Manufacturer's Association. When specified, test reports from a testing laboratory indicating that the equipment meets the specifications shall be supplied. In all cases,

equipment shall be new and a first-grade product. This equipment shall be supplied in the quantities required for the specific project and shall incorporate the electrical and mechanical characteristics specified in the Plans or in the proposal. Contractor shall confirm quantity for all electrical equipment with the Plans. Equipment and Materials shall be manufactured in the United States to comply with the Airport Improvement Program Buy American Requirements and the Buy American Act. Proposed electrical equipment for the vault shall be as follows:

- A. <u>Lighting Contactor Panel for Airport NAVAIDS</u>. The lighting contactor panel for use with the airfield Navaids and lighting systems shall be as detailed on the Plans. The lighting contactor panel shall be manufactured by an FAA approved L-821 control panel manufacturer or a UL 508 industrial control panel builder and shall be manufactured in the United States to comply with the Airport Improvement Program Buy American Requirements and the Buy American Act.
- B. Surge Protective Device for Vault Panelboard. AC power surge protective device shall be UL-listed per UL 1449, Third Edition, and shall conform to the applicable requirements of FAA-STD-019d dated August 9, 2002, "LIGHTNING AND SURGE PROTECTION, GROUNDING, BONDING, AND SHIELDING REQUIREMENTS FOR FACILITIES AND ELECTRONIC EQUIPMENT". AC power surge arrester/TVSS for the vault panel shall be suitable for a 120/240 VAC, 1-phase, 3-wire, plus ground system with a surge current rating of 240,000-Amps, 8 x 20 microsecond wave per mode (L-L, L-N, L-G, N-G), and status indication lights in a NEMA 12-rated enclosure, Lightning Protection Corporation Model LPC 2020-8U-G, or approved equal. Include six spare indicator lamps with each AC power surge arrester/TVSS.
- C. <u>Circuit Breakers.</u> Branch circuit breakers, to be installed in the existing vault panelboard, shall be compatible with the existing panelboard. Circuit breakers shall be bolt-on type with an amp interrupting capacity of 10,000 Amps minimum at 120/240 VAC. Circuit breaker amperage trip settings and number of poles shall be as detailed on the Plans.
- D. <u>Boost Transformers</u>. Provide boost transformers at the vault for the PLASI circuits as detailed on the Plans. Boost transformers shall be rated to handle the respective equipment loads, suitable for connection as 1200 VAC, 60 Hz, 1 phase, 2-wire input and provide the proper output voltage at the respective PLASI Unit with the PLASI system in operation. Boost transformer shall be UL listed and designed, manufactured, and tested in accordance with ANSI Standard Z535.3 and NEMA ST20 where applicable. Transformer shall be suitable for indoor/outdoor installation with a NEMA 3R weatherproof enclosure. Boost transformers shall be manufactured in the United States to comply with the Airport Improvement Program Buy American Requirement and the "Buy American Act". Confirm proper output voltage for the respective application.

Illinois Project: FWC-4105

- E. <u>Junction and Pull Boxes.</u> Junction and pull boxes shall be sized, as required for conductors and splices and per 2011 NEC Article 314. Boxes shall be UL-listed. Special boxes made to suit conditions shall be used to accommodate the respective application, or where required by the NEC, even though they might not be indicated on the Drawings. Surface-mounted exterior junction and pull boxes located in non-hazardous, non-classified areas shall be NEMA 4X stainless steel or aluminum, Crouse-Hinds, Killark, Hoffman, Hennessy, or equal. All junction and pull boxes installed in classified hazardous areas (Class 1, Division 1 or 2, Group D) shall be NEMA 7 and NEMA 4 and shall comply with applicable provisions of the NEC, including, but not limited to, Articles 500 and 501.
- F. Liquid-Tight Flexible Metal Conduit. Liquid-tight, flexible metal conduit shall consist of polyvinyl jacket over flexible hot dip galvanized steel tubing. The flexible conduit shall be completely sealed from liquids, dust, dirt, and fumes and be resistant to oil, gasoline, grease, and abrasion. Jacket shall also be sunlight-resistant. Liquid-tight flexible metal conduit shall be UL-listed, suitable for use as a grounding conductor, and comply with Article 350 of the NEC. Liquid-tight flexible metal conduit and associated fittings shall be UL-listed to meet the requirements of NEC 350.6. Liquid-tight flexible metal conduit shall be Anaconda Sealtite Type UA as manufactured by Anamet Electrical Inc., 1000 Broadway Avenue East, Mattoon, Illinois 61938-0039, (Phone: 217-234-8844), Liquatite Type LA as manufactured by Electri-Flex Company, 222 W. Central Ave., Roselle, Illinois 60172, (Phone: 630-529-2920 or 1-800-323-6174), or approved equal. Do not install liquid-tight, flexible metal conduit that is not UL listed. Confirm liquid-tight, flexible metal conduit bears the UL label prior to installation."

109-2.20 WIRE. Add the following to Section A. Control Circuits:

"THWN Wire. Cable shall comply with Underwriters' Laboratories Standard UL-83 and Federal Specification A-A-59544. Conductor shall be soft-annealed, uncoated copper and shall comply with ASTM B3 and B8. Insulation shall be rated for 600-Volt. Insulation shall be polyvinyl-chloride conforming to Underwriters' Laboratories requirements for Type THW. The outer covering shall be nylon-conforming to Underwriters' Laboratories for type THHN or THWN. Cable shall be UL-listed and marked THWN."

Delete paragraphs 1, 2, and 3 under Section B. Power Circuits.

Add the following:

"<u>Power Cable (600-Volt and Below)</u>. All power wiring, 600-Volt and below, shall be the type, size, and number of conductors as noted on the Plans.

<u>THWN Wire.</u> Cable shall comply with Underwriters' Laboratories Standard UL-83 and Federal Specification A-A-59544. Conductor shall be soft-annealed, uncoated copper and shall comply with ASTM B3 and B8. Insulation shall be rated for 600-Volt.

Illinois Project: FWC-4105

Insulation shall be polyvinyl-chloride conforming to Underwriters' Laboratories requirements for Type THW. The outer covering shall be nylon-conforming to Underwriters' Laboratories for type THHN or THWN. Cable shall be UL-listed and marked THWN-2. Power and control wiring shall be Type THWN-2, or approved equal. **Note where THWN wiring is referenced on the Plans, it shall be THWN-2.**

XHHW Wire. Cable shall be UL-listed as Type XHHW-2 per UL Standard 44. Cable shall also conform to ICEA S-95-658/NEMA WC70 and Federal Specification A-A-59544. Conductors shall be Class B stranded, annealed, uncoated copper per UL Standard 44. Insulation shall be rated for 600-Volt. Insulation shall be cross-linked polyethylene complying with the physical and electrical requirements of UL Standard 44 for Type XHHW-2. XHHW wire may be used in place of THWN wire for all applications.

<u>XLP-USE Wire.</u> Cable shall comply with UL Standard 44, UL Standard 854, and Federal Specification A-A-59544. Conductor shall be concentric-strand, soft copper, conforming to ASTM B8 and Underwriters' Laboratories Standard UL44 for Rubber-Insulated Wires. Insulation shall be rated for 600-Volts. Insulation shall be cross-linked polyethylene conforming to Underwriter's Laboratories Requirements for Type USE-2 insulation. Cable shall be UL-listed and marked USE-2.

Series Circuit 5000-Volt Cable. Cable for use with series circuit airfield lighting shall be FAA-L-824, Type C cable complying with Item 108. L-824 cable shall be FAA approved and listed in the current AC150/5345-53C, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum. Circuits for use with constant current regulator outputs (runway or taxiway lighting circuits) shall use 5000-Volt rated cable.

Grounding electrode conductors and/or bonding jumpers shall be the size and type, as detailed on the Plans. Ground wire for bonding constant current regulator housings, cutout enclosures, and other vault equipment frames to the vault ground bus shall be #6 AWG stranded copper."

109-2.21 FLOOR DRAINS. Delete this section.

109-2.22 FIRE EXTINGUISHERS. Furnish and install one UL rated, 10 pound Carbon Dioxide fire extinguisher suitable for use on Class C Fires, in the vault shelter. Per NFPA 10 "Portable Fire Extinguishers" Class C fires are fires that involve energized electrical equipment. Fire extinguisher shall be Amerex Model 3819, Kidde Model PRO10CDM, or approved equal. Confirm model numbers with the respective fire extinguisher manufacturer.

INSTALLATION OF EQUIPMENT IN VAULT OR PREFABRICATED METAL HOUSING

109-3.10 GENERAL. Add the following to this section:

Illinois Project: FWC-4105

"The Contractor shall furnish and install all materials necessary for complete and operational installation of the vault equipment, as specified herein and as shown on the Plans. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of the NFPA 70 – National Electrical Code (NEC) most current issue in force, and all other applicable local codes, laws, ordinances, and requirements in force. Electrical equipment shall be installed in conformance with the respective manufacturer's directions and recommendations for the respective application. Any installations which void the UL listing, ETL listing (or other third party listing), and/or the manufacturer's warranty of a device will not be permitted.

- A. Contractor shall keep a copy of the latest NEC in force on site at all times during construction for use as a reference.
- B. Contractor shall keep a copy of the Plans, Special Provision Specifications including any addenda, and copies of any change orders on site at all times during construction.
- C. Contractor shall coordinate work and any power outages with the Airport Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).
- D. Contractor shall comply with the applicable requirements of NFPA 70E Standard for Electrical Safety in the Workplace.
- E. All electrical equipment installed by the Contractor shall be properly labeled, and all cables must be tagged.
- F. All changes to the airfield lighting system control wiring will be documented by the Contractor and provided to the Resident Engineer.
- G. Locate Existing Underground Utilities and Cables. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor's responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans, and shall obtain, from the respective utility companies, detailed

Illinois Project: FWC-4105

information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner's Representative and/or the Resident Engineer shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract. All utility cables and lines shall be located by the respective utility. **Contact JULIE (Joint Utility Location Information for Excavators) for utility information, phone: 1-800-892-0123.** Contact the FAA (Federal Aviation Administration) for assistance in locating FAA cables and utilities. Location of FAA power, control, and communication cables shall be coordinated with and/or located by the FAA. Also contact Airport Director/Manager and Airport Personnel for assistance in locating underground Airport cables and/or utilities. Also coordinate work with all aboveground utilities.

- H. Contractor shall comply with the requirements of FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- I. Secure, identify, and place any temporary exposed wiring in conduit to prevent electrocution and fire ignition sources."

109-3.12 SWITCHGEAR AND PANELS. Add the following to this section:

- A. <u>Installation of Control Panels.</u> Install control panels, as detailed on the Plans and in conformance with the respective panel manufacturer's requirements and/or recommendations.
- B. <u>Installation of Circuit Breakers in Panelboards</u>. Install circuit breakers in panelboards in conformance with the respective manufacturer's directions. Connect only one wire/cable to each breaker terminal. Update circuit directory to identify the respective device fed by each new circuit breaker.
- C. <u>Surge Protective Device Installation.</u> Install Surge Protective Devices (SPD) in conformance with of FAA-STD-019d, dated August 9, 2002, "LIGHTNING AND SURGE PROTECTION, GROUNDING, BONDING AND SHIELDING REQUIREMENTS FOR FACILITIES AND ELECTRONIC EQUIPMENT" and the respective manufacturer's directions and recommendations. Contractor shall confirm all connections to the surge protective device (phases, neutral, and ground) are completed and secure. Connection leads to the surge arrester shall be sized per the respective manufacturer's recommendation and as detailed herein, and shall be maintained as short as possible, maximum 2 ft in length, and laced together for mutual coupling. The conduit or conduit nipple connecting the SPD enclosure to the panel enclosure shall be sealed with duct seal or other nonflammable medium to prevent soot from entering the enclosure in the event of a SPD failure.

Illinois Project: FWC-4105

109-3.13 DUCT AND CONDUIT. Add the following to this section:

- "A. Conduit shall be installed in accordance with the following:
 - 1. All service, feeder, branch circuit, and control circuit conduits associated with the vault shall be galvanized rigid steel conduit as detailed on the Plans.
 - 2. Schedule 40 PVC conduits shall be used for individual grounding electrode conductors and/or bonding jumpers.
 - 3. Liquid-tight, flexible metal conduit shall be used as specified herein.

B. Conduit Runs:

- 1. All conduit shall be sized, as indicated on the Drawings, or if conduit sizes not shown shall be in accordance with the NEC. All conduit systems shall be mechanically and electrically continuous from source of current to all outlets and grounded in accordance with the NEC.
- 2. Run all exposed conduit parallel to building walls using right angle bends. Exposed diagonal runs of conduit will not be permitted. Do not install conduit on roof surfaces unless specifically indicated on the Drawings.
- 3. Ream conduit after threads are cut. Cut ends square and butt solidly into couplings.
- 4. Prevent the accumulation of water, foreign matter, or concrete in the conduits during the execution of the work. Temporarily plug conduit, blowout, and swab before wires are pulled.
- 5. Fasten conduits to all sheet metal boxes and cabinets with two locknuts in accord with the NEC where insulated bushings are used and where bushings cannot be brought into firm contact with the metal enclosures; otherwise, use at least a single locknut and bushing.
- 6. Seal each underground joint and make water-tight.
- 7. Where building construction or other conditions make it impossible to use standard threaded couplings, install water-tight, threaded unions.
- 8. Make changes in direction of runs with symmetrical bends or cast-metal fittings. Make field-made bends and offsets with conduit bending machine to avoid changing the internal diameter of the conduit and not damage its protective coating either inside or outside. Individual bends shall not exceed 90 degrees, and not more than 270 degrees total bends will be allowed in any one conduit run. Where more bends are necessary,

Illinois Project: FWC-4105

and conduit runs exceed 150 lin. ft, install a suitable pull box or junction box

Illinois Project: FWC-4105

A.I.P. Project: 3-17-0043-B12

- 9. Provide empty conduits installed with a pull wire. Pull wire shall be No. 14 AWG, zinc-coated steel or of plastic having not less than 200 lb. tensile strength. Leave not less than 12 in. of slack at each end of the pull wire.
- 10. Use liquid-tight, flexible metal conduit for final connection to motors, constant current regulators, transformers, portable equipment, and for equipment subject to vibration and noise transmission. For each conduit size up to 1-in. trade size, flexible conduit shall be minimum length of 12 in. and a maximum length of 36 in. and for conduit sizes above 1-in. trade size, flexible conduit shall be minimum length of 20 in. and maximum length of 48 in. Liquid-tight flexible metal conduit and associated fitting shall be UL listed to meet the requirements of NEC 350.6. Liquid-tight flexible metal conduit that is used for flexibility (including connections to motors, constant current regulators, and transformers) shall require an external bonding jumper or internal equipment grounding conductor per NEC 350.60. Do not install liquid-tight flexible metal conduit that is not UL listed.
- 11. Provide duct seal at conduit terminations inside enclosures where the respective conduit is from below grade.

C. Raceway Support and Hangers:

1. Securely fasten raceways in-place and support from ceiling or walls at spacing not exceeding:

<u>Material</u>	Maximum Spacing of Supports
 a. ½-in. through 1-in. trade size conduit b. 1¼-in. through 1½-in. trade size conduit c. 2-in. to 4-in. trade size conduit d. Liquid-tight, flexible metal conduit e. Metal wireway 	6 ft 8 ft 10 ft 4½ ft 10 ft

- 2. Support rigid conduits within 3 ft of every outlet box, junction box, pull box, cabinet, or termination. Support flexible conduit within 12 in. on each side of every outlet box or fitting.
- 3. Support conduits by pipe straps, wall brackets, hangers, or ceiling trapeze. The use of perforated iron or wire for supporting conduits is prohibited. Fasten with wood screws or screw nails to wood; by toggle bolts on hollow masonry units, by concrete inserts, or expansion bolts on concrete or spring-tension or threaded C-clamps for rigid steel conduits on steel.

Do not weld conduits or pipe straps to steel structures unless specifically indicated

Illinois Project: FWC-4105

A.I.P. Project: 3-17-0043-B12

- 4. The load applied to fasteners shall not exceed one-third the proof test load of the fasteners.
- 5. Fasteners attached to concrete shall be vibration and shock-resistant.
- 6. All screws, bolts, washers, and miscellaneous hardware used for conduit supports shall be fabricated from rust-resisting metal. Trapeze hangers shall have hanger assemblies protected with galvanized finish."

<u>109-3.15 WIRING AND CONNECTIONS.</u> Add the following to this section.

"Low-voltage wiring shall maintain separation from high-voltage wiring. Low-voltage and high-voltage wiring shall not be installed in the same raceway. Low-voltage and high-voltage wiring shall not be installed in the same handhole or junction box."

109-3.16 MARKING AND LABELING. Add the following to this section:

- "C. Legend plates shall be provided for all equipment. Legend plates shall be provided to identify the equipment controlled, the power source, and the function of each device. Legend plates shall be weatherproof and abrasion-resistant phenolic/plastic engraved material and fastened with contact type permanent adhesive, screws, or rivets. Installation shall not break, crack, or deform the legend plate. Lettering shall be ¼ in. high, black on a white background, unless noted otherwise.
- D. Identify control wiring at each termination point and in junction/terminal boxes with wire number corresponding to the respective control wiring diagram or respective terminal numbering arrangement. Each individual control wire shall have unique identification and shall maintain that same identification from its point of origin to its final termination point. Wire markers shall be permanent pressure sensitive label with suitable numbers or letters for easy recognition. Where new control wiring is interfaced to existing control wiring it shall also match the color coding of the existing control wiring."
- E. Each constant current regulator shall be furnished with a phenolic-engraved legend plate that identifies the regulator number designation, the runway or taxiway served, and the power source and circuit number.
- F. Each plug cutout cabinet shall be furnished with a phenolic-engraved legend plate that identifies the respective circuit or regulator and the voltage system (5000-Volts).

- G. Each individual circuit breaker, control panel, terminal panel, safety switch, etc. shall be furnished with a phenolic-engraved legend plate that identifies the respective device, the power source, and the respective voltage, phase, and wire. Furnish additional phenolic-engraved legend plates as detailed on the Plans and/or where required by code.
- H. At electrical handholes, identify each cable originating in the vault with respect to the system or device served.
- I. Color-code phase and neutral conductor insulation for No. 6 AWG or smaller. Provide colored marking tape for phase and neutral conductors for No. 4 AWG and larger. Insulated ground conductors shall have green colored insulation for all conductor sizes (AWG and/or KCMIL) to comply with NEC 250.119. Neutral conductors shall have white colored insulation for No. 6 AWG and smaller to meet the requirements of NEC 200.6. Standard colors for power wiring and branch circuits shall be as follows:

120/240 VAC, 1-Phase, 3-Wire system	
Phase A	Black
Phase B	Red
White	Neutral
Ground	Green

J. Furnish and install weatherproof warning label for each meter socket, enclosed circuit breaker, disconnect switch, switchboard, cutout, panelboard, load center, motor control center, and control panel to warn persons of potential electric arc flash hazards, per the requirements of NEC 110.16 "Flash Protection". Labels shall also conform to ANSI Z535.4-2002 "American National Standard for Product Safety Signs and Labels". NEC 110.16 requires that switchboards, panelboards, industrial control panels, meter socket enclosures, and motor control centers that are likely to require examination, adjustment, servicing, or maintenance while energized shall be field marked to warn qualified persons of potential arc flash hazards. The markings shall be located so as to be clearly visible to qualified persons before examination, adjustment, servicing, or maintenance of the equipment. This new requirement is intended to help reduce the occurrence of serious injury or death due to arcing faults to those working on or near energized electrical equipment. The warning labels are to indicate to a qualified worker who intends to open the equipment for analysis of work that a serious hazard exists and that the worker should follow appropriate work practices and wear appropriate personal protective equipment (PPE) for the specific hazard. Labels shall be as detailed on the Plans or shall include at least the following information: "Warning - Potential Arc-Flash Hazards exist while working on this energized equipment. Appropriate PPE Required.

Illinois Project: FWC-4105

K. Furnish and install "DANGER – HIGH VOLTAGE" signs or labels on all fixed electrical equipment where potentials of 500 Volts or more terminal-to-ground are exposed (including, but not limited to, constant current regulators, series circuit cutout enclosures, high voltage junction boxes, and high voltage wireways) in accordance with FAA AC No. 150/5340-26B "MAINTENANCE OF AIRPORT VISUAL AID FACILITIES". Place signs in a conspicuous location, usually on the outside of equipment."

109-3.18 ELECTRICAL TESTING. The installation shall be tested in operation and as a completed unit prior to acceptance. Contractor shall furnish all equipment, meters, instruments, cable connections, tools, manpower, and labor to perform the respective tests. Test all new equipment and all existing equipment where modifications take place and confirm proper operation. Coordinate tests with the respective airport personnel and the Resident Engineer. Tests shall include resistance, voltage, and current reading, as applicable for the respective equipment. When tests disclose any unsatisfactory workmanship or equipment furnished under this contract, correct defects and retest. Repeat tests until satisfactory results are obtained. When any wiring or equipment is damaged by tests, the wiring or equipment shall be repaired or replaced at no additional cost to the contract. Test repaired or replaced items to ensure satisfactory operation. Submit three copies of all test reports to the Engineer. All test reports shall be assembled and bound in a folder or binder. Each test report shall include the following information:

- Project number,
- Project title and location,
- Device or system tested,
- Test performed,
- Date performed,
- Test equipment used,
- Respective Contractor's name, address, and telephone number,
- Testing firm's name, address, and telephone number if other than the Contractor,
- Names of individuals performing tests.
- Names of individuals observing tests,
- Statement verifying each test,
- Nameplate data from respective equipment tested,
- Test results, and
- Retest results after correction of defective components or systems (where applicable).

109-3.19 GROUNDING REQUIREMENTS. Grounding shall conform to the following as applicable: The Contractor shall furnish and install all grounding shown on the Plans and/or as may be necessary or required to make a complete grounding system, as required by the latest NEC (NFPA 70) in force. The reliability of the grounding system is dependent on careful, proper installation, and choice of materials. Improper preparation of surfaces to be joined to make an electrical path, loose joints, or corrosion can introduce impedance that will seriously

Illinois Project: FWC-4105

Fairfield Municipal Airport A.I.P. Project: 3-17-0043-B12 impair the ability of the ground path to protect personnel and equipment and to absorb transients

impair the ability of the ground path to protect personnel and equipment and to absorb transients that can cause noise in communications circuits. The following functions are particularly important to ensure a reliable ground system:

- A. All products associated with the grounding system shall be UL-listed and labeled.
- B. All bolted or mechanical connections shall be coated with a corrosion preventative/conductive grease and lubricant suitable for electrical connections and grounding connections, before joining, Sanchem Inc. "NO-OX-ID "A-Special" compound, Burndy Penetrox E, or approved equal
- C. Metallic surfaces to be joined shall be prepared by the removal of all non-conductive material, per 2011 NEC Article 250.12. All copper bus bars must be cleaned prior to making connections to remove surface oxidation.
- D. Metallic raceway fittings shall be made up tight to provide a permanent low impedance path for all circuits. Metal conduit terminations in enclosures shall be bonded to the enclosure with UL-listed fittings suitable for grounding. Provide grounding bushings with bonding jumpers for all metal conduits entering service equipment (meter base, CT cabinet, main service breaker enclosure, etc.), generator breaker enclosures, and automatic transfer switch enclosures. Provide grounding bushings with bonding jumpers for all metal conduits entering an enclosure through concentric or eccentric knockouts that are punched or otherwise formed so as to impair the electrical connection to ground. Standard locknuts or bushings shall not be the sole means for bonding where a conduit enters an enclosure through a concentric or eccentric knockout.
- E. All connections, located above grade, between the different types of grounding conductors shall be made using UL-listed, double-compression, crimp-type connectors or UL-listed, bolted ground connectors. For ground connections to enclosures, cases, and frames of electrical equipment not supplied with ground lugs, the Contractor shall drill required holes for mounting a bolted, ground connector. All bolted, ground connectors shall be Burndy, Thomas and Betts, or equal. Tighten connections to comply with tightening torques in UL Standard 486A to assure permanent and effective grounding.
- F. All metal equipment enclosures, conduits, cabinets, boxes, receptacles, etc. shall be bonded to the respective grounding system. Provide grounding bushings at all conduits entering service entrance equipment (meter bases, service disconnects, service panelboards, etc.) and distribution panels or load centers and ground wire from bushing to ground bus in the respective service entrance equipment or distribution panel.
- G. Each feeder circuit and/or branch circuit shall include an equipment ground wire. Metal raceway or conduit shall not meet this requirement. The equipment ground wire from equipment shall not be smaller than allowed by 2011 NEC Table 250.122 "Minimum Size Conductors or Grounding Raceway and Equipment." When conductors are adjusted in size to compensate for voltage drop, equipment-grounding conductors shall be adjusted proportionately according to circular mil area. All equipment ground wires shall be copper, either bare or insulated green in color. Where the equipment grounding conductors are

Illinois Project: FWC-4105

Illinois Project: FWC-4105 Fairfield Municipal Airport A.I.P. Project: 3-17-0043-B12

insulated, they shall be identified by the color green, and shall be the same insulation type as the phase conductors.

- H. Bond the main electrical service neutral to ground at the main service disconnect. Bond the service neutral to ground at one location only per the NEC. A grounding connection shall not be made to any neutral circuit conductor on the load side of the service disconnecting means, except as permitted by 2011 NEC 250.24.
- I. The secondary neutral of all transformers (separately derived system transformers) shall be grounded in accordance with the NEC. The respective grounding electrode conductor shall be connected to the neutral point of the transformer between the transformer and the output disconnect means. Size of the grounding electrode conductor shall be in accordance with 2011 NEC Article 250.66 and Table 250.66 unless shown larger on the Drawings. A bond shall be provided between the neutral and transformer case, or other metal that is part of the AC equipment grounding system, so as to complete a circuit for fault current to the transformer winding from the AC equipment grounding system. Size of the neutral bonding conductor shall be in accordance with 2011 NEC Article 250.102.
- J. All exterior metal conduits, where not electrically continuous because of manholes, handholes, non-metallic junction boxes, etc., shall be bonded to all other metal conduit in the respective duct run, and at each end, with a copper-bonding jumper sized in conformance with 2011 NEC 250.102. Where metal conduits terminate in an enclosure (such as a motor control center, switchboard, etc) where there is not electrical continuity with the conduit and the respective enclosure, provide a bonding jumper from the respective enclosure ground bus to the conduit sized per 2011 NEC 250.102.
- K. Install grounding electrode conductors and/or individual ground conductors in Schedule 40 or Schedule 80 PVC conduit. Where grounding electrode conductors or individual ground conductors are run in PVC conduit, do not completely encircle conduit with ferrous and/or magnetic materials. Use non-metallic, reinforced fiberglass strut support. Where metal conduit clamps are installed, use nylon bolts, nuts, washers, and spacers to interrupt a complete metallic path from encircling the conduit.
- L. Individual ground conductors and/or grounding electrode conductors shall not be run in metallic conduit and shall not be encircled by metallic clamps. If local codes dictate that grounding conductors must be run in metal conduit or raceway, then the conduit or raceway must be bonded to the grounding conductor at both ends with a bonding jumper sized in accordance with the NEC 250.64(E). All such installations requiring individual grounding conduits to be run in metal conduit or raceway shall be verified and reviewed with the Resident Engineer. This does not apply to AC equipment ground wires run with AC circuits.

109-3.20 RESTORATION. Any and all trenches and disturbed areas will be backfilled and restored to a smooth grade and seeded to the satisfaction of the Engineer. All trench settlement or disturbed areas shall be corrected for a period of one year. Restoration, grading, and seeding of areas disturbed during the installation of the proposed vault work and/or vault removal work will be incidental to the respective 109 Pay Item.

METHOD OF MEASUREMENT

<u>109-4.3.</u> Add the following to this section:

"The quantity of vault equipment to be paid for under Item AR109200 Install Electrical Equipment shall consist of furnishing and installing all electrical equipment at the vault, as detailed on the Plans and specified herein. This item shall include all labor, equipment, surge protection, grounding, materials, tools, operational instructions, coordination, and testing required to place the vault and associated electrical equipment into proper working order. Cables inside or at the Airport Electrical Vault Building shall be considered incidental to this item, and no additional compensation will be allowed. Conduit entries, elbows, and fittings located at, adjacent to, or beneath the vault shall be considered incidental to this item, and no additional compensation will be allowed. Furnishing and installing conduits from the vault to the low voltage handhole located near the vault shall be considered incidental to this item, and no additional compensation will be allowed.

BASIS OF PAYMENT

Payment will be made under:

Item AR109200 Install Electrical Equipment - per lump sum

END OF ITEM 109

Illinois Project: FWC-4105

ITEM 110 INSTALLATION OF AIRPORT UNDERGROUND ELECTRICAL DUCT

DESCRIPTION

110-1.1 Add the following:

"This item of work shall consist of the installation of all proposed conduits and ducts as shown on the Construction Plans."

110-1.2 REFERENCES

- A. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 Fittings Rigid Metal Conduit and EMT.
- C. ASTM D3350 Specification of Polyethylene Plastics Pipe and Fittings Materials.
- D. ASTM F2160 Standard Specification for Solid Wall, High-Density Polyethylene Conduit Based on Controlled Outside Diameter.
- E. NEMA TC-2 Electrical Plastic Tubing and Conduit.
- F. NEMA TC-3 Fittings Rigid PVC Conduit and Tubing.
- G. NEMA Specification TC-7 Smooth-Wall Coilable Polyethylene Electrical Plastic Conduit.
- H. NFPA 70 National Electrical Code (NEC), most current issue in force.
- I. UL Standard 6 Rigid Metal Conduit.
- J. UL Standard 514B Conduit, Tubing and Cable Fittings.
- K. UL Standard 651 Schedule 40 and 80 Rigid PVC Conduit.
- L. UL Standard 651B Standard for Continuous Length High-Density Polyethylene (HDPE) Conduit.
- <u>110-1.3 SHOP DRAWINGS.</u> The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for each type of conduit or duct to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:

Illinois Project: FWC-4105

- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Indicate the pay item number for each respective conduit or duct.
- D. Shop drawings shall include conduit and/or duct cut sheets with type, size, specifications, UL listing, manufacturer, and catalog or part number.
- E. Provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.

EQUIPMENT AND MATERIALS

110-2.1 GENERAL. Add the following:

"All materials for these items shall be in accordance with the FAA Standard Specification 110 Equipment and Materials, as detailed on the Plans, and as specified herein.

- A. Conduit for concrete encased duct shall be 4" Schedule 40 Polyvinyl Chloride (PVC).
- B. The duct to be directional-bored shall be Schedule 40 PVC Conduit, Schedule 80 PVC Conduit or High-Density Polyethylene (HDPE) duct, (Schedule 40, Schedule 80, SDR 9, or SDR 11).

110-2.2 STEEL CONDUIT. Replace this section with the following:

"Rigid Steel Conduit and fittings shall be hot-dipped, galvanized, UL-listed, and produced in accordance with UL Standard 6 – Rigid Metal Conduit and ANSI C80.1 – Rigid Steel Conduit, Zinc Coated. Couplings, connectors, and fittings for rigid steel conduit shall be threaded, galvanized steel or galvanized, malleable iron, specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 – Fittings Rigid Metal Conduit and EMT and UL 514B – Conduit, Tubing, and Cable Fittings. Set screw type fittings are not acceptable. Steel used to manufacture conduits shall be 100 percent domestic steel. Contractor shall provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.

<u>Miscellaneous Fittings</u>. Fittings shall be suitable for use with conduits and ducts supplied. All fittings for use with rigid metal conduit shall be threaded. Set screw-type fittings are not acceptable. All conduit bodies, fittings, and boxes installed in classified

Illinois Project: FWC-4105

hazardous locations (Class I, Division 1 or 2, Group D) shall be suitable for use in Class I, Division 1, and Group D locations. Fittings shall be as manufactured by Appleton, Crouse-Hinds, Hubbel-Killark, O-Z/Gedney, or approved equal."

110-2.3 PLASTIC CONDUIT. Add to this section:

"Conduits for concrete encasement shall be Schedule 40 PVC, UL-listed, rated for 90°C cable-conforming to NEMA Standard TC-2 and UL 651, listed suitable for concrete encasement. Conduits for directional boring shall be Schedule 40 PVC or Schedule 80 PVC conduit, UL-listed, rated for 90°C cable-conforming to NEMA Standard TC-2 and UL 651 and suitable for directional boring installation, Schedule 40 HDPE or Schedule 80 HDPE conduit, UL-listed, conforming to NEMA Standard TC-7 and UL 651B and suitable for directional boring installation, or Wall Type SDR 9 or SDR 11 HDPE conduit manufactured in accordance with ASTM D-3350 (Specification of Polyethylene Plastics Pipe and Fittings Materials) and ASTM F2160 (Standard Specification for Solid Wall, High-Density Polyethylene Conduit Based on Controlled Outside Diameter), and suitable for directional boring installation. Per NEC 300.5 (K), raceways installed using directional boring equipment shall be approved for the purpose. Provide manufacturer's literature confirming the respective duct is suitable for directional boring with the respective Shop Drawing submittal. Conduits shall be suitable for underground applications encased in concrete or direct burial, and suitable for exposed applications aboveground."

110-2.9 DUCT SPACERS. Provide duct spacers to provide proper separation of conduits installed in concrete encased duct. Duct spacers shall be designed to provide 3" separation of conduits. Duct spacers shall be Underground Devices Incorporated Wunpeece Series suitable for the respective size and quantity of ducts, or approved equal. Contact information for Underground Devices Incorporated is address: 3304 Commercial Avenue, Northbrook, Illinois 60062, Phone: (847) 205-9000, Fax: (847) 205-9004. Confirm catalog numbers with the manufacturer for the respective application.

CONSTRUCTION METHODS

110-3.1 GENERAL. Add to this section:

"The proposed conduits and ducts shall be constructed at the locations and in accordance with the details shown on the Construction Plans. Ducts shall be installed 18 in. minimum below grade. Ducts located in area subject to farming shall be 42 in minimum below grade. Where detailed on the Plans or where required to avoid obstructions, ducts shall be buried deeper. Where concrete-encased duct interfaces to directional-bored duct at a pavement crossing, the concrete encasement shall be installed up to the respective pavement edge. Where concrete-encased duct interfaces to an electrical handhole or manhole, the concrete encasement shall be installed up to the respective handhole or manhole. Provide bushings or bells at conduit terminations in electrical handholes or manholes.

Illinois Project: FWC-4105

Underground ducts installed by directional-boring method shall be installed in a manner that will not damage any existing underground utilities, and shall not disturb or damage the respective pavement or roadway surface. Ducts shall be directional-bored at the locations shown on the Construction Plans. The ducts will be bored at a minimum depth of 24 in. below the bottom of the pavement it is being bored under. Ducts installed under paved areas and roadways shall extend a minimum of 10 ft beyond the respective pavement or roadway surface. A pull wire will be left in the conduit if it is to be left vacant. The ends of the conduit will be sealed with approved plugs.

The Contractor will determine if there is a conflict between the installation of the proposed electrical ducts and any existing utilities. He will make all necessary adjustments in depth of installation to avoid any and all proposed underground improvements."

110-3.7 RESTORATION. Add to this section:

"Any and all trenches and disturbed areas will be backfilled and restored to a smooth grade and seeded to the satisfaction of the Engineer. All trench settlement shall be corrected for a period of one year. Restoration, grading, and seeding of areas disturbed during the installation of the proposed ducts will be incidental to the respective pay item for which the duct is installed. The fertilizing and seeding will be completed in accordance with Items 901 and 908, but will be incidental to the respective pay item for which the duct is installed."

110-3.8 LOCATING EXISTING UNDERGROUND UTILITIES AND CABLES. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor's responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans, and shall obtain from the respective utility companies detailed information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner's Representative and/or the Resident Engineer shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract.

All utility cables and lines shall be located by the respective utility. Contact JULIE (Joint Utility Location Information for Excavators) for utility information, phone: 1-800-892-0123. Contact the FAA (Federal Aviation Administration) for assistance in locating FAA cables and utilities. Location of FAA power, control, and communication cables shall be coordinated

Illinois Project: FWC-4105

Special Provisions Fairfield Municipal Airport

with and/or located by the FAA. Also contact Airport Director/Manager and Airport Personnel for assistance in locating underground Airport cables and/or utilities. Also coordinate work with all aboveground utilities.

Contractor shall locate and mark all existing cables within ten (10) feet of proposed excavating/trenching area. Any cables found interfering with proposed excavation or cable/trenching shall be hand dug and exposed. Any damaged cables shall be immediately repaired to the satisfaction of the Resident Engineer at the Contractor's expense. The Resident Engineer and Owner shall be notified immediately if any cables are damaged.

Payment for locating and marking underground utilities and cables will not be paid for separately, but shall be considered incidental to the respective duct installation.

METHOD OF MEASUREMENT

<u>110-4.1.</u> The quantity of conduit to be paid for shall be the number of lin. ft of ducts of the particular type installed and measured in-place, complete, and accepted by the Resident Engineer.

BASIS OF PAYMENT

<u>110-5.1.</u> Payment will be made at the contract unit price per each type and size of conduit, completed and accepted. This price shall be full compensation for furnishing all materials and for all preparation, assembly, and installation of these materials; for all sawing and pavement removal; for all duct interface work to handholes/manholes including coring of handholes/manholes; for all excavation and backfilling with aggregate backfill, earth backfill, and concrete; and for all labor, coordination, equipment, tools, and incidentals necessary to complete this Item.

Payment will be made under:

Item AR110014 4" Directional Bore - per linear foot

END OF ITEM 110

Illinois Project: FWC-4105

ITEM AR110610 ELECTRICAL HANDHOLE

DESCRIPTION

<u>110610-1.1.</u> This item of work shall consist of the construction of electrical handholes with lids complete, in accordance with this Specification and as detailed on the Construction Plans.

<u>110610-1.2</u> SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for each type of conduit or duct to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:

- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Concrete mix design for handholes to be cast in place.
- D. Precast concrete handholes and manholes must be on IDOT (Illinois Department of Transportation) List of Certified Precast Concrete Producers. Provide information on respective precast concrete producer for precast handholes and drawings for respective handholes.
- E. Provide cut sheets with part number and specification for handhole frame and lid.

MATERIALS

110610-2.1. The electrical handhole shall be constructed in accordance with the details as shown on the Construction Plans. The concrete shall conform to Item 610. The handholes shall be provided with heavy duty square slab type manhole frames and solid lids suitable for H-20 loading, NEENAH R-6662-PP frame and lid, or an approved equal. Lids for the handholes containing high voltage cables shall include lettering labeled "HIGH VOLTAGE". Lids for the handholes containing low voltage cables shall include lettering labeled "LOW VOLTAGE".

Illinois Project: FWC-4105

CONSTRUCTION METHODS

<u>110610-3.1.</u> The electrical handholes shall be constructed in accordance with the details as shown on the Construction Plans.

METHOD OF MEASUREMENT

<u>110610-4.1.</u> The number of electrical handholes to be paid for shall be the number of structures constructed in place and accepted by the Resident Engineer.

BASIS OF PAYMENT

110610-5.1. Payment will be made at the contract unit price bid for each electrical handhole completed and in place. This price shall be full compensation for furnishing all materials and for all preparation, excavation, backfilling, and placing of the materials; for all coring and labor associated with conduit, duct, cable in unit duct, and/or cable entries; and for all labor, equipment, tools, and incidentals necessary to complete the structure.

Payment will be made under:

Item AR110610 Electrical Handhole - per each

Illinois Project: FWC-4105

ITEM 125 INSTALLATION OF AIRPORT LIGHTING SYSTEMS

DESCRIPTION

125-1.1. Revise this paragraph to read as follows:

"This Item of work shall consist of furnishing and installing base-and/or stake-mounted, threshold lights and splice cans at the locations shown on the Construction Plans and in accordance with the details shown on the Plans. This Item of work shall also include the removal of base-and/or stake-mounted airfield lights. Also included in this Item will be the testing of the installation and all incidentals necessary to place the lighting systems into operation, completed, and to the satisfaction of the Engineer."

125-1.9 REFERENCES

- A. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 Fittings Rigid Metal Conduit and EMT.
- C. FAA AC No. 150/5340-30E "DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS".
- D. FAA AC No. 150/5345-42F "SPECIFICATION FOR AIRPORT LIGHT BASES, TRANSFORMER HOUSINGS, JUNCTION BOXES, AND ACCESSORIES".
- E. FAA AC No. 150/5345-46C "SPECIFICATION FOR RUNWAY AND TAXIWAY LIGHT FIXTURES".
- F. FAA AC No. 150/5345-47B "ISOLATION TRANSFORMERS FOR AIRPORT LIGHTING SYSTEMS".
- G. FAA AC No. 150/5345-53 "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM" (most current issue) and AC150/5345-53C, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum.
- H. FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- I. UL Standard 6 Rigid Metal Conduit.
- J. UL Standard 514B Conduit, Tubing and Cable Fittings.
- <u>125-1.10 SHOP DRAWINGS.</u> The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for airfield lighting equipment and materials to be used on the project. **Shop drawings shall be clear and legible. Copies that**

Illinois Project: FWC-4105

are illegible will be rejected. Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:

- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Cut sheets with part number and specifications for each airfield light fixture. Include cut sheets with part numbers and dimensions for mounting stakes, base cans, cover plates, transformers, and associated components for each light airfield fixture.
- D. Cut sheets with part number and specifications for base can and cover plates.
- E. Concrete mix design.
- F. Provide cut sheets with manufacturer's name, catalog number, dimensions, material and UL listing for each type and size ground rod. Include certification of 100% domestic steel for ground rods. Include cut sheets for exothermic weld connections, ground lugs, and ground wire.
- G. Provide cut sheets for all types of conduit used with the airfield light fixtures (for example galvanized rigid steel conduit). Include certification that steel conduits are made with 100 percent domestic steel.

EQUIPMENT AND MATERIALS

<u>125-2.1 GENERAL.</u> Add the following to this section:

"D. Threshold lights shall be Type L-861SE, with 115 Watt or 120 Watt quartz lamps. Lens colors for threshold lights shall be bi-color Red/Green. All lights shall have an overall height of 24 in. All of the above lights shall be manufactured in accordance to FAA Specification AC No. 150/5345-46C, or latest edition in force and shall be FAA approved and in compliance with the Airport Improvement Program Buy American Requirements.

The concrete used in the construction of these Items shall be in accordance with Item 610.

Illinois Project: FWC-4105

E. Where non-metallic light fixtures or plastic couplings are proposed the Contractor will be responsible to furnish all grounding connectors, bonding jumpers, pipe grounding clamps, and accessories to maintain continuity of the ground path for the required light base ground in accordance with FAA AC 150/5340-30E DESIGN AND INSTALLTION DETAILS FOR AIRPORT VISUAL AIDS, Chapter 12, Part 12.6."

<u>125-2.4 CONDUIT</u>. Add the following to this section:

"Rigid Steel Conduit and fittings shall be hot-dipped, galvanized, UL-listed, produced in accordance with UL Standard 6 – Rigid Metal Conduit and ANSI C80.1 – Rigid Steel Conduit, Zinc Coated. Couplings, connectors, and fittings for rigid steel conduit shall be threaded galvanized steel or galvanized malleable iron specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 – Fittings Rigid Metal Conduit and EMT. Set screw type fittings are not acceptable. Galvanized rigid steel conduit shall be manufactured in the United States of America produced from 100 percent domestic steel."

<u>125-2.7 ISOLATION TRANSFORMERS.</u> Add the following to this section:

"Series circuit isolation transformers for the runway or taxiway edge lights and taxi guidance signs shall be manufactured to FAA Specification AC 150/5345-47B (or current edition in force), and shall be FAA-approved (ETL-Certified). Series circuit transformer shall be properly sized for the respective runway or taxiway edge lights or taxi guidance signs and shall be as recommended by the respective runway or taxiway edge lights manufacturer or respective taxi guidance sign manufacturer. Confirm proper transformer selection and sizing with the respective runway or taxiway edge lights manufacturer, and the respective taxi guidance sign manufacturer."

125-2.8 LIGHT CANS. Add the following to this section:

"Each light base can and/or splice can shall include internal and external ground lugs. Cans shall be the size and depth as detailed on the Plans. L-867 splice cans shall have galvanized steel covers, 3/8 in. thick, with stainless steel bolts. The concrete used in the construction of these Items shall be in accordance with Item 610."

<u>125-2.14 IDENTIFICATION TAGS</u>. Identification tags shall be attached to each new fixture and sign. Where shown on the Plans provide new identification tags for existing fixtures. The tag shall be of the type and with the lettering shown on the Plans. The cost of furnishing and installing these tags shall be included in the unit price for the fixtures or signs and no additional compensation will be allowed.

<u>125-2.15</u> ANTI-SEIZE COMPOUND. Prior to installing the proposed taxi guidance signs, the Contractor will apply an oxide-inhibiting, anti-seizing compound to all screws, nuts, breakable

Illinois Project: FWC-4105

couplings, and all places where metal comes into contact with metal. The anti-seize compound will be as manufactured by I.T.T. brand name "Contax", or approved equal.

<u>125-2.16 STAINLESS STEEL BOLTS.</u> All base plate-mounting bolts and stake-mounting bolts shall be stainless steel.

<u>125-2.17 GROUND RODS.</u> Furnish and install a 5/8-inch diameter by 8-feet long (minimum), UL-listed, Copper-clad, ground rod at each L-867 transformer base/light can and at each stake-mounted light fixture. Ground rods shall be manufactured in the United States of America. Steel used to manufacture ground rods shall be 100 percent domestic steel.

CONSTRUCTION METHODS

125-3.1 GENERAL. Add the following to this section:

"The proposed threshold lights and other airfield lighting devices shall be installed in accordance with the details shown on the Construction Plans.

The existing airfield lights designated for removal shall be removed in their entirety. The Contractor shall remove the existing lights including mounting stakes, bases, foundations, and transformers. The electrical wire will be disconnected from each light and placed underground at a minimum depth of 18-in. If the Contractor elects to salvage the cable within the circuit of the lights to be removed, shown in the Construction Plans as cable to be abandoned, any cost associated with removal of the cable shall be considered incidental to the Contract and no additional compensation will be allowed. The existing lights, transformers, and mounting stakes shall be turned over to the Airport Manager. Any materials not salvaged by the Airport, shall be disposed of off the airport site, in a legal manner, at the Contractor's own expense. The concrete base mounted lights shall be removed and earth material will be placed in the hole made from the sign base removal. The disturbed area shall be seeded and mulched in accordance with Item 901 and 908. The seeding and mulching will be considered as an incidental item to the sign removal and/or light removal and no additional compensation will be allowed.

The proposed splice cans shall be constructed at the locations shown on the Construction Plans and in accordance with the details shown on the Construction Plans. Provide sufficient slack cable at each splice can to perform cable splices outside of the can.

Obtaining the required borrow material from an offsite borrow, placing the borrow material, grading, seeding, and mulching the disturbed areas will be considered as an Incidental Item to the proposed taxi guidance signs and/or lights, and no additional compensation will be allowed.

Contractor shall coordinate work and any power outages with the Airport Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall

Illinois Project: FWC-4105

be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).

The Contractor shall furnish and install all electrical materials necessary for complete and operational installation of the airfield lighting systems as shown on the Plans and detailed herein. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of the NFPA 70 - National Electrical Code (NEC) most current issue in force and the applicable Federal Aviation Administration standards, orders, and advisory circulars. Equipment shall be installed in conformance with the respective manufacturer's directions and recommendations for the respective application. Any installations which void the UL listing, ETL listing, (or other third party listing), and/or the manufacturer's warranty of a device will not be permitted.

Contractor shall comply with the requirements of FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".

Secure, identify, and place any temporary exposed wiring in conduit to prevent electrocution and fire ignition sources."

<u>125-3.4 IDENTIFICATION NUMBERS.</u> The Contractor will place light identification number tags on <u>ALL</u> of the proposed runway lights, threshold lights, taxiway lights, and taxi guidance signs as detailed on the Plans. The correct light identification numbers are shown on the Construction Plans.

125-3.5 GROUNDING FOR AIRFIELD LIGHTS AND TAXI GUIDANCE SIGNS. Grounding for Runway Lights, Taxiway Lights, and Lighted Taxi Guidance Signs shall be as detailed on the Plans and as specified herein. Per FAA AC 150/5340-30E DESIGN AND INSTALLTION DETAILS FOR AIRPORT VISUAL AIDS, Chapter 12, Part 12.6; a ground must be installed at each light fixture. The purpose of the light base ground is to provide a degree of protection for maintenance personnel from possible contact with an energized light base or mounting stake that may result from a shorted power cable or isolation transformer. A light base ground shall be installed at each transformer base/light can associated with runway lights, taxiway lights, and lighted taxi guidance signs. A light base ground shall also be installed at each stake-mounted light fixture. A light base ground shall be installed and connected to the metal frame of each taxi guidance sign as detailed on the Plans and in accordance with the respective taxi guidance sign manufacturer recommendations. The light base ground shall be a #6 AWG bare Copper conductor bonded to the ground lug on the respective L-867 transformer base/light can or mounting stake and a 5/8-in. diameter by 8-ft long (minimum), UL-listed, Copper-clad ground rod. Connections to ground lugs on the L-867 transformer base/light can or mounting stake shall be with a UL-listed grounding connector. Connections to ground rods shall be made with exothermic-weld type connectors, Cadweld by Erico Products, Inc., Solon, Ohio

Illinois Project: FWC-4105

(Phone: 800-248-9353), Thermoweld by Continental Industries, Inc., Tulsa, Oklahoma (Phone: 918-663-1440), Ultraweld by Harger, Grayslake, Illinois (Phone: 800-842-7437), or approved equal. Exothermic-weld connections shall be installed in conformance with the respective manufacturer's directions using molds, as required for each respective application. Bolted connections will not be permitted at ground rods. Top of ground rods shall be buried 30 in. minimum below grade.

BASIS OF PAYMENT

Add the following:

Payment will be made under:

Item AR125540 MI Threshold Light Stake Mtd – per each Item AR125565 Splice Can – per each Item AR125901 Remove Stake Mounted Light – per each"

Illinois Project: FWC-4105

ITEM AR125610 REILS

DESCRIPTION

<u>125610-1.1</u> This item of work shall consist of furnishing and installing Runway End Identification Lights (REILS) at the locations shown on the Construction Plans. Each installation will be in accordance with the details on the Plans and these Special Provisions. Also included in this item will be the testing of the installation and all incidentals necessary to complete and place the lighting system into proper operation to the satisfaction of the Engineer.

125610-1.2 REFERENCES.

- A. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 Fittings Rigid Metal Conduit and EMT.
- C. FAA AC 150/5345-42F "SPECIFICATION FOR AIRPORT LIGHT BASES, TRANSFORMER HOUSINGS, JUNCTION BOXES, AND ACCESSORIES".
- D. FAA AC No. 150/5345-51B "SPECIFICATION FOR DISCHARGE TYPE FLASHING LIGHT EQUIPMENT"
- E. FAA AC No. 150/5345-53 "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM" (most current issue) and AC150/5345-53C, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum.
- F. FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- G. NFPA 70 National Electrical Code (most current issue in force).
- H. UL Standard 6 Rigid Metal Conduit.
- I. UL Standard 467 Grounding and Bonding Equipment.
- J. UL Standard 486A-486B Wire Connectors.
- K. UL Standard 514B Conduit, Tubing and Cable Fittings.

<u>125610-1.3</u> SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for REIL units and materials to be used on the project. **Shop drawings shall be clear and legible.** Copies that are illegible will be rejected. Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:

Illinois Project: FWC-4105

- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Cut sheets with part number and specifications for REIL system.
- D. Concrete mix design.
- E. Provide cut sheets for L-867 light bases.
- F. Provide cut sheets with manufacturer's name, catalog number, dimensions, material and UL listing for each type and size ground rod. Include certification of 100% domestic steel for ground rods. Include cut sheets for exothermic weld connections, ground lugs, and ground wire.
- G. Provide cut sheets for all types of conduit used with the REIL installation (for example galvanized rigid steel conduit). Include certification that steel conduits are made with 100 percent domestic steel.

EQUIPMENT AND MATERIALS

<u>125610-2.1 REILS.</u> The proposed REILS shall be Type L-849I (powered by a constant current 6.6 Amp power supply), Style A (unidirectional, high intensity, one brightness step), base mounted, consisting of two lighting units (a master unit with controller and a slave unit), with transient suppression, and all accessories as per FAA AC 150/5345-51B (or latest edition in force), FAA approved, and in compliance with the Airport Improvement Program Buy American Requirements.

125610-2.2 POWER AND CONTROL CABLE. The REILS will be powered by the Runway 18-36 lighting series circuit. Series circuit power cables to the REILS shall be one conductor No. 8, 5,000-Volt, FAA L-824, Type C, stranded, in unit duct in conformance with Item 108. Series circuit power cables to the REILS shall be paid for under Item AR108158, 1/C #8 5 KV UG Cable in UD. Control cables between the REIL units shall be as recommended by the respective REIL manufacturer's instructions, per FAA AC 150/5345-51B, and as detailed on the Plans.

<u>125610-2.3 CONDUIT AND DUCTS.</u> Conduit and ducts for the REIL systems shall conform to Item 110, per manufacturer's recommendations, as detailed on the Plans, and as specified herein. Conduit for control cables from the REIL Master Control Unit to the REIL Slave unit shall be 2-

Illinois Project: FWC-4105

inch Galvanized Rigid Steel Conduit, or larger where required by NEC and/or manufacturer's recommendations for the respective cables. GRSC shall be heavy wall, hot-dipped, galvanized steel pipe bearing the UL label and conforming to UL-6 and ANSI Specification C80.1. Couplings, connectors, and fittings for rigid steel conduit shall be threaded galvanized steel or galvanized malleable iron specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 and UL-514B. Galvanized rigid steel conduit shall be produced from 100 percent domestic steel.

125610-2.4 REIL BASE/SPLICE CANS. REIL Base/Splice cans shall conform to the requirements of FAA AC 150/5345-42F for Type L-867, Class IA, Size D (16-inch nominal diameter), 24-inch deep, and/or as detailed on the Plans. Base cans shall include internal and external ground lugs. Base cans shall have 3/8" minimum thick galvanized steel covers, or aviation yellow powder coat painted steel covers with 2" NPT holes compatible with the respective REIL units and stainless steel bolts. Include breakable couplings for mounting REILS to the respective base. **Include internal and external ground lugs on each L-867 splice can.**

<u>125610-2.5 SERIES CIRCUIT TRANSFORMERS.</u> Series circuit isolation transformers for the REIL units shall be manufactured to FAA Specification AC 150/5345-47B (or current edition in force), and shall be FAA-approved (ETL-Certified). Series circuit transformer shall be properly sized for the respective REIL units in accordance with the manufacturer's instructions.

<u>125610-2.6 ANTI-SEIZE COMPOUND.</u> Prior to installing the proposed REIL units, the Contractor will apply an oxide-inhibiting, anti-seizing compound to all screws, nuts, breakable coupling, and all places where metal comes into contact with metal. The anti-seize compound will be as manufactured by I.T.T. brand name "Contax" or an approved equal.

125610-2.7 STAINLESS STEEL BOLTS. All base plate mounting bolts shall be stainless steel.

<u>125610-2.8 GROUND RODS.</u> Ground rods shall be 3/4-inch diameter by 10-feet long UL listed copper clad, with 10-mil minimum copper coating. Steel used to manufacture ground rods shall be 100% domestic steel.

<u>125610-2.9 CONCRETE</u>. Concrete associated with the each REIL foundation pads and/or splice cans shall conform to Item 610 Portland Cement Concrete of the Standard Specifications for Construction of Airports.

CONSTRUCTION METHODS

125610-3.1 INSTALLATION OF REILS. The REILS shall be installed at the locations shown on the Plans. Installation of REILS systems shall conform to FAA AC No. 150/5345-51B titled "SPECIFICATION FOR DISCHARGE-TYPE FLASHING LIGHT EQUIPMENT", the respective manufacturer's instructions, as detailed on the Plans, and as specified herein. The Contractor shall install L-867 base/splice cans and construct concrete bases for the REIL units in accordance with the respective REIL manufacturer's recommendation. Because of the difference

Illinois Project: FWC-4105

in manufacturers' installations, all required trenching, cable, and ducts between the master and slave units, associated hardware, mounting requirements, etc. shall be installed per the respective REIL manufacturer's recommendation, and shall be considered part of the installation with no additional compensation.

REILS shall be aimed as detailed on the Plans and in accordance with the respective manufacturer's instructions

Contractor shall coordinate work and any power outages with the Airport Manager, the respective Airport personnel, and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures, including, but not limited to, 29 CFR Section 1910.147 The Control of Hazardous Energy (lockout/tagout).

Contractor shall comply with the requirements of FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".

Secure, identify, and place any temporary exposed wiring in conduit to prevent electrocution and fire ignition sources.

125610-3.2 ELECTRICAL. The Contractor shall furnish and install all electrical materials necessary for complete and operational installation of the REIL systems as shown on the Plans and detailed herein. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of the NFPA 70 - National Electrical Code (NEC) most current issue in force and the applicable Federal Aviation Administration standards, orders, and advisory circulars. Equipment shall be installed in conformance with the respective manufacturer's directions and recommendations for the respective application. Any installations which void the UL listing, ETL listing, (or other third party listing), and/or the manufacturer's warranty of a device will not be permitted.

108, the applicable sections of FAA AC 150/5345-51B, per the respective equipment manufacturer's recommendations, as detailed on the Plans, and as specified herein. Where cable splices are required they shall conform to Item 108 and the details on the Plans. Power and control cables in conduit or duct between the REIL Master unit and the REIL Slave unit shall be installed as detailed on the Plans and in conformance with the respective REIL manufacturer's recommendations and instructions. Cables and conduits between the REIL units will be considered incidental to the REIL installation and no additional compensation will be allowed.

<u>125610-3.4 CONDUIT INSTALLATION FOR REILS.</u> Installation of conduit shall conform to Item 110, the respective REIL manufacturer's installation instructions and/or recommendations, as detailed on the Plans and as specified herein. Control cables between REIL units shall be

Illinois Project: FWC-4105

installed in a separate dedicated conduit. Power cables between the REIL units shall be installed in a conduit separate from the control cables.

125610-3.5 GROUNDING FOR REILS. Grounding for REILS shall conform to the respective REIL manufacturer's installation instructions, as detailed on the Plans, and as specified herein. Furnish and install a 3/4-inch diameter by 10-feet long copper clad ground rod at each REIL unit. Bond each REIL unit housing and the REIL base can to the respective ground rod in accordance with the manufacturer's instructions with a #6 AWG bare solid or stranded (per REIL manufacturer requirements) copper grounding electrode conductor. Top of ground rods shall be buried 30 inches below grade. All connections to ground rods shall be exothermic weld as manufactured by Cadweld, Thermoweld, Ultraweld, or approved equal. Connections to REIL unit frames shall be as recommended by the manufacturer or with a UL listed grounding connector. Provide multi-terminal ground bar or individual ground lugs to terminate each ground wire in each REIL unit.

<u>125610-3.6 REIL OPERATION</u>

A. In the automatic mode of operation the REILS shall be activated by L-854 radio receiver control with the runway lighting series circuit corresponding to the 100% brightness level of the respective runway lights as follows:

REIL Operation	
3 clicks – Off	
5 clicks – Off	
7 clicks – 100% Brightness/On	

B. In the manual mode of operation the REILS shall be activated by the constant current regulator for the runway lighting series circuit corresponding to the 100% brightness level of the respective runway lights as follows:

REIL Operation	
10% Brightness Level – Off	
30% Brightness Level – Off	
100% Brightness Level – On	

C. The Contractor shall test and demonstrate proper operation for the Resident Engineer and the Airport Managers.

<u>125610-3.7 GROUND CHECK.</u> Prior to final acceptance and activation, each completed REIL system will be ground checked by the Federal Aviation Administration and/or Illinois Division of Aeronautics, and it shall be the Contractor's responsibility to have a representative present to make any necessary adjustments and/or corrections of the respective REIL system installation. The Contractor shall be responsible to provide REIL systems that pass the ground check by Federal Aviation Administration and/or Illinois Division of Aeronautics.

Illinois Project: FWC-4105

<u>125610-3.8 FLIGHT CHECK.</u> Prior to final acceptance and activation, each completed REIL system will be flight checked by Federal Aviation Administration and/or Illinois Division of Aeronautics, and it shall be the Contractor's responsibility to have a representative present to make any necessary adjustments in the aiming of the respective REIL units. The Contractor shall be responsible to provide REIL systems that pass the flight check by Federal Aviation Administration and/or Illinois Division of Aeronautics.

METHOD OF MEASUREMENT

<u>125610-4.1</u> The REIL systems to be furnished and installed shall be measured for payment as a unit price per pair (master and slave unit) and shall include all concrete and materials as required for foundations, all cable and conduit between the master and slave units, base/splice cans, equipment, grounding, excavating, restoration, labor, tools, testing, and incidentals necessary to furnish a complete and operational REIL system as approved by the Engineer.

BASIS OF PAYMENT

<u>125610-5.1</u> Payment shall be made at the contract unit price per pair. This price and payment shall be full compensation for installation of the REIL units and bases; for furnishing and installing all equipment and materials; for all grounding, coordination, excavating, labor, tools, testing, restoration, and incidentals necessary to complete this item of work.

Payment will be made under:

Item AR125610 REILS - per pair

END OF ITEM AR125610

Illinois Project: FWC-4105

ITEM AR125907 REMOVE REILS

DESCRIPTION

<u>125907-1.1.</u> This item of work shall consist of the removal of the existing Runway End Identification Lights (REIL) units located on Runway 9.

125907-1.2 REFERENCES.

- D. FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- E. NFPA 70E Standard for Electrical Safety in the Workplace
- F. OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures

CONSTRUCTION

125907-2.1 REMOVAL OF REILS.

- H. Contractor shall examine the site to determine the extent of the work.
- I. Contractor shall coordinate work and any power outages with the Airport Manager, the respective Airport personnel, and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures, including, but not limited to, 29 CFR Section 1910.147 The Control of Hazardous Energy (lockout/tagout).
- J. Contractor shall comply with the requirements of FAA AC No. 150/5370-2E (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- K. Contractor shall comply with the applicable requirements of NFPA 70E Standard for Electrical Safety in the Workplace.
- L. Power for each respective REIL system shall be disconnected at the respective power source prior to removing the respective REIL system. Power for the existing REIL systems located on Runway 9 are understood to be powered from the respective runway lighting constant current regulator located the Airport Electrical Vault. Contractor shall field verify to confirm the respective power source for each REIL system.

Illinois Project: FWC-4105

M. The Contractor shall remove the REIL units when the runway is closed. The Contractor shall turn the REIL units over to the Airport Manager. The Contractor shall coordinate the removal of the existing REIL units with the Airport Manager. The Contractor shall remove the existing REIL bases and dispose of them off the airport site in a legal manner. The existing electrical cables from the vault shall be disconnected and abandoned in place or removed to accommodate new construction. The holes left from the removal of the concrete bases will be filled with earth material. The earth material will be compacted to prevent any future settlement. The earth material will be obtained from off the Airport site. The disturbed area will be restored, graded, and seeded to the satisfaction of the Engineer, and will be considered as an incidental item to the removal of the REIL units.

N. Existing airfield lighting cables associated with airfield lighting to be removed shall be abandoned in place unless it conflicts with new work and then it shall be removed at no additional cost to the Contact. If the Contractor elects to salvage the cable within the circuit to be removed, shown in the Construction Plans as cable to be abandoned, any cost associated with removal of the cable shall be considered incidental to the Contract and no additional compensation will be allowed.

BASIS OF PAYMENT

<u>125907-3.1.</u> This work will be paid for at the contract unit bid price per pair for REIL Removal. Said price and payment shall constitute full compensation for removing the existing REIL units; for all excavating and backfilling, for furnishing all earth material, materials, labor, tools, equipment, and incidentals necessary to complete this item of work.

Payment will be made under:

Item AR125907 Remove REILS - per pair

END OF ITEM AR125907

Illinois Project: FWC-4105

ITEM AR125989 REFURBISH PLASI

DESCRIPTION

<u>125989-1.1</u> This item of work shall consist of adding a safety switch and associated conduit, wiring, fittings, grounding, and accessories to each existing Pulse Light Approach Slope Indicator (PLASI) as detailed on the Plans and in accordance with this Special Provision.

<u>125989-1.2 REFERENCES</u>

- A. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 Fittings Rigid Metal Conduit and EMT.
- C. NEMA TC-2 Electrical Plastic Tubing and Conduit.
- D. NEMA TC-3 Fittings Rigid PVC Conduit and Tubing.
- E. NFPA 70 National Electrical Code (NEC), most current issue in force.
- F. UL Standard 6 Rigid Metal Conduit.
- G. UL Standard 467 Grounding and Bonding Equipment.
- H. UL Standard 486A-486B Wire Connectors.
- I. UL Standard 514B Conduit, Tubing and Cable Fittings.
- J. UL Standard 651 Schedule 40 and 80 Rigid PVC Conduit.
- <u>125989-1.3 SHOP DRAWINGS.</u> The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for PLASI units and materials to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** Contractor shall submit sufficient copies of shop drawings to meet the needs of his personnel, sub-contractor personnel, and equipment suppliers plus 4 copies to be retained by the Project Engineer. Shop drawings shall include the following information:
- A. Certification of compliance with the Airport Improvement Program Buy American Requirement and the Buy American Act for all materials and equipment.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such

Illinois Project: FWC-4105

statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.

- C. Provide cut sheets and manufacturer specifications for the safety switches.
- D. Provide cut sheets with manufacturer's name, catalog number, dimensions, material and UL listing for each type and size ground rod. Include certification of 100% domestic steel for ground rods.
- E. Provide cut sheets for all types of conduit used with the PLASI installation (for example galvanized rigid steel conduit and liquid-tight flexible metal conduit). Include certification that steel conduits are made with 100 percent domestic steel.

MATERIALS

125989-2.1 GALVANIZED RIGID STEEL CONDUIT. Galvanized rigid steel conduit (GRSC) shall be heavy wall, hot-dipped, galvanized steel pipe bearing the UL label and conforming to UL-6 and ANSI Specification C80.1. Couplings, connectors, and fittings for rigid steel conduit shall be threaded galvanized steel or galvanized malleable iron specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 and UL-514B. Set screw type fittings are not acceptable. Steel used to manufacture conduits shall be 100 percent domestic steel. Contractor shall provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.

<u>125989-2.2 SCHEDULE 40 PVC CONDUIT.</u> Schedule 40 PVC conduit shall be UL listed and comply with NEMA Specification TC-2 (Conduit), NEMA Specification TC-3 and UL-514B (for fittings), and UL-651 (Standard for rigid nonmetallic conduit), and shall be suitable for aboveground, direct earth burial, concrete encasement, and exposed applications.

125989-2.3 LIQUID-TIGHT FLEXIBLE METAL CONDUIT. Liquid-tight, flexible metal conduit shall consist of polyvinyl jacket over flexible hot dip galvanized steel tubing. The flexible conduit shall be completely sealed from liquids, dust, dirt, and fumes and be resistant to oil, gasoline, grease, and abrasion. Jacket shall also be sunlight-resistant. Liquid-tight flexible metal conduit shall be UL-listed, suitable for use as a grounding conductor, and comply with Article 350 of the NEC. **Liquid-tight flexible metal conduit and associated fittings shall be UL-listed to meet the requirements of NEC 350.6.** Liquid-tight flexible metal conduit shall be Anaconda Sealtite Type UA as manufactured by Anamet Electrical Inc., 1000 Broadway Avenue East, Mattoon, Illinois 61938-0039, (Phone: 217-234-8844), Liquatite Type LA as manufactured by Electri-Flex Company, 222 W. Central Ave., Roselle, Illinois 60172, (Phone: 630-529-2920 or 1-800-323-6174), or approved equal. Do not install liquid-tight, flexible metal conduit that is not UL listed. Confirm liquid-tight, flexible metal conduit bears the UL label prior to installation.

<u>125989-2.4 SAFETY SWITCH.</u> Furnish and install a safety switch for each PLASI as detailed on the Plans and specified herein. Safety switch shall be heavy duty, UL-listed, with amperage, voltage, number of poles, and type (fusible or not fusible), and accessories as detailed on the

Illinois Project: FWC-4105

Plans. Safety switch shall be pad lockable in the off position. Include ground lugs or grounding kits with the safety switch. Safety switches located outdoors, or in damp areas shall be in NEMA 3R and 12 or NEMA 4X enclosures without knockouts. Safety switch shall be as manufactured by Square D, Eaton Cutler-Hammer, or approved equivalent.

<u>125989-2.5 GROUND RODS.</u> Ground rods shall be 3/4-inch diameter by 10-foot long UL listed copper clad, with 10-mil minimum copper coating. Steel used to manufacture ground rods shall be 100 percent domestic steel.

<u>125989-2.6 LEGEND PLATES.</u> Legend plates shall be required for safety switches, circuit breakers, disconnects, etc. Legend plates shall be provided to identify the equipment controlled, the power source and voltage, and the function of each device. Legend plates shall be weatherproof and abrasion resistant phenolic material. Lettering shall be black letters on a white background, unless otherwise noted.

CONSTRUCTION METHODS

<u>125989-3.1.</u> The Contractor shall use care when rewiring and adding grounding to each respective PLASI unit so that it is not damaged. Any damage incurred will be repaired to the satisfaction of the Engineer, and no additional compensation will be allowed.

Contractor shall coordinate work and any power outages with the Airport Manager, the respective Airport personnel, and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures, including, but not limited to, 29 CFR Section 1910.147 The Control of Hazardous Energy (lockout/tagout).

The Contractor shall install a buck-boost transformer in the electrical vault to accommodate voltage drop at each respective PLASI unit. The Contractor will also install other associated electrical equipment in the vault as required to provide electrical power to each respective PLASI unit. The furnishing and installation of boost transformers and other electrical equipment in the vault will be paid for under item AR109200 Install Electrical Equipment.

125989-3.2 ELECTRICAL. The Contractor shall furnish and install all electrical materials necessary for complete and operational installation of the PLASI as shown on the Plans and detailed herein. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of the NFPA 70 - National Electrical Code (NEC) most current issue in force. Electrical equipment shall be installed in conformance with the respective manufacturer's directions and recommendations for the respective application. Any installations which void the UL listing, ETL listing, (or other third party listing), and/or the manufacturer's warranty of a device will not be permitted.

Illinois Project: FWC-4105

125989-3.3 CABLE INSTALLATION FOR PLASI. The Contractor will be responsible for installing all required power cables in accordance with the PLASI unit manufacturer's recommendations. Installation of cables shall conform to Item 108, per the respective equipment manufacturer's recommendations, and as detailed on the Plans. The existing cable and conduit terminated at each respective PLASI unit shall be disconnected from the respective PLASI and reconnected to the safety switch to be added at each PLASI location. New conduit and conductors shall be furnished and installed from the load side of the safety switch to the PLASI unit as described in the Grounding requirements and as detailed on the Plans.

125989-3.4 CONDUIT INSTALLATION FOR PLASI. Installation of conduit shall conform to Item 110, the respective PLASI manufacturer's installation instructions and/or recommendations, as detailed on the Plans and as specified herein. Do not install liquid-tight, flexible metal conduit that is not UL-listed.

125989-3.5 INSTALLATION OF SAFETY SWITCHES: All safety switches shall be provided with appropriate mounting hardware and strut support. Strut support shall be stainless steel Unistrut P-1000-SS, or hot dipped, galvanized steel strut support, Unistrut P-1000-HG, or approved equal. Provide zinc rich paint applied to field cuts of strut support to minimum the potential for corrosion per the respective strut support manufacturer's recommendation. All hardware shall be corrosion resistant. Mount safety switches securely in accordance with the manufacturer's recommendations/instructions and as required for the respective application. Inspect all safety switches for proper operation, tight and secure connections, and correctness. All safety switch enclosures shall be bonded to ground with a ground lug or bar and ground wire. Field cut holes in safety switch enclosures to accommodate conduit entrances. Where safety switches are provided with concentric knockouts, and the respective conduit does not use the largest knockout, install a grounding bushing with ground wire connections between the bushing and the ground bus. Do not use safety switch enclosures for a splice box or for a pull box. Do not route control wires or other circuit wiring through a safety switch. Where splices are required or other control circuit wires are installed in the respective conduit to a safety switch, provide a separate junction box to accommodate the splices and/or other circuit conductors. The furnishing and installing of the safety switch at the PLASI unit shall be incidental to Item AR125989 Refurbish PLASI -- per each.

125989-3.6 GROUNDING FOR PLASI. Grounding for PLASI shall conform to the respective PLASI manufacturer's installation instructions, as detailed on the Plans, and as specified herein. The power circuit to the PLASI unit shall include an equipment ground wire. To comply with the requirements of National electrical Code and the PLASI manufacturer's installation instructions a safety switch/disconnect shall be installed at the PLASI. The 120 VAC feeder conductors from the vault shall terminate on this safety switch/disconnect. Furnish and install a 3/4-in. diameter by 10-ft long, copper-clad ground rod at the site of the PLASI unit. Top of ground rod shall be buried 30 in. below grade. All connections to ground rods shall be made with exothermic weld type connectors, Cadweld by Erico Products, Inc., Solon, Ohio, (Phone 1-800-248-9353), Thermoweld by Continental Industries, Inc., Tulsa, Oklahoma (Phone 918-663-1440) or Ultraweld by Harger Lightning Protection Grounding Equipment, Grayslake, Illinois (Phone 1-800-842-7437), or approved equal. Exothermic weld connections shall be installed in conformance with the respective manufacturer's directions using molds as required for each

Illinois Project: FWC-4105

above the frangible coupling.

respective application. Bolted connections will not be permitted at ground rods or at buried grounding electrode conductors. Connect the safety switch enclosure frame/ground bar to the ground rod with a #6 AWG bare stranded copper grounding electrode conductor. From the load side of the safety switch install 1 #10 THWN, 1 #10 THWN Neutral, and 1 #10 equipment ground in 3/4-in. liquid-tight, flexible metal conduit to the PLASI unit. The PLASI unit shall also be bonded to the ground rod with a #6 AWG bare stranded copper conductor. Ground wire connection to a PLASI unit shall be with a two-hole tongue compression lug bolted to the bottom of the PLASI housing or with a UL-listed pipe clamp connected to one of the PLASI legs located

<u>125989-3.7 GROUNDING REQUIREMENTS.</u> Grounding shall conform to the following as applicable: The Contractor shall furnish and install all grounding shown on the Plans and/or as may be necessary or required to make a complete grounding system, as required by the latest NFPA 70 – National Electrical Code in force. The reliability of the grounding system is dependent on careful, proper installation, and choice of materials. Improper preparation of surfaces to be joined to make an electrical path, loose joints, or corrosion can introduce impedance that will seriously impair the ability of the ground path to protect personnel and equipment and to absorb transients that can cause noise in communications circuits. The following functions are particularly important to ensure a reliable ground system:

- A. All products associated with the grounding system shall be UL-listed and labeled.
- B. All bolted or mechanical connections shall be coated with a corrosion preventative/conductive grease and lubricant suitable for electrical connections and grounding connections, before joining, Sanchem Inc. "NO-OX-ID "A-Special" compound, Burndy Penetrox E, or approved equal.
- C. Metallic surfaces to be joined shall be prepared by the removal of all non-conductive material, per 2011 NEC Article 250-12. All copper bus bars must be cleaned prior to making connections to remove surface oxidation.
- D. Metallic raceway fittings shall be made up tight to provide a permanent low impedance path for all circuits. Metal conduit terminations in enclosures shall be bonded to the enclosure with UL-listed fittings suitable for grounding. Provide grounding bushings with bonding jumpers for all metal conduits entering an enclosure through concentric or eccentric knockouts that are punched or otherwise formed so as to impair the electrical connection to ground. Standard locknuts or bushings shall not be the sole means for bonding where a conduit enters an enclosure through a concentric or eccentric knockout.
- E. Furnish and install ground rods at all locations where shown on the Plans or specified herein. Ground rods shall be spaced, as detailed on the Plans, and in no case spaced less than one rod length apart. All connections to ground rods and/or buried grounding electrode conductors shall be made with exothermic, weld-type connectors, Cadweld by Erico Products, Inc., Solon, Ohio, (Phone: 1-800-248-9353), Thermoweld by Continental Industries, Inc., Tulsa, Oklahoma (Phone: 918-663-1440), or approved equal. Exothermic-weld connections shall be installed in conformance with the respective manufacturer's directions using molds, as

Illinois Project: FWC-4105

required for each respective application. Bolted connections will not be permitted at ground rods or at buried grounding electrode conductors.

- F. All connections, located above grade, between the different types of grounding conductors shall be made using UL-listed, double-compression, crimp-type connectors or UL-listed, bolted ground connectors. For ground connections to enclosures, cases, and frames of electrical equipment not supplied with ground lugs, the Contractor shall drill required holes for mounting a bolted, ground connector. All bolted, ground connectors shall be Burndy, Thomas and Betts, or equal. Tighten connections to comply with tightening torques in UL Standard 486A to assure permanent and effective grounding.
- G. All metal equipment enclosures, conduits, cabinets, boxes, receptacles, etc. shall be bonded to the respective grounding system.
- H. Each new feeder circuit and/or branch circuit shall include an equipment ground wire. Metal raceway or conduit shall not meet this requirement. The equipment ground wire from equipment shall not be smaller than allowed by 2011 NEC Table 250-122 "Minimum Size Conductors or Grounding Raceway and Equipment." When conductors are adjusted in size to compensate for voltage drop, equipment-grounding conductors shall be adjusted proportionately according to circular mil. area. All equipment ground wires shall be copper, either bare or insulated, green in color. Where the equipment grounding conductors are insulated, they shall be identified by the color green, and shall be the same insulation type as the phase conductors.
- I. Install grounding electrode conductors and/or individual ground conductors in Schedule 40 or Schedule 80 PVC conduit. Coordinate the installation of PVC conduit sleeves into the PLASI foundations to accommodate grounding electrode conductor installations from the respective PLASI unit to the respective ground rod.

<u>125989-3.8 PLASI OPERATION.</u> Control of the PLASI units shall be with the L-854 radio receiver and lighting contactors located in the vault. The lighting contactor panel shall include an "ON-OFF-AUTO" three position selector switch for each PLASI system. In the manual mode of operation the PLASI units shall be activated by the respective "ON-OFF-AUTO" selector switch on the lighting contactor panel. In the "ON" position the PLASI units will be on. In the "AUTO" mode of operation the PLASI units shall be activated by L-854 radio receiver control as follows:

3 clicks – On

5 clicks - Remain on

7 clicks – Remain on

METHOD OF MEASUREMENT

<u>125989-4.1.</u> The refurbishment of each PLASI system to be furnished and installed shall be measured for payment as a unit price per each and shall include shall consist of adding a safety switch and associated conduit, wiring, fittings, grounding, and accessories to each existing Pulse

Illinois Project: FWC-4105

Light Approach Slope Indicator (PLASI) and all coordination, excavating, labor, tools, testing, restoration, and incidentals as necessary to furnish a complete and operational PLASI system as approved by the Resident Engineer.

BASIS OF PAYMENT

<u>125989-5.1.</u> Payment shall be made at the contract unit price per each. This price and payment shall be full compensation for furnishing and installing all materials; for all excavating, labor, tools, equipment and incidentals necessary to complete this item of work.

Payment will be made under:

Item AR125989 Refurbish PLASI - per each

END OF ITEM AR125989

Illinois Project: FWC-4105