

SUMMARY OF QUANTITIES

F.A.I. RTE. 94/90	SECTION #-----	COUNTY COOK	TOTAL SHEETS 556	SHEET NO. 5
STA. FED. ROAD DIST. NO. 62300		TO STA. ILLINOIS FED. AID PROJECT 1818, ETC, 2324.6-1P/R-8		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE				
				ROADWAY J000-2A	SIGNING Y002-1C	SURVEILLANCE Y032-1F	SN 016-2625 X928-2A	SN 016-0142 SN 016-1148 SFTY-2A
20200100	EARTH EXCAVATION	CU YD	217,181	217,181				
20800150	TRENCH BACKFILL	CU YD	37,065	37,065				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	219,063	219,063				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,139	2,139				
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	3,208	3,208				
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	3,208	3,208				
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	540	540				
25000210	SEEDING, CLASS 2A	ACRE	1	1				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	99	99				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	99	99				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	99	99				
25100115	MULCH, METHOD 2	ACRE	1	1				
25100630	EROSION CONTROL BLANKET	SQ YD	5,347	5,347				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	110	110				
28000400	PERIMETER EROSION BARRIER	FOOT	1,744	1,744				
28000510	INLET FILTERS	EACH	209	209				
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	225,099	225,099				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	456				456	
42001300	PROTECTIVE COAT	SQ YD	227,431	227,431				
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	148,867	148,867				
42101448	LUG SYSTEM COMPLETE 48'	EACH	2	2				
42101452	LUG SYSTEM COMPLETE 52'	EACH	1	1				
44000013	BITUMINOUS SURFACE REMOVAL, 5"	SQ YD	143				143	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	82				82	
44000100	PAVEMENT REMOVAL	SQ YD	151,914	151,914				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8,832	8,832				
44000700	APPROACH SLAB REMOVAL	SQ YD	219				219	
44001980	CONCRETE BARRIER REMOVAL	FOOT	21,318	21,318				
44004250	PAVED SHOULDER REMOVAL	SQ YD	63,649	63,649				
44201474	CLASS C PATCHES, TYPE I	SQ YD	25	25				
44201476	CLASS C PATCHES, TYPE II	SQ YD	60	60				
44201478	CLASS C PATCHES, TYPE III	SQ YD	50	50				
44213200	SAW CUTS	FOOT	100	100				
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	36	36				
50300225	CONCRETE STRUCTURES	CU YD	57	57				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,316	1,204			112	

* SPECIALITY ITEM



REVISIONS NAME	DATE

S00-1

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 NB EXPRESS LANE RECONSTRUCTION

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: 7/7/05

DRAWN BY: TAI
 CHECKED BY: PJM

I:\030019\035\001 48\J5-CA00V4-SP4026-311
 06/28/2005 12:43:51 PM