

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
62300		1818, ETC, 2324.6-1PR-8		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE					
				ROADWAY	SIGNING	SURVEILLANCE	SN 016-2625	SN 016-0142 SN 016-1148	
				J000-2A	Y002-1C	Y032-1F	X928-2A	SFTY-2A	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	31,465	31,465					
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	218	218					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	113,394	113,394					
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	15,638	15,638					
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	15,925	15,925					
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	3,774	3,774					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	64,198	64,198					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	25,315	25,315					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	24,312	24,312					
72000100	SIGN PANEL - TYPE 1	SQ FT	12		12				
72000200	SIGN PANEL - TYPE 2	SQ FT	96		96				
72000300	SIGN PANEL - TYPE 3	SQ FT	4,186		4,186				
72100100	SIGN PANEL OVERLAY	SQ FT	2		2				
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	72		72				
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	591		591				
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	12		12				
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	488		488				
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1,890		1,890				
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	88		88				
73000100	WOOD SIGN SUPPORT	FOOT	17		17				
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" x 4'-6")	FOOT	72		72.0				
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	142		142				
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	332		332				
73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FT	403		403				
73400100	CONCRETE FOUNDATIONS	CU YD	7		7				
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	179		179				
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	6		6				
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	7		7				
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	14		14				
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	327	327					
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	100,671	100,671					
78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	26,758	26,758					
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	21,714	21,714					
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	5,824	5,824					
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	1,643	1,643					
78200530	BARRIER WALL MARKERS, TYPE C	EACH	414	414					
78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	1	1					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	26,297	26,297					
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	299			299			

* SPECIALITY ITEM @ @ SFTY - 3C



REVISIONS	
NAME	DATE

S00-4
ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
SUMMARY OF QUANTITIES
SCALE: NONE
DATE: 7/7/05
DRAWN BY: TAI
CHECKED BY: PJM

PA: 03/09/05 05:00 PM FAX: 312/251-3015