

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	COOK	556	30
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
62300		(1818, ETC, 2324.6-1PR-8	

PAY ITEM	SIGN NO.	ISO161094 L056.60	TS17-01	ES17-01	W12-1	W4-3	TS17-03	ISO161094 L056.43	ES17-02 ES17-03	TS17-02	TS18-01	TS18-02	ISO161094 L055.94	ES18-01	TS18-03	ES19-02	180161094 L055.73	ES19-04	PS09-02	ISO161094 L055.41	ES20-01	
	STATION	4536+00	4540+00	4540+17	4542+40	4542+90	4544+00	4545+35	4545+43	4545+50	4555+00	4569+50	4571+00	4571+02	4571+00	4582+26	4582+26	4597+12	4598+65	4599+00	4608+15	
	ROUTE	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94	I-94
	SIZE (HEIGHTxLENGTH)		8'x15'		4'x4'	4'x4'	4'x3'		8'x15' 8'x11' 4'x3'	8'x11'	8'x10'	8'x10'	7'x10'	8'x10' 8'x10' 8'x15'	8'x15'	9'-6"x26' 12'-6"x19'-6"	14'x23' 14'x17'-6"		20'-1"x8'-6"			4'x3'
UNIT																						
SIGN PANEL - TYPE 1	SQ FT				16	16																
SIGN PANEL - TYPE 2	SQ FT																					
SIGN PANEL - TYPE 3	SQ FT																567					
SIGN PANEL OVERLAY	SQ FT										2											
REMOVE SIGN PANEL - TYPE 2	SQ FT								12													12
REMOVE SIGN PANEL - TYPE 3	SQ FT								208					280								
RELOCATE SIGN PANEL - TYPE 2	SQ FT								12													
RELOCATE SIGN PANEL - TYPE 3	SQ FT		120.0							88	80	80					120					
STRUCTURAL STEEL SIGN SUPPORT-BREAKAWAY	POUND		450.0							450	270	270					450					
TELESCOPING STEEL SIGN SUPPORT	FOOT				12	12																
WOOD SIGN SUPPORT	FOOT								17													
OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT																		69.8			
OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT																56					
CONCRETE FOUNDATIONS	CU YD		1.4							1.4	1.4	1.4										
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	22.4						19.8					20.4						26.1	34.0		
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH			1					1								1					
REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH															1						
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH			2					2						2			1				
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT																56		56			
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER (VMS)	EACH																	1				
TEMPORARY INFORMATION SIGNING	SQ FT																					

PAY ITEM	SIGN NO.	ES20-03	180161094 L054.97	ES21-01	180161094 L054.72	MILE MARKER	TEMPORARY INFORMATION SIGN	TEMPORARY INFORMATION SIGN	3530+00 4528+55	TEMPORARY INFORMATION SIGN
	STATION	4622+25	4622+31	4635+47	4635+47	VARIOUS	4515+00	4519+00		4528+50
	ROUTE	I-94	I-94	I-94	I-94	I-94	I-94	I-94		I-94
	SIZE (HEIGHTxLENGTH)	10'-6"x26' 13'x16'	14'x23' 14'x17'-6"	13'x26' 13'x19'-6"	14'x23' 14'x17'-6"	3'x1'	7' X 10'	7' X 10'	4.5' X 6' 4.5' X 6'	4.5' X 6' 4.5' X 6'
UNIT										
SIGN PANEL - TYPE 1	SQ FT					12				
SIGN PANEL - TYPE 2	SQ FT									
SIGN PANEL - TYPE 3	SQ FT		567		567		70	70		51
SIGN PANEL OVERLAY	SQ FT									
REMOVE SIGN PANEL - TYPE 2	SQ FT									
REMOVE SIGN PANEL - TYPE 3	SQ FT									
RELOCATE SIGN PANEL - TYPE 2	SQ FT									
RELOCATE SIGN PANEL - TYPE 3	SQ FT									
STRUCTURAL STEEL SIGN SUPPORT-BREAKAWAY	POUND									
TELESCOPING STEEL SIGN SUPPORT	FOOT					16				
WOOD SIGN SUPPORT	FOOT									
OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT									
OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT		52		56					
CONCRETE FOUNDATIONS	CU YD									
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD									
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH									
REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1	1	1	1					
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH									
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT		52		56					
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER (VMS)	EACH									
TEMPORARY INFORMATION SIGNING	SQ FT							54	30	

**Edwards
AND Kelcey**
ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION

SIGNING
SCHEDULE

SCALE: NONE
DATE: 7/7/05

DRAWN BY: TAI
CHECKED BY: GG

06/28/2005 08:26:27 AM