

SCHEDULE OF STORM SEWERS

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	COOK	556	143A
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
62300		1818, ETC. 2324.6-1PJR-8	

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T2 12	SS CL A T2 15	SS CL A T2 18	SS CL A T2 21	SS CL A T2 24	SS CL A T2 27	SS CL A T2 30	SS CL A T2 33	SS CL A T2 36	SS CL A T2 42	SS CL A T2 48	SS CL A T3 12	SS CL A T3 21	SS CL A T3 24	SS CL A T3 30	SS CL A T3 36	SS CL A T3 42	SS CL B T1 12	SS CL B T1 15	TRENCH BACKFILL
25-08	25-06	0.32																								281.4
25-06	JC T2 25-01	0.32																				131				281.4
25-09	25-08	0.41		25																		45				86.6
25-10	25-08	0.45																								4.6
25-11	25-10	0.60	51																	98						184.4
25-12	25-10	0.44							32																	8.8
25-13	25-01	1.00	2																							9.8
25-14	25-12	0.72						44																		0.5
25-15	25-06	1.00	6																							11.3
25-16	25-10	1.00	1																							0.5
26-01	25-14	0.50	212																							0.5
26-02	26-03	0.79		29																						41.1
26-03	26-05	0.79		6																						5.0
26-04	26-05	0.68	30																							1.3
26-05	JC T2 26-01	0.45																								5.8
26-06	JC T2 26-01	1.00	31									42														73.2
26-07	27-02	0.54	38																							4.7
27-01	27-02	0.57	36																							6.6
26-08	27-03	0.59	46																							6.2
27-02	27-03	0.84							3																	8.0
27-03	27-06	0.45												193												1.0
27-04	27-05	0.50	30																							178.9
27-05	27-06	1.68	6																							5.8
27-07	27-06	0.50	45																							1.0
27-06	27-08	0.32											71													7.8
27-10	27-08	1.44			7																					46.9
27-08	JC T2 27-01*	0.32																								1.0
27-09	27-10	0.64			2																					24.0
27-12	JC T2 27-01*	0.91	31																							0.5
27-13	27-14	2.00	8																							6.7
27-14	27-15	3.30	3																							1.2
27-15	27-17	0.20												129												0.5
27-16	27-17	4.00	44																							130.8
27-17	28-02	0.20													50											6.7
28-01	28-02	2.01	2																							11.7
28-02	28-03	0.15																								0.5
28-04	28-05	0.50	11																							130.7
28-06	28-05	1.00		11																						1.7
28-03	28-07	0.15																								1.8
28-05	28-07	0.34		3																						70.8
28-09	28-08	0.50		11																						0.5
28-10	28-09	0.50	11																							1.8
28-07	JC T2 28-01*	0.15																								1.9
28-08	JC T2 28-01*	1.00	3																							175.8
28-11	28-10	0.50	33																							0.6
28-12	28-06	0.50	35																							7.0
28-13	28-15	4.06							48																	7.2
28-14	28-15	3.30	3																							17.3
28-15	28-07	0.50		165																						0.5
																										31.5

DS-28A



NOTE: \* INDICATED STRUCTURE BEEN CONSTRUCTED IN CONTRACT 62302

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
 31ST STREET TO 71ST STREET  
 NB EXPRESS LANE RECONSTRUCTION  
 DRAINAGE SCHEDULE  
 PROPOSED STORM SEWERS  
 SCALE: 1" = N.T.S.  
 DATE: 7/7/05  
 DRAWN BY: MJO  
 CHECKED BY: LPN

06/27/2005 07:47:10 PM