

SCHEDULE OF STORM SEWERS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	143A
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62300	* (1818, ETC, 2324.6-IPR-8			

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T2 12	SS CL A T2 15	SS CL A T2 18	SS CL A T2 21	SS CL A T2 24	SS CL A T2 27	SS CL A T2 30	SS CL A T2 33	SS CL A T2 36	SS CL A T2 42	SS CL A T2 48	SS CL A T3 12	SS CL A T3 21	SS CL A T3 24	SS CL A T3 30	SS CL A T3 36	SS CL A T3 42	SS CL B T1 12	SS CL B T1 15	TRENCH BACKFILL
25-08	25-06	0.32																								281.4
25-06	JC T2 25-01	0.32																								86.6
25-09	25-08	0.41		25																						4.6
25-10	25-08	0.45																								184.4
25-11	25-10	0.60	51																98							8.8
25-12	25-10	0.44									32															23.8
25-13	25-01	1.00	2																							0.5
25-14	25-12	0.72					44																			11.3
25-15	25-06	1.00	6																							0.5
25-16	25-10	1.00	1																							0.5
26-01	25-14	0.50	212																							41.1
26-02	26-03	0.79																								5.1
26-03	26-05	0.79		29																						1.5
26-04	26-05	0.68	30	6																						5.8
26-05	JC T2 26-01	0.45																								73.2
26-06	JC T2 26-01	1.00	31								42															4.7
26-07	27-02	0.54	38																							6.6
27-01	27-02	0.57	36																							8.6
26-08	27-03	0.59	46																							8.0
27-02	27-03	0.84		3																						1.0
27-03	27-06	0.45																								178.9
27-04	27-05	0.50	30								193															5.8
27-05	27-06	1.68	6																							1.0
27-07	27-06	0.50	45																							7.8
27-06	27-08	0.32																								46.9
27-10	27-08	1.44				7																				1.0
27-08	JC T2 27-01*	0.32																								24.0
27-09	27-10	0.64				2																				0.5
27-12	JC T2 27-01*	0.91	31																							6.7
27-13	27-14	2.00	8																							1.8
27-14	27-15	3.30	3																							0.7
27-15	27-17	0.20																								130.8
27-16	27-17	4.00	44																							6.7
27-17	28-02	0.20																								11.7
28-01	28-02	2.01	2																							0.9
28-02	28-03	0.15																								130.7
28-04	28-07	3.34																								2.7
28-06	28-05	1.00																								17.1
28-03	28-07	0.15																								70.8
28-05	28-04	0.34																								9.1
28-09	28-08	0.50																								1.8
28-10	28-09	0.50	11																							1.9
28-07	JC T2 28-01*	0.15																								175.8
28-08	JC T2 28-01*	1.00	3																							0.6
28-11	28-10	0.50	33																							7.0
28-12	28-06	0.50	35																							7.2
28-13	28-15	4.06																								17.3
28-14	28-15	3.30	3																							0.5
28-15	28-07	0.50		165																						31.5
PLUG	10-09	1.00																								3.7
PLUG	11-11	1.00	2																							0.5
PLUG	11-06	1.00																								1.7
PLUG	11-07	1.00																								1.8
PLUG	11-10	1.00	2																							0.6
PLUG	12-04	1.00		3																						1.2
PLUG	12-08	1.00	5																							1.5
PLUG	13-04	1.00																								0.7
PLUG	13-10	1.00	2																							0.5
PLUG	13-15	1.00		2																						0.6
PLUG	13-18	1.00	3																							0.8
PLUG	13-20	1.00	3																							0.8
PLUG	14-03	1.00	2																							0.6
PLUG	14-07	0.50	2																							0.5
PLUG	15-05	0.50	2																							0.5
PLUG	15-09	0.50	2																							0.5
PLUG	15-17	1.00	2																							0.5
PLUG	15-21	1.00	2																							0.5
16-07	15-19	1.00	132																							40.7
PLUG	16-07	1.00	5																							1.3



DS-28A

REVISIONS	
NAME	DATE
ADDENDUM 2	9/16/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
 31ST STREET TO 71ST STREET  
 NB EXPRESS LANE RECONSTRUCTION  
 DRAINAGE SCHEDULE  
 PROPOSED STORM SEWERS  
 SCALE: 1" = N.T.S.  
 DATE: 1/7/05  
 DRAWN BY: MJO  
 CHECKED BY: LPN



NOTE: \* INDICATED STRUCTURE BEEN CONSTRUCTED IN CONTRACT 62302

09/14/2005 02:50:43 PM