

SCHEDULE OF STORM SEWERS

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	•	COOK	556	145
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62300		• (1818, ETC, 2324.6-1PIR-8		

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 1, 12	SS CL A 1, 15	SS CL A 1, 18	SS CL A 1, 21	SS CL A 1, 24	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS CL A 2, 21	SS CL A 2, 24	SS CL A 2, 27	SS CL A 2, 30	SS CL A 2, 33	SS CL A 2, 36	SS CL A 2, 42	SS CL A 2, 48	SS CL A 3, 12	SS CL A 3, 21	SS CL A 3, 24	SS CL A 3, 27	SS CL A 3, 30	SS CL A 3, 36	SS CL A 3, 42	SS CL B 1, 12	SS CL B 1, 15	TRENCH BACKFILL (CU. YD.)
31-09	31-08	28.2	12	1.00%						28.2																			8.0	
EX MH	31-06	16.4	12	1.00%																							16.4		13.7	
31-10	31-09	48.1	12	1.00%						48.1																			11.2	
31-12	31-13	1.3	12	1.00%						1.3																			4.3	
31-14	31-13	26.8	12	1.00%						26.8																			4.3	
EX P	31-11	0.3	12	0.55%																							0.3		5.6	
31-15	31-14	46.9	12	1.00%						46.9																			0.4	
EX CB	31-15	5.9	12	1.00%						5.9																			14.9	
30-19	30-21	16.6	15	0.32%							16.6																		1.7	
30-18	30-19	1.3	12	1.00%						1.3																			6.0	
30-20	DMH30-01	17.7	12	1.00%						17.7																			70.3	
EX CB	30-17	10.9	12	1.00%																						10.9			62.9	
EX P	30-21	45.0	24	0.38%																			45.0						109.3	
32-15	JC32-01	50.0	42	0.10%															50.0										18.2	
33-09	32-15	124.8	30	0.21%											124.8														26.6	
33-16	33-09	61.8	27	0.44%											61.8														50.3	
33-20	33-16	86.0	21	0.44%																									7.7	
33-24	33-20	141.0	18	0.44%																									1.1	
33-08	33-09	0.8	18	1.00%																									2.2	
33-10	33-09	54.5	15	1.00%						54.5																			0.6	
33-05	33-08	9.7	12	1.00%						9.7																			0.4	
33-12	33-08	7.3	18	1.00%									7.3																0.6	
33-06	33-10	9.7	12	1.00%						9.7																			13.6	
33-13	33-10	7.3	12	1.00%						7.3																			6.2	
EX CB	33-04	13.6	12	1.00%																						13.6			6.2	
EX CB	33-11	21.5	18	1.00%									21.5																6.2	
33-15	33-16	1.3	12	1.00%						1.3																			0.1	
33-17	33-16	55.0	12	1.00%						55.0																			14.3	
33-14	33-15	2.0	12	1.00%						2.0																			1.8	
33-19	33-20	1.3	15	1.00%							1.3																		6.3	
33-21	33-20	55.0	12	1.00%						55.0																			1.8	
EX CB	33-21	0.9	12	1.00%						0.9																			231.8	
EX CB	33-18	1.8	15	1.00%																									74.8	
33-23	33-24	1.3	12	1.00%						1.3																			289.6	
33-25	33-24	55.0	12	1.00%						55.0																			131.2	
EX CB	33-22	1.8	12	1.00%																						1.8			1.0	
32-11	32-15	208.7	36	0.13%														208.7											2.7	
32-07	32-11	75.0	30	0.13%											75.0														1.0	
32-03	32-07	220.0	30	0.17%																						220.0			2.7	
31-18	32-03	140.5	27	0.32%											140.5														1.0	
32-16	JC32-01	4.5	12	1.00%						4.5																			2.7	
32-14	32-15	0.8	12	1.00%						0.8																			1.0	
33-02	32-14	11.0	12	1.00%						11.0																			2.7	
33-03	JC32-01	4.6	12	1.00%						4.6																			1.0	
32-10	32-11	0.8	15	1.00%							0.8																		1.0	

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
DRAINAGE SCHEDULES
PROPOSED STORM SEWER PIPES
SCALE: 1"=N.T.S. DRAWN BY: JAM
DATE: 07/07/05 CHECKED BY: DDM

DS-30

08/10/2005 08:24:47 PM H:\660\cor\94\90\AS\SHEET 5 660_A.DWG