

SCHEDULE OF STORM SEWERS

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	149
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62300		• (1818, ETC, 2324.6-1PIR-8		

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 1, 12	SS CL A 1, 15	SS CL A 1, 18	SS CL A 1, 21	SS CL A 1, 24	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS CL A 2, 21	SS CL A 2, 24	SS CL A 2, 27	SS CL A 2, 30	SS CL A 2, 33	SS CL A 2, 36	SS CL A 2, 42	SS CL A 2, 48	SS CL A 3, 12	SS CL A 3, 21	SS CL A 3, 24	SS CL A 3, 27	SS CL A 3, 30	SS CL A 3, 36	SS CL A 3, 42	SS CL B 1, 12	SS CL B 1, 15	TRENCH BACKFILL (CU. YD.)
42-05	41-17	62.5	33	0.11%													62.5													54.3
42-14	42-05	141.1	27	0.15%											141.1															108.0
42-19	42-14	180.0	27	0.17%											180.0															149.1
42-23	42-19	220.0	21	0.32%										220.0																141.7
42-04	42-05	0.8	18	0.25%										0.8																
42-06	42-05	54.5	15	1.00%										54.5																15.9
42-02	42-04	19.9	12	0.44%									19.9																	5.3
42-08	42-04	12.1	15	0.32%										12.1																3.6
42-03	42-06	19.9	12	1.00%									19.9																	1.8
42-09	42-06	12.1	12	1.00%									12.1																	0.9
42-07	42-08	0.7	15	1.00%										0.7																
42-10	42-07	10.3	15	1.00%										10.3																1.9
42-11	42-10	11.7	12	1.00%										11.7																1.1
EX P	42-01	1.6	12	2.10%																								1.6		
EX IN	42-03	3.6	12	1.00%										3.6																0.1
EX IN	42-06	0.9	12	1.00%										0.9																
42-13	42-14	0.8	12	1.00%										0.8																
42-15	42-14	54.4	12	1.00%										54.4																9.0
EX IN	42-15	4.5	12	1.00%										4.5																0.3
42-16	42-12	9.7	12	1.00%										9.7																0.6
EX CB	42-12	7.1	12	1.00%																								7.1		0.6
EX P	42-12	1.6	12	2.00%																								1.6		
42-18	42-19	0.8	12	1.00%										0.8																
42-20	42-19	51.3	12	1.00%										51.3																7.4
EX IN	42-20	13.7	12	1.00%										13.7																1.2
EX P	42-17	4.5	12	0.20%																								4.5		0.9
EX P	42-17	4.5	12	2.00%																								4.5		0.6
EX CB	42-17	8.2	12	1.00%																							8.2		1.0	
42-22	42-23	0.8	12	1.00%										0.8																
42-24	42-23	51.3	12	1.00%										51.3																5.3
EX CB	42-21	1.5	12	1.00%																								1.5		
41-15	41-17	31.4	42	0.10%																										45.6
41-11	41-15	125.0	42	0.10%																										202.4
41-07	41-11	195.0	36	0.11%																								195.0		390.9
41-03	41-07	190.0	36	0.13%																										223.8
40-11	41-03	180.0	30	0.17%																										191.3
40-07	40-11	145.5	21	0.25%																										56.0
40-03	40-07	96.0	18	0.32%																										29.0
41-14	41-15	0.8	12	1.00%										0.8																
41-16	41-15	54.5	12	1.00%										54.5																7.1
EX CB	41-13	7.2	12	1.00%																										1.3
EX P	41-13	2.0	12	2.10%																									7.2	0.1
EX IN	41-16	3.4	12	1.00%										3.4																0.1
41-10	41-11	0.8	12	1.00%										0.8																
41-12	41-11	54.5	12	1.00%										54.5																7.3

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
DRAINAGE SCHEDULES
PROPOSED STORM SEWER PIPES
SCALE: 1"=N.T.S
DATE: 07/07/05
DRAWN BY: JAM
CHECKED BY: DDM