62302 * (18)B, ETC, 2324.6-1PJR-9

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 94/90 * | C.R.D. BRI | COOK | 598 | 72 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

EB I-94/90 RAMP TO EB I-90 OVER I-94

MATCH LINE STA. 1395+00

VPI STA. 1401+80.00
ELEVATION 7.07

+0.96%

-1.24%

15.27' MIN. CLEARANCE

EXISTING ℄ SB I-94/90 EXPRESS LANES PROFILE

PROPOSED ℄ SB I-94/90 EXPRESS LANES PROFILE

ex = -2.20'
800.00' V.C.

23.48' MIN. CLEARANCE

MATCH LINE STA. 1410+00

| 1395+00 | 1396+00 | 1397+00 | 1398+00 | 1399+00 | 1400+00 | 1401+00 | 1402+00 | 1403+00 | 1404+00 | 1405+00 | 1406+00 | 1407+00 | 1408+00 | 1409+00 | 1410+00 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0.63 / 0.56 | 1.17 / 1.03 | 1.84 / 1.51 | 2.35 / 1.99 | 3.06 / 2.47 | 3.83 / 2.95 | 4.27 / 3.42 | 4.66 / 3.84 | 5.01 / 4.19 | 5.34 / 4.47 | 5.65 / 4.68 | 5.80 / 4.82 | 5.96 / 4.89 | 6.05 / 4.90 | 6.21 / 4.83 | 6.28 / 4.70 | 6.10 / 4.50 | 5.95 / 4.23 | 5.85 / 3.89 | 5.46 / 3.49 | 5.04 / 3.01 | 4.20 / 2.46 | 3.44 / 1.86 | 2.52 / 1.24 | 1.70 / 0.62 | 0.81 / -0.00 | -0.06 / -0.62 | -0.97 / -1.24 | -1.69 / -1.86 | -2.51 / -2.48 | -3.05 / -3.10 |

MATCH LINE STA. 1410+00

ex = 0.59'
250.00' V.C.

-1.24%

+0.63%

VPI STA. 1411+25.00
ELEVATION -4.65

20.63' MIN. CLEARANCE

WENTWORTH AVE. BRIDGE

63rd ST. BRIDGE

PROPOSED ℄ SB I-94/90 EXPRESS LANES PROFILE

EXISTING ℄ SB I-94/90 EXPRESS LANES PROFILE

15.62' MIN. CLEARANCE

MATCH LINE STA. 1425+00

| 1410+00 | 1411+00 | 1412+00 | 1413+00 | 1414+00 | 1415+00 | 1416+00 | 1417+00 | 1418+00 | 1419+00 | 1420+00 | 1421+00 | 1422+00 | 1423+00 | 1424+00 | 1425+00 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| -3.05 / -3.10 | -3.73 / -3.63 | -3.83 / -3.97 | -3.83 / -4.12 | -3.82 / -4.08 | -3.58 / -3.86 | -3.36 / -3.54 | -3.00 / -3.23 | -2.58 / -2.91 | -2.33 / -2.59 | -2.09 / -2.28 | -1.91 / -1.96 | -1.59 / -1.64 | -1.37 / -1.33 | -1.07 / -1.01 | -0.79 / -0.69 | -0.51 / -0.38 | -0.16 / -0.06 | 0.19 / 0.26 | 0.47 / 0.57 | 0.68 / 0.89 | 0.79 / 1.21 | 1.03 / 1.52 | 1.52 / 1.84 | 1.83 / 2.16 | 2.34 / 2.47 | 3.21 / 2.79 | 3.64 / 3.10 | 4.03 / 3.37 | 4.33 / 3.58 | 4.42 / 3.73 |

PRO-2

PLAN
SURVEYED
ALIGNMENT CHECKED
ALL DIM'S CHECKED
LAND TIES MADE
NOTE BOOK
NO.
BY:
DATE:

PLAN
SURVEYED
ALIGNMENT CHECKED
ALL DIM'S CHECKED
CROP TIES MADE
NOTE BOOK
NO.
BY:
DATE:

Edwards AND Kelcey
ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION
EXISTING AND PROPOSED PROFILES
SOUTHBOUND STA. 1395+00 TO STA. 1425+00

SCALE: H 1"=50' 0' 50' 100'
V 1"=5' 0' 5' 10'
DATE: 7/7/05
DRAWN BY: TAI
CHECKED BY: PJM

p:\630090135\Con 1A&S\CADD\S ppp5c132e.dgn
06/24/2005 09:28:04 AM