



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 25, 2016

SUBJECT: FAS Route 1279 (IL 178)
Project ACRS-1279(114)
Section (1)BR&I
LaSalle County
Contract No. 66992
Item No. 8, November 4, 2016 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised pages 5 and 52 of the Special Provisions
3. Revised sheets 1, 7, 8, 20, 21, 81, 89, 220, 223, 250, 251 and 276-279 of the Plans
4. Added sheet 325A to the Plans
5. Added Roadway and Structural Geotechnical Reports as Additional Information online.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Acting Bureau Chief of Design & Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger', followed by the letters 'P.E.' in a smaller font.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: K. F. Marchek, Region 2, District 3; Tim Kell; D. Carl Puzey; Estimates

JW/kf

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
XZ039900	REM PIER PROT CELL	L SUM	1.000				
X0300864	MAINT OF NAVIGATION	L SUM	1.000				
X0322464	ABAN FILL EX SAN MAN	EACH	3.000				
X0322791	FILL EXIST SAN SEWER	CU YD	75.000				
X0325279	CLASS SI CONC (MISC)	CU YD	0.700				
X0326498	GFCI20A DX RECEPTACLE	EACH	12.000				
X0326649	LINEAR DELIN PANELS 6	EACH	30.000				
X0326654	ORNAM LIGHT UNIT COMP	EACH	12.000				
X0326747	SANITARY FORCE MAIN 6	FOOT	99.000				
X0327980	PAVMT MRKG REM WTR BL	SQ FT	21,550.000				
X0900034	HLMR BRNG FIXED 1400K	EACH	12.000				
X1400113	LUM LED HM MED WATT	EACH	31.000				
X1400189	UD 2#6 #8G XLPUSE 1.5	FOOT	1,205.000				
X2130010	EXPLOR TRENCH SPL	FOOT	6,925.000				
X4400110	TEMP PAVT REMOVAL	SQ YD	6,669.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X4402805	ISLAND REMOVAL	SQ FT	254.000				
X5210160	HLMR BRG GUID EXP 450	EACH	12.000				
X5860110	GRANULAR BACKFILL STR	CU YD	602.000				
X6022810	MAN SAN 4 DIA T1F CL	EACH	4.000				
X6024875	TEMPORARY INLET	EACH	4.000				
X6026050	SANITARY MANHOLE ADJ	EACH	3.000				
X6026051	SAN MAN RECONST	EACH	1.000				
X6026623	VALVE BOX	EACH	3.000				
X6026632	VALVE BOX REMOVED	EACH	2.000				
X6061055	CONCRETE ISLAND SPL	SQ FT	689.000				
X6330705	RUB RAIL	FOOT	1,975.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7040125	PIN TEMP CONC BARRIER	EACH	1,085.000				
X7830060	GRV RCSD PM LTR & SYM	SQ FT	23.000				
X7830074	GRV RCSD PVT MRKG 7	FOOT	306.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7830076	GRV RCSD PVT MRKG 9	FOOT	1,337.000				
X7830090	GRV RCSD PVT MRKG 25	FOOT	120.000				
X8110454	CON AT ST 1 SS	FOOT	795.000				
X8110458	CON AT ST 2 SS	FOOT	70.000				
X8250505	LIGHT CONTROLLER SPL	EACH	1.000				
X8360110	LIGHT POLE FDN SPL	FOOT	70.000				
Z0004522	HMA DRIVEWAY PAVT 6	SQ YD	116.000				
Z0004530	HMA DRIVEWAY PAVT 8	SQ YD	130.000				
Z0004552	APPROACH SLAB REM	SQ YD	219.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018002	DRAINAGE SCUPPR DS-11	EACH	8.000				
Z0018010	DRAINAGE SCUPPR DS-33	EACH	8.000				
*ADD Z0034393	MODULAR EXPAN JT 9	FOOT	100.000				
*DEL Z0034396	MODULAR EXPAN JT 12	FOOT	400.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	108.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number
 ACRS-1279/114/
 *REVISED: OCTOBER 21, 2016

Route
 FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0054400	ROCK FILL	CU YD	6,392.000				
Z0057300	SAN SEW 18	FOOT	1,680.000				
Z0057500	SAN SEW 24	FOOT	80.000				
Z0062456	TEMP PAVEMENT	SQ YD	6,669.000				
Z0067450	STEEL CASINGS 15	FOOT	90.000				
20100500	TREE REMOV ACRES	ACRE	8.000				
20101000	TEMPORARY FENCE	FOOT	4,119.000				
20101400	NITROGEN FERT NUTR	POUND	990.000				
20101500	PHOSPHORUS FERT NUTR	POUND	990.000				
20101600	POTASSIUM FERT NUTR	POUND	990.000				
20200100	EARTH EXCAVATION	CU YD	7,355.000				
20201200	REM & DISP UNS MATL	CU YD	8,090.000				
20400800	FURNISHED EXCAVATION	CU YD	197,295.000				
20800150	TRENCH BACKFILL	CU YD	1,493.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	3,195.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
21101505	TOPSOIL EXC & PLAC	CU YD	17,680.000				
25000210	SEEDING CL 2A	ACRE	4.250				
25000300	SEEDING CL 3	ACRE	6.750				
25100115	MULCH METHOD 2	ACRE	2.500				
25100635	HD EROS CONTR BLANKET	SQ YD	40,764.000				
28000305	TEMP DITCH CHECKS	FOOT	803.000				
28000400	PERIMETER EROS BAR	FOOT	9,338.000				
28000500	INLET & PIPE PROTECT	EACH	10.000				
28100101	STONE RIPRAP CL A1	SQ YD	130.000				
28100105	STONE RIPRAP CL A3	SQ YD	1,578.000				
28100107	STONE RIPRAP CL A4	SQ YD	3,900.000				
28200200	FILTER FABRIC	SQ YD	4,883.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	19,913.000				
35100500	AGG BASE CSE A 6	SQ YD	3,971.000				
40200500	AGG SURF CSE A 6	SQ YD	844.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600275	BIT MATLS PR CT	POUND	10,873.000				
40600290	BIT MATLS TACK CT	POUND	2,752.000				
40600637	LB MM IL-9.5FG N70	TON	156.000				
40603080	HMA BC IL-19.0 N50	TON	188.000				
40603305	HMA SC "C" N30	TON	445.000				
40603340	HMA SC "D" N70	TON	359.000				
42000401	PCC PVT 9 JOINTED	SQ YD	13,972.000				
42001300	PROTECTIVE COAT	SQ YD	20,916.000				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	112.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	899.000				
42400800	DETECTABLE WARNINGS	SQ FT	128.000				
44000100	PAVEMENT REM	SQ YD	14,609.000				
44000158	HMA SURF REM 2 1/4	SQ YD	3,681.000				
44000200	DRIVE PAVEMENT REM	SQ YD	863.000				
44000500	COMB CURB GUTTER REM	FOOT	4,761.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44004250	PAVED SHLD REMOVAL	SQ YD	4,336.000				
44213200	SAW CUTS	FOOT	177.000				
48100500	AGGREGATE SHLDS A 6	SQ YD	2,098.000				
48203029	HMA SHOULDERS 8	SQ YD	185.000				
48300400	PCC SHOULDERS 9	SQ YD	5,750.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	409.000				
50200100	STRUCTURE EXCAVATION	CU YD	290.000				
50200300	COFFERDAM EXCAVATION	CU YD	273.000				
*REV 50200400	ROCK EXC STRUCT	CU YD	2,403.400				
50201121	COFFERDAM TYP 2 LOC 1	EACH	1.000				
50201122	COFFERDAM TYP 2 LOC 2	EACH	1.000				
50300225	CONC STRUCT	CU YD	2,425.000				
50300255	CONC SUP-STR	CU YD	1,828.000				
50300260	BR DECK GROOVING	SQ YD	4,579.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*REV 50300265	SEAL COAT CONC	CU YD	658.000				
50300280	CONCRETE ENCASEMENT	CU YD	15.400				
50300300	PROTECTIVE COAT	SQ YD	7,711.000				
50301350	CONC SUPSTR APP SLAB	CU YD	140.200				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	10,512.000				
50800105	REINFORCEMENT BARS	POUND	30.000				
50800205	REINF BARS, EPOXY CTD	POUND	910,030.000				
50800515	BAR SPLICERS	EACH	96.000				
50800530	MECHANICAL SPLICERS	EACH	384.000				
50901720	BICYCLE RAILING	FOOT	3,756.000				
50901750	PARAPET RAILING	FOOT	1,213.000				
51201800	FUR STL PILE HP14X73	FOOT	1,847.000				
51202305	DRIVING PILES	FOOT	1,847.000				
51203800	TEST PILE ST HP14X73	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE -
 Code - 99 - -
 District - 3 - -
 Section Number - (1)BR&I

Project Number
 ACRS-1279/114/
 *REVISED: OCTOBER 21, 2016

Route
 FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51204650	PILE SHOES	EACH	44.000				
51500100	NAME PLATES	EACH	1.000				
52100520	ANCHOR BOLTS 1	EACH	48.000				
52100540	ANCHOR BOLTS 1 1/2	EACH	72.000				
52200020	TEMP SOIL RETEN SYSTM	SQ FT	740.000				
542A0235	P CUL CL A 1 30	FOOT	76.000				
542A0241	P CUL CL A 1 36	FOOT	52.000				
542A5473	P CUL CL A 1 EQRS 18	FOOT	117.000				
542A5479	P CUL CL A 1 EQRS 24	FOOT	172.000				
5421A030	P CUL CL A 1 30 TEMP	FOOT	59.000				
5421A036	P CUL CL A 1 36 TEMP	FOOT	15.000				
54213465	END SECTIONS 30	EACH	2.000				
54213471	END SECTIONS 36	EACH	2.000				
54213657	PRC FLAR END SEC 12	EACH	1.000				
54213660	PRC FLAR END SEC 15	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54213663	PRC FLAR END SEC 18	EACH	2.000				
54213675	PRC FLAR END SEC 30	EACH	2.000				
54213681	PRC FLAR END SEC 36	EACH	1.000				
54214713	PRCF END S EL EQRS 18	EACH	6.000				
54214719	PRCF END S EL EQRS 24	EACH	8.000				
54215553	MET END SEC 18	EACH	1.000				
5422A012	P CUL CL A 2 12 TEMP	FOOT	103.000				
5425A015	P CUL CL A 5 15 TEMP	FOOT	82.000				
5425A018	P CUL CL A 5 18 TEMP	FOOT	72.000				
550A0050	STORM SEW CL A 1 12	FOOT	10.000				
550A0070	STORM SEW CL A 1 15	FOOT	16.000				
550A4000	SS CL A 1 EQRS 18	FOOT	337.000				
550A4100	SS CL A 1 EQRS 24	FOOT	497.000				
56100600	WATER MAIN 6	FOOT	769.000				
56101142	DI WAT MN RED, 4 X 6	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
56104900	WATER VALVES 6	EACH	3.000				
56108800	TAP VALVE & SLEEVE 6	EACH	1.000				
56200300	WATER SERV LINE 1	FOOT	7.000				
56400500	FIRE HYDNPTS TO BE REM	EACH	2.000				
56400600	FIRE HYDRANTS	EACH	2.000				
58700300	CONCRETE SEALER	SQ FT	2,334.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	174.000				
60100060	CONC HDWL FOR P DRAIN	EACH	14.000				
60103700	PIPE DRAINS CS 18	FOOT	185.000				
60108501	PIPE UNDERDR T 3	FOOT	8,210.000				
60218400	MAN TA 4 DIA T1F CL	EACH	7.000				
60236200	INLETS TA T8G	EACH	1.000				
60240301	INLETS TB T8G	EACH	1.000				
60240327	INLETS TB T23F&G	EACH	1.000				
60266600	VALVE BOX ADJ	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60500205	FILL CATCH BAS	EACH	1.000				
60500305	FILL INLETS	EACH	17.000				
60605000	COMB CC&G TB6.24	FOOT	106.500				
60608300	COMB CC&G TM2.12	FOOT	482.500				
63000001	SPBGR TY A 6FT POSTS	FOOT	3,475.000				
63100045	TRAF BAR TERM T2	EACH	1.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	1.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	2.000				
63200310	GUARDRAIL REMOV	FOOT	4,895.000				
66600105	FUR ERECT ROW MARKERS	EACH	16.000				
66700205	PERM SURV MKRS T1	EACH	14.000				
66900200	NON SPL WASTE DISPOSL	CU YD	6,650.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	13.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number
 ACRS-1279/114/
 *REVISED: OCTOBER 21, 2016

Route
 FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
67000400	ENGR FIELD OFFICE A	CAL MO	30.000				
67100100	MOBILIZATION	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	300.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	72.000				
70300100	SHORT TERM PAVT MKING	FOOT	5,000.000				
70300150	SHRT TRM PAVT MK REM	SQ FT	1,667.000				
70300220	TEMP PVT MK LINE 4	FOOT	49,776.000				
70300250	TEMP PVT MK LINE 8	FOOT	335.000				
70300260	TEMP PVT MK LINE 12	FOOT	17.000				
70300280	TEMP PVT MK LINE 24	FOOT	146.000				
70400100	TEMP CONC BARRIER	FOOT	4,062.500				
70400200	REL TEMP CONC BARRIER	FOOT	3,525.000				
70600260	IMP ATTN TEMP FRN TL3	EACH	8.000				
70600332	IMP ATTN REL FRN TL3	EACH	9.000				
72000100	SIGN PANEL T1	SQ FT	291.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72000200	SIGN PANEL T2	SQ FT	114.000				
72400100	REMOV SIN PAN ASSY TA	EACH	22.000				
72400200	REMOV SIN PAN ASSY TB	EACH	19.000				
72501000	TERMINAL MARKER - DA	EACH	3.000				
73000100	WOOD SIN SUPPORT	FOOT	838.000				
78003100	PREF PL PM TB LTR-SYM	SQ FT	23.000				
78003130	PREF PL PM TB LINE 6	FOOT	306.000				
78003140	PREF PL PM TB LINE 8	FOOT	1,337.000				
78003180	PREF PL PM TB LINE 24	FOOT	120.000				
78008310	POLYUREA PM T2 LN 4	FOOT	24,574.000				
78008330	POLYUREA PM T2 LN 6	FOOT	1,734.000				
78008350	POLYUREA PM T2 LN 12	FOOT	1,418.000				
78100100	RAISED REFL PAVT MKR	EACH	171.000				
78100105	RAISED REF PVT MKR BR	EACH	30.000				
78200005	GRDRAIL REF TYPE A	EACH	48.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78200010	BARR WALL REF TYPE B	EACH	182.000				
78300200	RAISED REF PVT MK REM	EACH	88.000				
80400100	ELECT SERV INSTALL	EACH	2.000				
81028750	UNDRGRD C CNC 2	FOOT	1,088.000				
81028770	UNDRGRD C CNC 3	FOOT	262.000				
81200230	CON EMB STR 2 PVC	FOOT	2,020.000				
81300220	JUN BX SS AS 6X6X4	EACH	4.000				
81300530	JUN BX SS AS 12X10X6	EACH	3.000				
81300550	JUN BX SS AS 12X12X6	EACH	1.000				
81300610	JUN BX SS AS 14X12X6	EACH	2.000				
81603000	UD 2#8 #8G XLP USE 3/4	FOOT	2,585.000				
81603040	UD 2#6 #8G XLP USE 1	FOOT	4,122.000				
81702120	EC C XLP USE 1C 8	FOOT	11,010.000				
81702130	EC C XLP USE 1C 6	FOOT	2,440.000				
82200605	WATWY OBS WARN LM LED	EACH	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66992

State Job # - C-93-072-10

County Name - LASALLE - -

Code - 99 - -

District - 3 - -

Section Number - (1)BR&I

Project Number

ACRS-1279/114/

*REVISED: OCTOBER 21, 2016

Route

FAS 1279

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
82600105	NAV OBSTRUCT LT CONT	EACH	1.000				
83002200	LT P A 40MH 6DA	EACH	5.000				
83003600	LT P A 45MH 15DA	EACH	26.000				
83600300	LIGHT POLE FDN 30D	FOOT	169.000				
83800205	BKWY DEV TR B 15BC	EACH	12.000				
84200600	REM LT U NO SALV	EACH	2.000				
84200804	REM POLE FDN	EACH	2.000				
84301200	REM NAV OBS WL SYSTEM	L SUM	1.000				

CONTRACT NUMBER 66992

THIS IS THE TOTAL BID \$ _____

NOTES:

1. Each PAY ITEM should have a UNIT PRICE and a TOTAL PRICE.
2. The UNIT PRICE shall govern if no TOTAL PRICE is shown or if there is a discrepancy between the product of the UNIT PRICE multiplied by the QUANTITY.
3. If a UNIT PRICE is omitted, the TOTAL PRICE will be divided by the QUANTITY in order to establish a UNIT PRICE.
4. A bid may be declared UNACCEPTABLE if neither a unit price nor a total price is shown.

US ARMY CORPS OF ENGINEERS NATIONWIDE PERMIT #23 FOR APPROVED CATEGORICAL EXCLUSIONS

Effective March 19, 2012

The resident engineer shall complete the work completion form at the completion of the contract and submit to the address stated on the form.

Permit Expiration – March 18, 2017

For projects under contract, the US Army Corps of Engineers permit will be extended until March 18, 2018.

ARMY CORPS NOTIFICATION REQUIREMENTS

Prior to starting any in-stream work, the Contractor shall coordinate with the Engineer for notification to the Army Corps of Engineers 45 days prior to commencement. No in-stream work may begin until such notification has been done. The contact person for notification is Gene Wassenhove – phone number (309)794-5368. Any correspondence with the Army Corps shall refer to Permit No. CEMVR-OD-P -2015-152.

SPECIAL CONDITIONS

The Contractor shall comply with the Special Conditions provided in the permit issued on June 3, 2015. Attached as part of this special provision is a copy of the permit.

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY - BUREAU OF WATER

SPECIAL CONDITIONS

The Contractor shall comply with the special conditions provided in the Permit Number C-0033-15 issued on April 25, 2016. Attached as part of this special provision is a copy of the permit.

Revised 10/25/16

Crane mats shall be used as a temporary wetland protection measure. The area to be protected shall be adequately dewatered and prepared as shown on the plans and detailed in the applicable special provisions. Equipment used to lift and place the mats and the condition of the area shall be approved by the Engineer. If applicable, a manufacturer's representative shall be available for on premise oversight during initial installation for a length of time deemed necessary by the Engineer. Throughout the installation process the mats shall be installed in a manner so that they will maintain intimate contact with the prepared bedding. Placement of the mats on the side slopes shall begin at the toe and proceed up. Any additional manufacturer's specifications with regards to method of placement shall be adhered to. Surplus or waste material shall be disposed of according to Article 202.03 of the Standard Specifications for Road and Bridge Construction. Excess excavated material shall not remain in the flood plain, nor shall it be placed within the banks of the waterway.

Submittals. If the Contractor elects to use a temporary work bridge, structural plans and procedures shall be prepared and sealed by an Illinois Licensed Structural Engineer, and submitted to the Engineer for review and approval.

Basis of Payment. Temporary facilities installed by the Contractor and their subsequent removal shall not be measured nor paid for separately but shall be considered as included in the unit cost of the various related pay items in the contract.

TEMPORARY INLET

This work consists of providing temporary inlets during stage construction to promote pavement drainage where the existing inlets will be covered up. The inlets shall be connected to the temporary pipe drains, and design and method of connection will be subject to approval of the Engineer.

Basis of Payment. This work will be paid for at the contract unit price each for TEMPORARY INLET.

TEMPORARY PAVEMENT

Description: This item shall include all materials, labor, and equipment necessary to construct temporary pavement at the locations shown in the plans, or as directed by the Engineer.

Materials: The temporary pavement shall consist of 2" Hot-Mix Asphalt Surface Course, Mixture C N50, 6" Hot-Mix Asphalt Binder Course and 4" Aggregate Base Course Type A. The PCC option for temporary pavement shall be Portland Cement Concrete Base Course 8". The bituminous mix design shall be as shown in the plans. The temporary pavement shall be constructed in accordance with the applicable descriptions in Sections 406, Section 351 and Section 210 of the Standard Specifications and details in the plans.

Basis of Payment: This work shall be paid for at the contract unit price per square yard for TEMPORARY PAVEMENT, which price shall be payment in full for all materials, labor and equipment necessary to perform the work as specified herein.