

CODE NO.	PAY ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE
				URBAN 0020
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	135	135
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	400	400
20400800	FURNISHED EXCAVATION	CU YD	58,000	58,000
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	30,000	30,000
25000200	SEEDING, CLASS 2	ACRE	6.6	6.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	600	600
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	600	600
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	600	600
25100105	MULCH, METHOD 1	ACRE	6.6	6.6
44000100	PAVEMENT REMOVAL	SQ YD	12,530	12,530
44000300	CURB REMOVAL	FOOT	480	480
44000600	SIDEWALK REMOVAL	SQ FT	9,870	9,870
50102400	CONCRETE REMOVAL	CU YD	200	200
X0323099	RETAINING WALL REMOVAL	CU YD	15	15
Z0007126	HANDRAIL REMOVAL	FOOT	96	96
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	3	3
56500700	DOMESTIC WATER SERVICE BOXES TO BE REMOVED	EACH	2	2
60500040	REMOVING MANHOLES	EACH	2	2
60500050	REMOVING CATCH BASINS	EACH	4	4
● 66410300	CHAIN LINK FENCE REMOVAL	FOOT	3,350	3,350
● 66410800	CHAIN LINK GATES REMOVAL	EACH	2	2
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1
66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	3	3

● INDICATES SPECIALTY ITEMS

CODE NO.	PAY ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE
				URBAN 0020
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	29,550	29,550
66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	50,000	50,000
66900450	SPECIAL WASTE PLAN AND REPORT	L SUM	1	1
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2
67100100	MOBILIZATION	L SUM	1	1
67201100	SEALING ABANDONED MONITORING WELLS	EACH	29	29
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	1	1
● Z0019600	DUST CONTROL WATERING	UNIT	300	300
● Z0048900	RAILROAD TRACK REMOVAL	FOOT	130	130
● Z0075505	TIMBER RETAINING WALL REMOVAL	FOOT	293	293
● XX004878	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	L SUM	1	1
● XX007562	SIGN REMOVAL, SPECIAL	L SUM	1	1
● X0327081	WATER SERVICE LINE REMOVAL	FOOT	790	790
● X0301339	REMOVE EXISTING PARKING BLOCKS	EACH	6	6
● X0322329	TIMBER CURB REMOVAL	FOOT	190	190
● Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	550	550
● X0324056	REMOVAL OF EXISTING WOOD BOLLARDS	EACH	24	24
● X0840000	SANITARY SEWER REMOVAL, 8"	FOOT	340	340
● X7240300	SIGN REMOVAL	EACH	5	5
● X5510100	STORM SEWER REMOVAL	FOOT	400	400
● X0327070	REMOVE EXISTING FLAG POLE	EACH	1	1
● X0327071	REMOVE EXISTING STEEL DRUM	EACH	4	4

● INDICATES SPECIALTY ITEMS

FILE NAME =
...D160K02-ah-summary-01.dgn

USER NAME = ctb

DESIGNED - CTB

REVISED -

DRAWN - CTB

REVISED -

PLOT SCALE = 1:8000 / IN.

CHECKED - GAB

REVISED -

PLOT DATE = 5/12/2010

DATE -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2009-136 I	McHENRY	16	3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60K02	