

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134(B&B-2R-1)	LAKE	137	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62037				

LOCATION OF WORK: F.A.U. 303 IL ROUTE 173 OVER WEST AND EAST BOAT CHANNELS LAKE COUNTY

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				URBAN- 100% STATE			
				WEST BOAT CHANNEL		EAST BOAT CHANNEL	
				ROAD	BRIDGE	ROAD	BRIDGE
				0004	0014	0004	0014
MX207400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU M	305		75		230
*M2113100	TOPSOIL FURNISH AND PLACE, 100mm	SQ M	5,308	464		4,844	
*M2500210	SEEDING, CLASS 2A	HA	0.3	0.1		0.2	
*M2500310	SEEDING, CLASS 4	HA	0.4	0.1		0.3	
*M2500400	NITROGEN FERTILIZER NUTRIENT	KG	54	6		48	
*M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	54	6		48	
*M2510630	EROSION CONTROL BLANKET	SQ M	5,308	464		4,844	
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	2,101	183		1,918	
M2800305	TEMPORARY DITCH CHECKS	METER	96	2		94	
M2800400	PERIMETER EROSION BARRIER	METER	705	119		586	
M2810107	STONE RIPRAP, CLASS A4	SQ M	1,005			1,005	
M2820200	FILTER FABRIC	SQ M	1,065			1,065	
M3550500	HOT-MIX ASPHALT BASE COURSE, 200mm	SQ M	595			595	
M4030100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	6,260	440		5,820	
M4060300	AGGREGATE (PRIME COAT)	M TON	44	3		41	
M4060895	CONSTRUCTING TEST STRIP	EACH	2	1		1	
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	60	44		16	
M4061005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	M TON	71	6		65	
M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	10	10			
M4063085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	M TON	155			155	
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	75			75	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				URBAN- 100% STATE			
				WEST BOAT CHANNEL		EAST BOAT CHANNEL	
				ROAD	BRIDGE	ROAD	BRIDGE
				0004	0014	0004	0014
M4063595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	M TON	24	24			
M4075320	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 320mm	SQ M	2,910			2,910	
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	30	5		25	
M4206200	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ M	766	46		720	
M4400765	HOT-MIX ASPHALT SURFACE REMOVAL, 65mm	SQ M	451	451			
M4401250	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 150mm	SQ M	195	15		180	
M4402000	PAVEMENT REMOVAL	SQ M	1,902	136		1,766	
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	555			555	
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	195	27		168	
M4402060	APPROACH SLAB REMOVAL	SQ M	444	228		216	
M4402530	PAVED SHOULDER REMOVAL	SQ M	1,363	198		1,165	
M4428010	CLASS D PATCHES, TYPE I, 150mm	SQ M	60			60	
M4428210	CLASS D PATCHES, TYPE II, 150mm	SQ M	60			60	
M4428310	CLASS D PATCHES, TYPE III, 150mm	SQ M	75	15		60	
M4430080	REFLECTIVE CRACK CONTROL TREATMENT, SPECIAL 900mm	METER	48	48			
M5010240	CONCRETE REMOVAL	CU M	14		14		

* SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 IL ROUTE 173 OVER WEST AND EAST
 BOAT CHANNELS
SUMMARY OF QUANTITIES
 SCALE: NTS
 DRAWN BY CLG
 CHECKED BY JJD
 DATE 3-8-10

3116&17SHT3.DGN