

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134(B&B-2)R-1	LAKE	137	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62037				

WORK ZONE PAVEMENT MARKING REMOVAL

STA TO STA	SQ M
WEST	
STAGE 1	
25+012 TO 25+084 LT & RT	58
25+112 TO 25+185 LT 7 RT	58
STAGE 2	
25+000	2
25+012 TO 25+197 LT & RT	148
25+197	2
WEST SUBTOTAL	268
EAST	
STAGE 1	
26+400 TO 26+470 RT	28
26+400 TO 26+525 LT	50
STAGE 2	
26+210	2
26+210 TO 26+526 LT & RT	254
26+526	2
EAST SUBTOTAL	342
TOTAL	610

SHORT-TERM PAVEMENT MARKING

STA TO STA	METER
WEST	
25+012 TO 25+185 BINDER	346
25+012 TO 25+185 SURFACE	346
WEST SUBTOTAL	692
EAST	
26+096 TO 26+526 BINDER	860
26+096 TO 26+526 SURFACE	860
EAST SUBTOTAL	1,720
TOTAL	2,412

TEMPORARY CONCRETE BARRIER

STA TO STA	METER
WEST	
STAGE 1	
25+084 TO 25+114	30
WEST SUBTOTAL	30
EAST	
STAGE 1	
26+210 TO 26+470	260
EAST SUBTOTAL	260
TOTAL	290

RELOCATE TEMPORARY CONCRETE BARRIER

STA TO STA	METER
WEST	
25+084 TO 25+114	30
WEST SUBTOTAL	30
EAST	
26+210 TO 26+470	260
EAST SUBTOTAL	260
TOTAL	290

THERMOPLASTIC PAVEMENT MARKING- LINE 100mm

STA TO STA	METER
WEST	
WHITE	
25+012 TO 25+084 LT	72
25+012 TO 25+079 RT	67
25+112 TO 25+121 LT	9
25+112 TO 25+143 RT	31
WHITE SUBTOTAL	179
DOUBLE YELLOW	
25+012 TO 25+079	134
25+112 TO 25+123	22
25+145 TO 25+185	80
DOUBLE YELLOW SUBTOTAL	236
WEST SUBTOTAL	415
EAST	
WHITE	
26+096 TO 26+238 LT	142
26+096 TO 26+244 RT	148
26+298 TO 26+526 LT	228
26+307 TO 26+526 RT	219
WHITE SUBTOTAL	737
DOUBLE YELLOW	
26+096 TO 26+241	290
26+303 TO 26+526	446
DOUBLE YELLOW SUBTOTAL	736
EAST SUBTOTAL	1,473
TOTAL	1,888

POLYUREA PAVEMENT MARKING TYPE I- LINE 100mm

STA TO STA	METER
WEST	
WHITE	
25+084 TO 25+112 LT	28
25+088 TO 25+112 RT	28
WHITE SUBTOTAL	56
DOUBLE YELLOW	
25+087 TO 25+112	50
WEST SUBTOTAL	106
EAST	
WHITE	
26+238 TO 26+298 LT	60
26+244 TO 26+307 RT	63
WHITE SUBTOTAL	123
DOUBLE YELLOW	
26+241 TO 26+303	124
EAST SUBTOTAL	247
TOTAL	353

PAVEMENT MARKING REMOVAL

STA TO STA	SQ M
WEST	
25+000 TO 25+197	315
WEST SUBTOTAL	315
EAST	
26+210 TO 26+526	506
EAST SUBTOTAL	506
TOTAL	821

3116&17SCHEDULE.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 IL ROUTE 173 OVER WEST AND EAST
 BOAT CHANNELS
SCHEDULE OF QUANTITIES
 SCALE: NTS
 DRAWN BY CLG
 DATE 3-8-10
 CHECKED BY JJD

