

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134(B&B-2)R-1	LAKE	137	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62037				

TEMPORARY PAVEMENT

STA	SQ M
WEST	
CIRCLE DRIVE	75
25+103 TO 25+130 RT	135
WEST SUBTOTAL	210
TOTAL	210

**WET TEMPORARY PAVEMENT MARKING
TAPE, TYPE III, 600mm**

STA	METER
WEST	
25+000	4
25+197	4
WEST SUBTOTAL	8
EAST	
26+210	4
26+526	4
EAST SUBTOTAL	8
TOTAL	16

AGGREGATE SUBGRADE, 300mm

STA TO STA	SQ M
EAST	
26+096 TO 26+242	2,044
26+303 TO 26+400	1,358
EAST SUBTOTAL	3,402
TOTAL	3,402

**WET TEMPORARY PAVEMENT MARKING
TAPE, TYPE III 100mm**

STA TO STA	METER
WEST	
STAGE I	
25+012 TO 25+185 LT & RT	346
STAGE II	
25+102 TO 25+185 LT & RT	346
WEST SUBTOTAL	692
EAST	
STAGE I	
26+210 TO 25+526 LT & RT	632
STAGE II	
26+210 TO 25+526 LT & RT	632
EAST SUBTOTAL	1,264
TOTAL	1,956

FENCE REMOVAL

STA TO STA	METER
EAST	
26+320 TO 26+337	80
EAST SUBTOTAL	80
TOTAL	80

CORED DRAIN HOLES

STA TO STA	EACH
WEST	
25+105 LT	1
WEST SUBTOTAL	1
TOTAL	1

3116&17SCHEDULE.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 IL ROUTE 173 OVER WEST AND EAST
 BOAT CHANNELS
SCHEDULE OF QUANTITIES
 SCALE: NTS
 DRAWN BY CLG
 CHECKED BY JJD
 DATE 3-8-10

