

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134(B&B-2)R-1	LAKE	137	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 62037

STAGE I

EARTHWORK SCHEDULE						
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USE IN EMBANKMENT ADJUSTED FOR SHRINKAGE	FURNISHED EXCAVATION*	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU METER	CU METER	CUBIC METER	CUBIC METER	CUBIC METER	CUBIC METER
BRIDGE						
STA 26+294 TO STA 26+400	546	—	—	—	1150	-1150

STAGE II

EARTHWORK SCHEDULE						
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USE IN EMBANKMENT ADJUSTED FOR SHRINKAGE	FURNISHED EXCAVATION*	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU METER	CU METER	CUBIC METER	CUBIC METER	CUBIC METER	CUBIC METER
BRIDGE						
STA 26+294 TO STA 26+400	249	—	—	—	1373	-1373

STAGE III

EARTHWORK SCHEDULE						
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USE IN EMBANKMENT ADJUSTED FOR SHRINKAGE	FURNISHED EXCAVATION*	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU METER	CU METER	CUBIC METER	CUBIC METER	CUBIC METER	CUBIC METER
BRIDGE						
STA 26+096 TO STA 26+250	510	—	—	—	685	-685

* INCLUDES 15% SHRINK

311TEARTHWORKSCHED.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 IL ROUTE 173 OVER EAST BOAT CHANNEL
EARTHWORK SCHEDULE
 SCALE: NTS
 DRAWN BY CLG
 CHECKED BY JJD
 DATE 3-8-10

