

INDEX OF SHEETS

1	COVER SHEET
2-5	INDEX OF SHEETS & GENERAL NOTES
6	INDEX OF STANDARDS
7-9	SUMMARY OF QUANTITIES
10-14	TYPICAL SECTIONS
15-28	SCHEDULE OF QUANTITIES
29-35	ALIGNMENT, TIES, & BENCHMARKS
36-46	ROADWAY PLAN & PROFILE SHEETS
47	SUGGESTED STAGES OF CONSTRUCTION
48	TRAFFIC CONTROL PLAN
49-52	TRAFFIC DETOUR SHEETS
53-58	LANDSCAPING SHEETS
59	PERMANENT & TEMPORARY EROSION CONTROL NOTES & STAGING
60-65	PERMANENT & TEMPORARY EROSION CONTROL SHEETS
66	DRAINAGE SCHEDULES AND LEGEND
67-77	DRAINAGE PLAN & PROFILE SHEETS
78-79	STREET LIGHTING SHEETS
80-81	STREET LIGHTING SINGLE LINE DIAGRAM SHEETS
82-89	RIGHT-OF-WAY SHEETS
90-92	ROUNDBOUT DETAIL SHEETS
93-94	ROUNDBOUT ELEVATION SHEETS
95-100	PERMANENT PAVEMENT MARKING SHEETS
101-103	CONSTRUCTION DETAILS
104-113	LCDOT HIGHWAY STANDARDS
114-119	IDOT DISTRICT ONE STANDARDS
120-177	CROSS SECTIONS IDOT HIGHWAY STANDARDS

GENERAL NOTES

1. ALL CONSTRUCTION SHALL BE DONE ACCORDING TO THE STATE OF ILLINOIS "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JAN. 1, 2007, THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" ADOPTED JANUARY 1, 2010, THE DETAILS IN THESE PLANS, AND THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS.
2. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE THE MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTIL THE OWNER, AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
3. THE CONTRACTOR SHALL NOTIFY THE AGENCIES AND UTILITIES AT LEAST 10 DAYS PRIOR TO ANY CONSTRUCTION IN THE AREA AND SHALL COMPLY WITH ALL RESTRICTIONS FOR EQUIPMENT MOVEMENTS AND CLEARANCES IN REGARDS TO THEIR FACILITIES.
4. DISTRIBUTORS: ALL DISTRIBUTORS FOR HOT-MIX ASPHALT PAVING OPERATIONS SHALL BE EQUIPPED WITH SHIELDS TO PREVENT DAMAGES TO MOTORIST'S VEHICLES AND TO ADJACENT HIGHWAY APPURTENANCES.
5. ANY RIGHT-OF-WAY MARKERS DISTURBED BY THE CONTRACTOR'S OPERATION THAT ARE NOT SCHEDULED FOR REMOVAL SHOULD BE REESTABLISHED BY A REGISTERED LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE.
6. THE SCALE SHOWN ON THE DRAWINGS APPLIES ONLY TO FULL SIZE PLANS AND NOT TO THE REDUCED SIZE PLANS.
7. ALL ELEVATIONS SHOWN ON THESE PLANS ARE ON UNITED STATES COAST AND GEODETIC SURVEY DATUM. BENCHMARKS FOR THE PROJECT ARE DESCRIBED IN THE PLANS.
8. POLLUTION CONTROL: THE CONTRACTOR WILL BE REQUIRED TO COMPLY WITH ALL STATE REGULATIONS REGARDING AIR, WATER AND NOISE POLLUTION. THE CONTRACTOR WILL NOT BE ALLOWED TO BUILD FIRES ON THE SITE.
9. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP AN OFFICE OR YARD ON THE COUNTY PROPERTY WITHOUT WRITTEN APPROVAL FROM THE COUNTY.
10. VERIFICATIONS OF DIMENSIONS: IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
11. THE CONTRACTOR IS ADVISED THAT IN THE EVENT OF SNOW, THE CONTRACTOR WILL BE RESPONSIBLE FOR THE IMMEDIATE REMOVAL OF ANY MAINTENANCE OF TRAFFIC PROTECTIVE DEVICES REQUIRED FOR THEIR OPERATIONS THAT WOULD INTERFERE WITH SNOW REMOVAL OPERATIONS PERFORMED BY THE APPROPRIATE AGENCY. THE CONTRACTOR WILL ALSO BE RESPONSIBLE FOR RESTORING THE MAINTENANCE OF TRAFFIC DEVICES AFTER THE COMPLETION OF SNOW REMOVAL OPERATION.
12. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING HIS CONSTRUCTION OPERATIONS WITH THE CONSTRUCTION AND MAINTENANCE OPERATIONS, INCLUDING UTILITY RELOCATIONS AND ADJUSTMENTS OF OTHER CONTRACTORS WORKING WITHIN THE LIMITS OF THE PROJECT AND ADJACENT TO THE PROJECT.
13. THE CONTRACTOR SHALL USE ALL NECESSARY PRECAUTIONS AND PROTECTIVE MEASURES REQUIRED TO MAINTAIN EXISTING UTILITIES, SEWERS AND APPURTENANCES THAT MUST BE KEPT IN OPERATION, IN PARTICULAR, THE CONTRACTOR WILL TAKE ADEQUATE MEASURES TO PREVENT THE UNDERMINING OF UTILITIES AND SEWERS WHICH ARE STILL IN SERVICE.
14. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR JOB SITE SAFETY AS WELL AS SUPERVISION, DIRECTION AND MEANS/METHOD OF CONSTRUCTION.
15. PROPOSED PERMANENT SIGNING WILL BE INSTALLED BY LCDOT AND IS NOT PART OF THIS CONTRACT.
16. ALL REMOVAL ITEMS FOR THE PROJECT ARE SHOWN ON THE ROADWAY PLAN AND PROFILE SHEETS WITH THE EXCEPTION OF THE FOLLOWING; DRAINAGE REMOVAL ITEMS ARE SHOWN IN THE DRAINAGE PLAN AND PROFILE SHEETS (I.E. PIPE CULVERT REMOVAL, ETC). TREE REMOVAL IS SHOWN IN THE LANDSCAPING PLAN SHEETS.
17. SLOPES SHOWN THROUGHOUT THE PLANS ARE GIVEN BY THE VERTICAL RISE TO HORIZONTAL RUN DIMENSION RATIO (I.E. 1V:1H)
18. SURFACE TESTS
 - A. THE COMPLETED SURFACE COURSE WILL BE TESTED FOR SMOOTHNESS IN THE WHEEL PATH WITH A 16 FT. STRAIGHTEDGE ACCORDING TO ARTICLE 406.11 OF THE STANDARD SPECIFICATIONS.
 - B. THE CONTRACTOR SHALL FURNISH THE APPROPRIATE PERSONNEL AND EQUIPMENT REQUIRED TO PERFORM THE SURFACE COURSE TESTING ACCORDING TO ARTICLE 406.11 OF THE STANDARD SPECIFICATIONS, AND TO THE SATISFACTION OF THE ENGINEER. TRAFFIC CONTROL AND PROTECTION FOR THE TESTING SHALL BE INCLUDED. THE TESTING, INCLUDING ALL REQUIRED PERSONNEL AND EQUIPMENT, WILL BE CONSIDERED INCLUDED IN THE COST OF THE HMA SURFACE COURSE.
 - C. AT THE ENGINEER'S DISCRETION THE SURFACE TESTING MAY INCLUDE SECTIONS OF THE HIGHWAY REPAIRED WITH PARTIAL DEPTH OR FULL DEPTH PAVEMENT PATCHING AND/OR AREAS OF PAVEMENT REPLACEMENT.

INDICATES NOTE CONTAINS PAY ITEM INFORMATION

FILE NAME = SA\JOL\1988--1999\1982\002\Micro\Plan_Sheets\DLT-mlt-notes-general.dgn



USER NAME = amenda.j	DESIGNED -	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 4/1/2010	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

INDEX OF SHEETS AND GENERAL NOTES			
SCALE: AS SHOWN	SHEET NO.	OF SHEETS	STA. N/A TO STA. N/A

F.A.U. RTE. 2661	SECTION 02-00076-13-CH	COUNTY LAKE	TOTAL SHEETS 177	SHEET NO. 2
CONTRACT NO. 63457				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				