

FILE NAME = s:\p1\1980-1999\1982\002\mccross\plan\_sheets\DI-sht-800.dgn

S.P.	SPECIALTY ITEM	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	LIGHTING Y030-1E
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,330	1,330	
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	767	767	
		20101100	TREE TRUNK PROTECTION	EACH	15	15	
	++	20101200	TREE ROOT PRUNING	EACH	13	13	
	++	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1	1	
	++	20101700	SUPPLEMENTAL WATERING	UNIT	49	49	
		20200100	EARTH EXCAVATION	CU YD	3,210	3,210	
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6,440	6,440	
		20400800	FURNISHED EXCAVATION	CU YD	12,445	12,445	
*		20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	681	681	
*		20800250	TRENCH BACKFILL, SPECIAL	CU YD	418	418	
		20900110	POROUS GRANULAR BACKFILL	CU YD	61	61	
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	21,884	21,884	
	++	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	32,964	32,964	
*	++	25000115	SEEDING, CLASS 1B	ACRE	5.50	5.50	
*	++	25000210	SEEDING, CLASS 2A	ACRE	1.00	1.00	
*	++	25000312	SEEDING, CLASS 4A	ACRE	0.50	0.50	
	++	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	607	607	
	++	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	607	607	
	++	25100630	EROSION CONTROL BLANKET	SQ YD	32,964	32,964	
*	++	25400105	PERENNIAL PLANTS	EACH	1,070	1,070	
	++	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	674	674	
*		28000305	TEMPORARY DITCH CHECKS	FOOT	2,016	2,016	
*		28000400	PERIMETER EROSION BARRIER	FOOT	9,728	9,728	
		28000510	INLET FILTERS	EACH	37	37	

S.P.	SPECIALTY ITEM	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	LIGHTING Y030-1E
		28100101	STONE RIPRAP, CLASS A1	SQ YD	176	176	
		28100105	STONE RIPRAP, CLASS A3	SQ YD	541	541	
		28100107	STONE RIPRAP, CLASS A4	SQ YD	176	176	
*		28200200	FILTER FABRIC	SQ YD	176	176	
*		28400105	GABION REMOVAL	CU YD	1	1	
		35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	2,538	2,538	
		35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	289	289	
*		40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	253	253	
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15,245	15,245	
*		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	155	155	
		40600895	CONSTRUCTING TEST STRIP	EACH	4	4	
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	385	385	
*		40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7,524	7,524	
*		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	33	33	
*		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70	TON	1,733	1,733	
		42001300	PROTECTIVE COAT	SQ YD	22,404	22,404	
*		42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	24	24	
*		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5,069	5,069	
		42400800	DETECTABLE WARNINGS	SQ FT	560	560	
		44000100	PAVEMENT REMOVAL	SQ YD	11,737	11,737	
		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3,517	3,517	
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	368	368	
*		44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	18	18	
*		44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	27	27	
*		44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	80	80	
*		44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	53	53	



1170 SOUTH HOBOLT ROAD  
JOLIET, ILLINOIS 60431  
(815) 744-4200

USER NAME = saron	DESIGNED -	REVISED -
PLOT SCALE = 28.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 4/1/2012	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO. OF	SHEETS	STA. TO STA.

F.A. RTE. 2661	SECTION 02-00076-13-CH	COUNTY LAKE	TOTAL SHEETS 177	SHEET NO. 7
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 63457	