


1		SCHEDULE OF TREE MAINTENANCE & REMOVAL				
STATION	OFFSET	TREE REMOVAL (6 TO 15 UNITS DIAMETER) (UNIT) 20100110	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT) 20100210	TREE TRUNK PROTECTION (EACH) 20101100	TREE ROOT PRUNING (EACH) 20101200	TREE PRUNING (OVER 10 INCH DIAMETER) (EACH) 20101350
103+60	34.7 RT	8				
103+61	34.7 RT	8				
103+62	34.7 RT	8				
103+63	34.7 RT	8				
103+64	34.7 RT	8				
103+65	34.7 RT	8				
103+70	37.9 RT	9				
103+71	37.9 RT	9				
103+72	37.9 RT	9				
103+73	37.9 RT	9				
103+74	37.9 RT	9				
103+75	37.9 RT	9				
103+76	37.9 RT	9				
103+77	37.9 RT	9				
103+78	37.9 RT	9				
103+84	40.0 RT		21			
103+93	40.6 RT	12				
105+54	32.7 RT	8				
105+43	31.0 RT	14				
105+54	31.2 RT	6				
111+46	31.1 RT		28			
113+65	28.0 RT	12				
113+84	30.0 RT	15				
79+78	37.4 LT			1	1	
79+89	39.1 LT			1	1	
81+37	50.9 LT			1	1	
81+65	55.7 LT			1	1	
82+05	42.4 LT	10				
82+49	44.7 LT	12				
82+54	54.2 LT	12				
82+54	54.2 LT	12				
82+54	54.2 LT	12				
83+02	41.5 LT		30			
83+35	35.0 LT	10				
83+57	46.4 LT		36			
83+71	59.2 LT		36			
84+45	35.8 LT		60			
84+67	86.9 LT			1	1	
85+19	81.0 LT		50			
87+65	45.4 LT		16			
87+94	55.1 LT	8				
88+05	51.9 LT		16			
88+29	41.5 LT	8				
88+43	55.2 LT	8				
88+41	45.2 LT	8				
88+92	44.0 LT			1	1	
89+44	39.5 LT	6				
97+65	24.0 LT		24			
98+20	26.2 LT		30			
98+85	22.0 LT		30			
SUBTOTAL						
MILLBURN ROAD						
6+37	46.8 RT					1
6+60	37.3 RT			1	1	
8+36	50.1 RT		50			
8+94	54.9 RT		24			
10+52	25.6 RT	8				
10+52	25.6 RT		18			
10+71	30.4 RT	7				
10+83	27.1 RT	10				
10+83	27.1 RT	10				
10+83	27.1 RT	10				
11+05	20.2 RT	8				
11+06	14.4 RT	10				
11+25	21.2 RT	12				
11+77	21.5 RT		44			
SUBTOTAL		377	513	7	7	1

1		SCHEDULE OF TREE MAINTENANCE & REMOVAL				
STATION	OFFSET	TREE REMOVAL (6 TO 15 UNITS DIAMETER) (UNIT) 20100110	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT) 20100210	TREE TRUNK PROTECTION (EACH) 20101100	TREE ROOT PRUNING (EACH) 20101200	TREE PRUNING (OVER 10 INCH DIAMETER) (EACH) 20101350
11+84	18.6 RT	12				
1187	30.0 RT				1	
12+13	24.6 RT	12				
12+13	24.6 RT	12				
12+13	24.6 RT	12				
4+30	38.5 LT			1	1	
6+03	45.4 LT	7				
6+21	45.5 LT	8				
6+46	49.7 LT		16			
6+56	48.8 LT			1	1	
6+58	48.0 LT			1	1	
6+76	51.0 LT	10				
6+92	49.4 LT			1	1	
7+04	47.1 LT	12				
7+04	47.1 LT	12				
7+43	52.4 LT	7				
7+88	56.2 LT	10				
7+84	65.7 LT			1	1	
8+31	57.9 LT	15				
8+42	41.3 LT	7				
8+57	56.9 LT	10				
8+57	56.9 LT	10				
8+57	56.9 LT	10				
8+57	56.9 LT	10				
8+66	71.7 LT		20			
8+73	87.0 LT	8				
8+73	87.0 LT	8				
8+73	87.0 LT	8				
8+75	75.4 LT	15				
8+75	75.4 LT	15				
8+75	75.4 LT	15				
8+75	75.4 LT	15				
8+86	86.9 LT	11				
8+98	85.4 LT	8				
9+00	78.9 LT	10				
9+12	100.7 LT	6				
9+17	49.6 LT	12				
9+17	49.6 LT	12				
9+17	49.6 LT	12				
9+19	96.7 LT	6				
9+35	68.6 LT	7				
9+40	99.6 LT	8				
9+47	96.9 LT	6				
10+86	16.4 LT	12				
10+86	16.4 LT	12				
10+93	14.1 LT		18			
11+19	13.2 LT	10				
11+22	13.6 LT	12				
11+39	16.4 LT		29			
11+68	12.8 LT	12				
11+76	13.5 LT		20			
12+24	16.4 LT		18			
WADSWORTH ROAD						
15+22	34.7 LT	18				
SUBTOTAL		454	121	5	6	0
TOTAL		1330	767	15	13	1

FILE NAME = s:\p1\1980--1995\1982\002\microna\Plan_Sheets\DI-int-schedule.dgn



USER NAME = searsh	DESIGNED -	REVISED -
PLOT SCALE = 28,0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 4/1/2010	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2661	02-00076-13-CH	LAKE	177	16
CONTRACT NO. 63457				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				