


6 SCHEDULE OF STONE RIPRAP								
FROM STATION	TO STATION	OFFSET	WIDTH (FT)	LENGTH (FT)	STONE RIPRAP, CLASS A1 (SQ YD)	STONE RIPRAP, CLASS A3 (SQ YD)	STONE RIPRAP, CLASS A4 (SQ YD)	FILTER FABRIC (SQ YD)
<b>HUNT CLUB ROAD</b>								
82+53.6	82+69.0	RT	13.00	15.25			23.9	
84+12.8	84+27.8	LT	15.00	15.25			27.6	
85+16.5	85+30.6	LT	11.00	15.25			20.3	
87+00.9	87+50.0	LT	26.00	50.00			157.3	
86+76.7	87+23.4	RT	VARIES	50.00	87.9		87.9	87.9
88+45.9	88+60.9	LT	14.00	15.25		24.5		
102+64.6	102+86.6	LT	13.50	22.08	35.9		35.9	35.9
105+13.7	105+31.7	LT	11.00	18.17		24.2		
109+44.3	-	RT	2.00	5.00		1.2		
110+09.1	110+24.1	RT	11.00	15.25		20.3		
110+81.9	110+97.1	LT	11.00	15.25		20.3		
113+48.0	113+62.1	LT	12.00	15.25		22.1		
115+49.0	115+64.4	LT	6.00	15.33		11.0		
116+75.6	116+93.5	RT	7.00	22.00		18.4		
117+47.0	-	LT	VARIES	11.00		19.8		
<b>MILLBURN ROAD</b>								
7+59.2	7+75.0	RT	9.00	18.17		19.6		
8+70.4	8+85.4	RT	5.00	15.25		9.1		
8+98.3	9+25.0	LT	14.00	28.00		47.3		
11+31.3	11+46.5	LT	13.00	15.25		23.9		
12+20.0	12+52.0	RT	15.00	28.00	51.3		51.3	51.3
<b>WADSWORTH ROAD</b>								
11+50.2	11+66.2	RT	7.00	22.00		18.4		
12+70.3	12+85.6	LT	9.00	15.25		16.5		
13+45.4	13+63.6	LT	7.00	18.17		15.2		
<b>TOTAL</b>					<b>175.1</b>	<b>540.9</b>	<b>175.1</b>	<b>175.1</b>

STATIONING SHOWN FOR RIPRAP IS FROM THE CENTER OF THE DITCH.

7 SCHEDULE OF GABION REMOVAL				
STATION	OFFSET	AREA (SF)	ESTIMATED DEPTH (FT)	GABION REMOVAL (CU YD)
<b>HUNT CLUB ROAD</b>				
86+67.4	28.2	RT	7.30	1.50
<b>TOTAL</b>				<b>0.4</b>

8 SCHEDULE OF AGGREGATE BASE						
FROM STATION	TO STATION	OFFSET	LENGTH (FT)	AVERAGE WIDTH (FT)	AGGREGATE BASE COURSE, TYPE A 4" (SQ YD)	AGGREGATE BASE COURSE, TYPE A 6" (SQ YD)
<b>HUNT CLUB ROAD</b>						
83+48.0	83+75.2	RT	27.2	-	15.4	
83+62.6	83+71.6	LT	9.0	-	4.4	
84+32.2	84+41.7	LT	9.5	-	3.4	
84+77.5	85+00.0	RT	22.5	-	17.4	
84+78.8	85+00.9	LT	22.1	-	17.4	
84+89.3	84+99.5	RT/LT	10.2	-	35.7	
85+00.0	85+15.1	RT/LT	15.1	-	67.2	
86+84.8	87+00.1	RT/LT	15.3	-	68.9	
86+99.9	87+22.1	RT	22.2	-	17.4	
87+00.0	87+22.5	LT	22.5	-	17.4	
87+00.7	87+10.8	RT/LT	10.1	-	35.9	
87+58.5	87+67.8	RT	9.3	-	3.4	
88+17.7	88+59.4	RT	41.7	-	20.7	
89+28.4	89+37.4	RT/LT	9.0	-	4.4	
92+35.2	106+74.0	RT	1438.8	5.0	799.3	
92+35.2	106+74.0	LT	1438.8	5.0	799.3	
102+51.3	103+21.3	LT	70.0	-		48.9
105+32.1	105+56.1	LT	24.0	-		49.6
109+02.2	109+11.2	LT	9.0	-	4.4	
110+08.9	110+43.4	RT	34.5	-	19.5	
110+97.5	111+06.7	LT	9.2	-	3.3	
111+33.9	111+56.5	RT	22.6	-	17.5	
111+34.3	111+56.0	LT	21.7	-	17.0	
111+46.7	111+56.7	RT/LT	10.0	-	20.0	
111+57.3	111+71.9	RT/LT	14.6	-	41.6	
112+48.2	112+78.1	LT	29.9	-	57.9	
113+22.1	113+36.6	RT/LT	14.5	-	41.1	
113+37.1	113+47.1	RT/LT	10.0	-	19.8	
113+38.6	113+59.9	LT	21.3	-	16.6	
113+37.5	113+59.2	RT	21.7	-	6.3	
113+83.4	113+93.1	RT	9.7	-	3.3	
114+76.4	115+01.3	LT	24.9	-	16.4	
115+79.2	115+88.2	RT	9.0	-	4.4	
116+46.6	116+72.6	RT	26.0	-		41.7
<b>MILLBURN ROAD</b>						
6+49.7	6+58.7	LT	9.0	-	4.4	
6+85.3	7+57.8	RT	72.5	-		49.5
7+57.8	7+75.0	RT	17.2	-	9.4	
8+43.9	8+53.2	LT	9.3	-	3.3	
8+77.5	9+00.0	RT	22.5	-	17.4	
8+79.1	9+01.2	LT	22.1	-	17.0	
8+89.4	8+99.5	RT/LT	10.1	-	36.7	
9+00.2	9+14.9	RT/LT	14.7	-	71.1	
10+85.5	10+92.4	RT/LT	6.9	-	10.7	
10+85.9	11+06.0	RT	20.1	-	12.4	
10+85.9	11+06.0	LT	20.1	-	12.4	
10+93.0	11+03.0	RT/LT	10.0	-	14.8	
11+03.50	11+14.60	RT/LT	11.1	-	7.6	
11+96.7	12+25.0	RT	28.3	-		33.7
<b>WADSWORTH ROAD</b>						
10+75.20	10+90.1	RT/LT	14.9	-	39.6	
10+90.6	11+12.9	LT	22.3	-	7.9	
10+90.7	11+00.7	RT/LT	10.0	-	18.5	
10+91.1	11+12.9	RT	21.8	-	16.9	
11+33.3	11+44.0	RT	10.7	-	4.1	
12+38.9	12+63.9	LT	25.0	-	12.5	
12+68.3	12+77.3	RT	9.0	-	4.4	
13+16.4	13+47.7	LT	31.3	-		65.6
<b>TOTAL</b>					<b>2,537.8</b>	<b>288.9</b>

FILE NAME = s:\p\1900-1995\1902\002\micos\Plan Sheets\01-int-schedule.dgn



USER NAME = soren	DESIGNED -	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 4/1/2219	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2661	02-00076-13-CH	LAKE	177	20
CONTRACT NO. 63457				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				