

HMA DRIVEWAY REMOVAL/REPLACEMENT SCHEDULE		
STATION	(SY) DRIVEWAY REMOVAL	(SY) DRIVEWAY REPLACEMENT
A. HAWTHORNE		
101+57 - 101+80 LT	22.3	3.3
102+08 - 102+36 LT	27.8	3.7
105+98 - 106+23 LT	16.5	6.2
112+00 - 112+14 LT	14.0	5.4
129+03 - 129+14 LT	13.0	4.9
131+89 - 132+13 LT	16.0	
135+92 - 136+11 LT	38.3	27.3
136+94 - 137+12 LT	34.2	23.7
A TOTAL (HAWTHORNE)	182.1	74.5
C. HOOK		
723+44 - 723+64 LT	18.4	7.0
C TOTAL (HOOK)	18.4	7.0
MISCELLANEOUS	179.5	48.5
A+C+MISC. TOTAL	380.0	130.0

ORNAMENTAL FENCE (THREE RAIL) SCHEDULE	
STATION	(FT) LENGTH
C. HOOK DRIVE	
738+54 - 739+99 LT	177
C TOTAL (HOOK)	177

CHAIN LINK FENCE, 4' SCHEDULE	
STATION	(FT) LENGTH
C. HOOK DRIVE	
733+34 - 734+34 LT	100
735+49 - 736+94 LT	107
C TOTAL (HOOK)	207

PCC DRIVEWAY REMOVAL/REPLACEMENT SCHEDULE		
STATION	(SY) REMOVAL	(SY) REPLACEMENT
A. HAWTHORNE		
104+88 - 105+02 LT	35.1	35.1
111+15 - 111+32 LT	19.6	19.6
131+89 - 132+13 LT	16.4	32.6
133+66 - 133+87 LT	53.7	53.7
TOTAL A (HAWTHORNE)	124.8	141.0
MISCELLANEOUS		4
A+MISC. TOTAL	124.8	145.0

CURB REMOVAL/REPLACEMENT SCHEDULE		
STATION	(FT) CURB REMOVAL	(FT) COM CONC C&G TY B-6.12
A. HAWTHORNE		
100+33 - 100+43 RT	10	10
100+66 - 100+70 LT	10	10
TOTAL A (HAWTHORNE)	20	20
C. HOOK		
717+59 - 717+64 LT	10	10
717+92 - 717+98 LT	10	10
722+70 - 722+75 LT	10	10
722+97 - 723+02 LT	10	10
726+45 - 726+50 LT	10	10
726+80 - 726+85 LT	10	10
732+16 - 732+24 LT	12	12
732+16 - 732+26 RT	10	10
732+80 - 732+85 LT	10	10
734+90 - 734+94 RT	10	10
735+25 - 735+30 RT	10	10
737+75 - 737+79 LT	10	10
737+96 - 738+02 LT	10	10
738+24 - 738+30 LT	12	12
738+48 - 738+54 LT	12	12
739+66 - 739+76 RT	10	10
739+88 - 739+98 LT	10	10
740+17 - 740+22 LT	10	10
740+67 - 740+71 LT	10	10
TOTAL C (HOOK)	196	196
MISCELLANEOUS	64	28
A+C+MISC. TOTAL	260	244

CURB SCHEDULE	
STATION	(FT) COM CONC C&G TY B-6.12
A. HAWTHORNE	
101+52 - 102+52 LT	100
103+97 - 105+38 LT	141
123+71 - 124+76 LT	115
TOTAL A (HAWTHORNE)	356

OUTLET (CLASS SI CONCRETE) SCHEDULE	
STATION	(CY) OUTLET
A. HAWTHORNE	
105+36 LT	1
124+84 LT	1
TOTAL A (HAWTHORNE)	2

FENCE REMOVAL SCHEDULE	
STATION	(FT) FENCE REMOVAL
A. HAWTHORNE	
102+39 - 103+30 LT	95
110+40 - 110+66 LT	30
TOTAL A (HAWTHORNE)	125

HEDGE REMOVAL SCHEDULE	
STATION	(UNIT) HEDGE REMOVAL
A. OAKWOOD	
102+37 - 103+37 LT	10.0
110+45 - 111+00 LT	5.5
111+05 - 111+12 LT	0.7
111+35 - 111+55 LT	2.0
123+40 - 123+65 LT	2.5
124+60 - 126+15 LT	5.5
TOTAL A (HAWTHORNE)	26.2
C. HOOK	
704+90 - 706+00 LT	11.0
707+80 - 712+50 LT	47.0
737+50 - 737+75 LT	1.0
738+55 - 738+90 LT	1.0
739+93 - 739+98 LT	1.0
TOTAL C (HOOK)	61.0
TOTAL A + C	87.2

* 1 UNIT = 10 FEET

SEGMENTAL CONCRETE BLOCK WALL SCHEDULE	
STATION	(SF) AREA
A. HAWTHORNE	
134+80 - 135+92 LT	250
A TOTAL	250
C. HOOK	
736+39 - 736+78 LT	225
738+54 - 739+99 LT	415
C TOTAL	640
MISCELLANEOUS	10
A+C+MISC. TOTAL	900

FILE NAME = 10258902.DWG	USER NAME =	DESIGNED -- RJD	REVISED --
	FILE NAME =	DRAWN -- EC	REVISED --
	PLOT SCALE =	CHECKED -- RJD	REVISED --
	PLOT DATE =	DATE -- 10/02/09	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 5 OF 75 SHEETS

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	10-00073-00-SW	LAKE	75	5
CONTRACT NO. 63467			ILLINOIS FED. AID PROJECT	