

EARTHWORK SCHEDULE						
STATION	20200100		20201200		EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL			
LINE "DUNHAM"	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
500+00 TO 504+50	2	2	7	3	-2	
504+50 TO 505+00	55	46	40	16	30	
505+00 TO 505+50	130	110	70	49	61	
505+50 TO 506+00	196	167	80	111	55	
506+00 TO 506+50	239	203	92	179	24	
506+50 TO 507+00	251	213	98	239	-26	
507+00 TO 507+50	274	233	99	298	-65	
507+50 TO 508+00	271	231	102	383	-152	
508+00 TO 508+50	715	608	263	1,048	-440	
508+50 TO 509+00	272	231	115	552	-321	
509+00 TO 509+50	248	211	93	424	-213	
509+50 TO 510+00	110	94	35	130	-37	
510+00 TO 510+50	6	5	17	66	-60	
510+50 TO 511+00	19	16	50	265	-249	
511+00 TO 511+50	15	13	55	259	-247	
511+50 TO 512+00	7	6	49	185	-180	
512+00 TO 512+50	4	4	26	115	-112	
512+50 TO 513+00	16	13	23	60	-46	
513+00 TO 513+10	7	6	6	4	2	
TOTALS	2,835	2,410	1,313	4,385	-1,975	

EARTHWORK SCHEDULE			
LOCATION FROM CENTERLINE			20300100
			CHANNEL EXCAVATION
			(CU YD)
60.0' RT TO 40.8' RT			51
40.8' RT TO 21.7' RT			92
21.7' RT TO 13.3' RT			45
13.3' RT TO 13.5' LT			184
13.5' LT TO 21.7' LT			57
21.7' LT TO 49.4' LT			309
49.4' LT TO 77.2' LT			244
TOTALS			982

SUMMARY			
20200100	20400800	20201201	20201201
EARTH EXCAVATION	FURNISHED EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CHANNEL EXCAVATION
(CU YD)	(CU YD)	(CU YD)	(CU YD)
2,835	1,975	1,313	982

FILE NAME = c:\p\proj\3381\01_kish\design\proposals\3381_01_04_eor.dwg



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = espina	DESIGNED - CLG	REVISED - 8/02/2010
	DRAWN - EPS	REVISED -
PLOT SCALE = 1,0000' / IN.	CHECKED - MJL	REVISED -
PLOT DATE = 8/30/2010	DATE - 6/18/2010	REVISED -

MCHENRY COUNTY DIVISION OF TRANSPORTATION

EARTHWORK SCHEDULES

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1233	06-00321-00-BR	McHENRY	48	5
CONTRACT NO. 63516				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				