

EARTHWORK SCHEDULE			
20200100 EARTH EXCAVATION [CUT]	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT [FILL]	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
(CU YD)	(CU YD)	(CU YD)	(CU YD)
303	227.3	306	-78.8
303	227.3	306	-78.8
20400800 FURNISHED EXCAVATION (CU YD)			79

ENTRANCE SCHEDULE					
STA	LT / RT	WIDTH	APRON LENGTH	ENTRANCE LENGTH	35102000 AGG BASE CSE B 8
		(FEET)	(FEET)	(FEET)	(SQ YD)
404+50	LT	24	12.00	60.50	177
TOTALS					177

PAVEMENT REMOVAL SCHEDULE						
STA	TO	STA	LT / RT	AVG PAVEMENT WIDTH	AREA (CALC'D. IN CADD)	44000100 PAVEMENT REM
				(FOOT)	(SQ FT)	(SQ YD)
397+90.00		398+65.84		22	1,668	186
401+30.40		402+10.00		22	1,751	195
402+88.00		403+50.00	LT	1.34	83	10
TOTAL						391

EROSION CONTROL SCHEDULE						
STATION	TO	STATION	OFFSET	LT / RT	28000400 PERIMETER EROS BAR	28000500 INLET & PIPE PROTECT
					(FOOT)	(EACH)
395+88		398+67		RT	330	
401+20		402+94		RT	188	
397+59		398+84		LT	165	
401+40		402+70		LT	206	
402+96			32.0	RT		1
404+19			32.0	LT		1
TOTAL					889	2

FLEXIBLE CONNECTOR SCHEDULE					
STA	TO	STA	WIDTH	LENGTH	42001430 BR APPR PVT CON (FLX)
			(FEET)	(FEET)	(SQ YD)
397+90.00		398+35.84	32	45.84	163
401+60.40		402+10.00	32	49.60	177
TOTALS					340

DRAINAGE SCHEDULE							
STATION	RT / LT	542D0220 P CUL CL D 1 15	54213447 END SECTIONS 12	54213450 END SECTIONS 15	60100945 PIPE DRAINS 12	60900240 TY C INLET BOX 609006	60900515 CONC THRUST BLOCKS
		(FOOT)	(EACH)	(EACH)	(FOOT)	(EACH)	(EACH)
398+32	RT		1		66	1	1
398+62	LT		1		26	1	1
401+34	RT		1		18	1	
401+64	LT		1		66	1	1
404+50	LT	56		2			
TOTALS		56	4	2	176	4	3

TEMP EROSION SEEDING SCHEDULE							
STA	TO	STA	LT / RT	AREA (CALC'D. IN CADD) SF = SLOPE FACTOR			28000250 TEMP EROS CONTR SEED (8 APPS)
				(SQ FT)	(SF)	(ACRE)	(POUND)
395+88		396+50	RT	849	1.031	0.02	16
396+50		398+50	RT	3,368	1.054	0.08	64
396+92		397+50	LT	366	1.031	0.01	8
397+50		398+75	LT	903	1.054	0.02	16
401+20		401+60	RT	497	1.054	0.01	8
401+60		402+99	RT	1,087	1.031	0.03	24
401+41		402+10	LT	2,290	1.054	0.06	48
402+10		404+39	LT	4,212	1.031	0.10	80
404+62		405+00	LT	1,016	1.031	0.02	16
TOTAL							264

ESTIMATED QUANTITY SCHEDULE		
PAY CODE	DESCRIPTION	QUANTITY
70300100	SHORT-TERM PAVEMENT MARKING	240 SQ FT
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	1,320 FOOT
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	4,481 SQ FT
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	600 FOOT
78300100	PAVEMENT MARKING REMOVAL	2,700 SQ FT

BITUMINOUS SHOULDER SCHEDULE							
STA	TO	STA	LT / RT	AVERAGE WIDTH	LENGTH	40603310 HMA SC "C" N50	48203021 HMA SHOULDER 6
				(FEET)	(FEET)	(TON)	(SQ YD)
395+88.00		396+18.00	RT	9.92	30.00	3.9	34
396+18.00		396+53.00	RT	12.39	35.00	5.5	49
396+53.00		396+83.00	RT	9.87	30.00	3.7	33
396+83.00		398+46.13	RT	5.84	163.13	11.9	106
396+92.00		397+22.00	LT	10.44	30.00	4.0	35
397+22.00		397+57.00	LT	13.2	35.00	5.9	52
397+57.00		397+87.00	LT	10.59	30.00	4.1	36
397+87.00		398+74.83	LT	3.03	87.83	3.4	30
401+41.05		403+14.00	LT	5.50	172.95	11.9	106
403+14.00		403+44.00	LT	9.98	30.00	3.9	34
403+44.00		403+79.00	LT	12.51	35.00	5.5	49
403+79.00		404+09.00	LT	10.25	30.00	4.0	35
404+09.00		405+00.00	LT	8.19	91.00	9.3	83
401+20.32		402+08.50	RT	2.86	88.18	3.3	29
402+08.50		402+38.50	RT	11.00	30.00	4.2	37
402+38.50		402+73.50	RT	13.72	35.00	6.1	54
402+73.50		402+98.47	RT	11.57	24.97	3.7	33
TOTALS						94.3	835
USE						95	835