

TEMPORARY BARRIER & IMPACT ATTENUATOR SCHEDULE								
STA	OFFSET	STA	OFFSET	LT / RT	70400100	70400200	Z0030250	Z0030350
					TEMP CONC BARRIER	REL TEMP CONC BARRIER	IMP ATTN NRD TL3	IMP ATTN REL NRD TL3
	(FOOT)		(FOOT)		(FOOT)	(FOOT)	(EACH)	(EACH)
STAGE 1								
556+36.50				RT			1	
556+36.50	18.1	556+74.00	15.0	RT	37.5			
556+74.00	15.0	561+61.50	15.0	RT	487.5			
119+24.00	15.0	124+11.50	15.0	LT	487.5			
124+11.50	15.0	124+49.00	18.1	LT	37.5			
124+49.00				LT			1	
STD 701402								
556+36.50				RT				1
556+36.50		556+74.00		RT		37.5		
556+74.00		561+61.50		RT		487.5		
119+24.00		124+11.50		LT		487.5		
124+11.50		124+49.00		LT		37.5		
124+49.00				LT				1
556+36.50				RT				1
556+36.50		556+74.00		RT		37.5		
556+74.00		561+61.50		RT		487.5		
119+24.00		124+11.50		LT		487.5		
124+11.50		124+49.00		LT		37.5		
124+49.00				LT				1
TOTALS					1,050.0	2,100.0	2	4

STRIPING SCHEDULE				
STA	TO	STA	LT/RT/CL	78001110
				PAINT PVT MK LINE 4 (2 APPS)
				(FOOT)
395+88.00		405+00.00	LT	1,824
395+88.00		405+00.00	RT	1,824
395+88.00		405+00.00	CL	3,648
TOTALS				7,296

BARRIER WALL MARKER SCHEDULE				
STATION	TO	STATION	LT / RT	78200520
				BAR WALL MKR TYPE B
				(EACH)
399+00		401+00	RT	2
399+00		401+00	LT	2
TOTAL				4

GUARDRAIL SCHEDULE										
STA	TO	STA	LT / RT	63000001	63100085	63100167	63200310	63302000	78200410	78201000
				SPBGR TY A 6FT POSTS	TRAF BAR TERM T6	TR BAR TRM T1 SPL TAN	GUARDRAIL REMOV	REM RE-E T B TERM T2	GUARDRAIL MKR TYPE A	TERMINAL MKR - DA
				(FOOT)	(EACH)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)
WELDON ROAD										
396+28.00		396+78.00	RT			1				1
396+78.00		398+03.00	RT	125.0					2	
398+03.00		398+46.00	RT		1				1	
397+32.00		397+82.00	LT			1				1
397+82.00		398+32.00	LT	50.0					1	
398+32.00		398+75.00	LT		1				1	
401+20.00		401+63.00	RT		1				1	
401+63.00		402+13.00	RT	50.0					1	
402+13.00		402+63.00	RT			1				1
401+51.00		401+94.00	LT		1				1	
401+94.00		403+19.00	LT	125.0					2	
403+19.00		403+69.00	LT			1				1
398+00.00		398+46.00	RT				46.0			
398+27.00		398+73.00	LT				46.0			
401+24.00		401+70.00	RT				46.0			
401+49.00		401+95.00	LT				46.0			
US 20										
121+71.00		121+83.50	LT					2		
120+33.50		121+83.50	LT	150.0			150.0		2	
559+15.50		559+28.00	RT					2		
559+15.50		560+65.50	RT	150.0			150.0		2	
TOTALS				650.0	4	4	484	4	14	4

DELINEATOR SCHEDULE			
STATION	OFFSET	LT / RT	63500105
			DELINEATORS
			(EACH)
396+28	26	RT	1
397+32	26	LT	1
398+32	38	RT	1
398+62	78	LT	1
401+34	31	RT	1
401+64	78	LT	1
402+64	26	RT	1
403+69	26	LT	1
TOTAL			8

PERMANENT SURVEY MARKER		
ITEM NO.	LOCATION	66700095
		PERM SURV MKRS
		(EACH)
1	SOUTH OF STRUCTURE	1
2	SOUTH OF STRUCTURE	1
3	NORTH OF STRUCTURE	1
4	NORTH OF STRUCTURE	1
TOTAL		4

CONTRACTOR SHALL COORDINATE & VERIFY EXACT LOCATION OF PERMANENT SURVEY MARKERS WITH THE ENGINEER.

SIGNING SCHEDULE									
EX STA	PR STA	RT / LT	MUTCD CODE NUMBER	DESCRIPTION	HEIGHT	WIDTH	X0321866	X8950810	73000100
					(IN)	(IN)	RM STOR & RE-E SN PAN	REM & RE-E FL BEACON	WOOD SIGN SUPPORT
							(SQ FT)	(EACH)	(FOOT)
401+49	401+49	RT	W3-1a	STOP AHEAD	30	30	6.25	1	14
TOTALS							6.25	1	14
USE							7	1	14