

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK EX S ABUT	398+52.94	14.69	832.38	832.38
CL BRG S ABUT	398+55.82	14.69	832.41	832.41
A	398+65.82	14.69	832.53	832.54
B	398+75.82	14.69	832.63	832.65
C	398+85.82	14.69	832.72	832.74
D	398+95.82	14.69	832.80	832.81
CL EX BRG PIER 1	399+10.69	14.69	832.89	832.89
E	399+20.69	14.69	832.94	832.95
F	399+30.69	14.69	832.97	833.01
G	399+40.69	14.69	833.00	833.05
H	399+50.69	14.69	833.01	833.07
I	399+60.69	14.69	833.01	833.06
J	399+70.69	14.69	833.00	833.02
K	399+80.69	14.69	832.98	832.98
CL EX BRG PIER 2	399+86.19	14.69	832.96	832.96
L	399+96.19	14.69	832.92	832.93
M	400+06.19	14.69	832.86	832.90
N	400+16.19	14.69	832.80	832.85
O	400+26.19	14.69	832.72	832.78
P	400+36.19	14.69	832.63	832.68
Q	400+46.19	14.69	832.53	832.56
R	400+56.19	14.69	832.41	832.42
CL EX BRG PIER 3	400+61.69	14.69	832.35	832.35
S	400+71.69	14.69	832.21	832.22
T	400+81.69	14.69	832.07	832.08
U	400+91.69	14.69	831.91	831.93
V	401+01.69	14.69	831.75	831.76
CL BRG N ABUT	401+13.07	14.69	831.54	831.54
BK EX N ABUT	401+15.94	14.69	831.49	831.49

WEST GUTTER LINE

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK EX S ABUT	398+81.53	-16.00	832.65	832.65
CL BRG S ABUT	398+84.40	-16.00	832.68	832.68
A	398+94.40	-16.00	832.76	832.78
B	399+04.40	-16.00	832.83	832.85
C	399+14.40	-16.00	832.88	832.90
D	399+24.40	-16.00	832.93	832.94
CL EX BRG PIER 1	399+39.28	-16.00	832.97	832.97
E	399+49.28	-16.00	832.98	833.00
F	399+59.28	-16.00	832.98	833.02
G	399+69.28	-16.00	832.97	833.03
H	399+79.28	-16.00	832.95	833.01
I	399+89.28	-16.00	832.92	832.97
J	399+99.28	-16.00	832.87	832.90
K	400+09.28	-16.00	832.82	832.82
CL EX BRG PIER 2	400+14.78	-16.00	832.78	832.78
L	400+24.78	-16.00	832.70	832.72
M	400+34.78	-16.00	832.62	832.65
N	400+44.78	-16.00	832.52	832.57
O	400+54.78	-16.00	832.40	832.47
P	400+64.78	-16.00	832.28	832.33
Q	400+74.78	-16.00	832.14	832.18
R	400+84.78	-16.00	832.00	832.00
CL EX BRG PIER 3	400+90.28	-16.00	831.91	831.91
S	401+00.28	-16.00	831.74	831.75
T	401+10.28	-16.00	831.57	831.58
U	401+20.28	-16.00	831.38	831.39
V	401+30.28	-16.00	831.17	831.19
CL BRG N ABUT	401+41.65	-16.00	830.93	830.93
BK EX N ABUT	401+44.53	-16.00	830.87	830.87

DESIGNED	SCD
CHECKED	DRB
DRAWN	THW
CHECKED	SCD



IE CONSULTANTS, INC  
6420 SOUTH SIXTH STREET  
SPRINGFIELD, ILLINOIS 62712  
TEL. (217) 529-8027  
FAX (217) 529-4543  
WWW.IE-CONSULTANTS.COM

E-S

11-1-09

DECK ELEVATIONS  
S.N. 101-0120

SHEET NO.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7 OF 34 SHEETS	301	(1-1HB-1)D	WINNEBAGO	55	23
CONTRACT NO. 64E11					
ILLINOIS FED. AID PROJECT					