

IL ROUTE 251 PAVING SUMMARY	
LOCATION	HMA SURFACE COURSE MIX "D", N50 (TON)
STATION - STATION	
849+49 - 851+49 (NORTH APPROACH)	90
861+39 - 863+39 (SOUTH APPROACH)	81
TOTAL	171

PCC SURFACE REMOVAL - BUTT JOINT	
STATION - STATION	(SQ. YD.)
849+49 - 850+19 (NORTH APPROACH)	340
862+69 - 863+39 (SOUTH APPROACH)	320
TOTAL	660

POLYUREA PAVEMENT MARKING TYPE 1, LETTER & SYMBOLS	
STATION - STATION	(SQ. FT.)
848 + 84 (RIGHT + ONLY)	36.4
849 + 84 (RIGHT + ONLY)	36.4
863 + 06 (LEFT + ONLY)	36.4
TOTAL	109.2
USE	110

POLYUREA PAVEMENT MARKING TYPE 1, LINE 4"	
STATION - STATION	(FOOT)
848+84 - 865+08 (DOUBLE YELLOW)	3,800
860+38 - 863+25 (DOUBLE YELLOW)	650
845+46 - 864+46 LT (WHITE EDGE LT.)	1,900
848+66 - 865+45 RT (WHITE EDGE RT.)	1,680
TOTAL	8,030

POLYUREA PAVEMENT MARKING TYPE 1, LINE 8"	
STATION - STATION	(FOOT)
848+46 - 849+92 (SOLID WHITE)	146
849+92 - 850+99 (SKIP DASH)	36
861+97 - 863+25 (SKIP DASH)	43
863+25 - 865+08 (SOLID WHITE)	183
TOTAL	408
USE	410

POLYUREA PAVEMENT MARKING TYPE 1, LINE 12"	
STATION - STATION	(FOOT)
860+38 - 863+25 (DIAGONAL LINE)	45
TOTAL	45

FILE NAME = D264G24-aht-schedule.dgn
 PLOT DATE = 8/12/2010
 PLOT SCALE = 50.0000' / IN.

CR
CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - AUGUST 2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL. RTE. 251

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
740	(108HVB) M	OGLE	55	4
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64G24	