

NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE ACRS L25			NON-PART 80% STATE 20% VILLAGE	80% FED. 20% VILLAGE ACTE L22	NON-PART 100% VILLAGE
				0001 ROADWAY	0008 SN050-0250	0008 SN050-7201	0021 SIDEWALK	0031 ITEP	0043 WATER MAIN
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	311	311	--	--	--	--	--
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5643	5643	--	--	--	--	--
72000100	SIGN PANEL - TYPE 1	SQ FT	245.0	245.0	--	--	--	--	--
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	595	595	--	--	--	--	--
73000100	WOOD SIGN SUPPORT	FOOT	16	16	--	--	--	--	--
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	298	298	--	--	--	--	--
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	447	447	--	--	--	--	--
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	89	89	--	--	--	--	--
78200300	PRISMATIC CURB REFLECTOR	EACH	28	28	--	--	--	--	--
81000400	CONDUIT IN TRENCH, 1 1/4" DIA., GALVANIZED STEEL	FOOT	22	22	--	--	--	--	--
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	390	--	--	--	--	390	--
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	56	--	--	--	--	56	--
81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	422	410	--	--	--	12	--
81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	210	--	--	--	--	210	--
81200215	CONDUIT EMBEDDED IN STRUCTURE, 1 1/4" DIA., PVC	FOOT	238	119	--	--	--	119	--
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	23	--	--	--	--	23	--
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	800	--	--	--	--	800	--
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	1560	--	--	--	--	1560	--
81702420	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/2 NO. 8	FOOT	925	781	--	--	--	144	--
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3480	419	--	--	--	3061	--
82500410	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 200AMP (DUAL)	EACH	1	--	--	--	--	1	--
83600120	LIGHT POLE FOUNDATION (SPECIAL)	FOOT	136	--	--	--	--	136	--
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	12.5	12.5	--	--	--	--	--
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	1	1	--	--	--	--	--
84200804	REMOVAL OF POLE FOUNDATION	EACH	4	4	--	--	--	--	--
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3	3	--	--	--	--	--
X0301852	DEWATERING STRUCTURE NO. 1	EACH	2	--	2	--	--	--	--
Z0056650	STORM SEWERS/WATER MAIN QUALITY PIPE (TYPE 1) 15"	FOOT	15	15	--	--	--	--	--
X0325607	GROUND STABILIZATION GEOSYNTHETIC	SQ YD	16119	16119	--	--	--	--	--
X0325670	CONCRETE BRIDGE RAILING, SIDEWALK MOUNTED	FOOT	190	--	190	--	--	--	--
X0326498	GFCI 20 AMP DUPLEX RECEPTACLE	EACH	16	--	--	--	--	16	--
X0326654	ORNAMENTAL LIGHT UNIT, COMPLETE	EACH	27	--	--	--	--	27	--
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	268	--	183	85	--	--	--
X4240440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	233	233	--	--	--	--	--
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	--	--	1	--	--	--
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	150	150	--	--	--	--	--
X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	7779	7779	--	--	--	--	--
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	1872	1872	--	--	--	--	--
X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	416	416	--	--	--	--	--

* SPECIALTY ITEM

FILE NAME =
0366547-SHT-SUM-QUANTS.DGN

USER NAME = ---
PLOT SCALE = 1"=10'
PLOT DATE = 08/10

DESIGNED - JKC
DRAWN - ARR
CHECKED - JKC
DATE - 08/10

REVISED - ---
REVISED - ---
REVISED - ---
REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.S. RTE. 1279	SECTION 6R,B	COUNTY LASALLE	TOTAL SHEETS 190	SHEET NO. 7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
CONTRACT NO. 66547				