

NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE ACRS L25			NON-PART 80% STATE 20% VILLAGE	80% FED. 20% VILLAGE	NON-PART 100% VILLAGE
				0001 ROADWAY	0008 SN050-0250	0008 SN050-7201	0021 SIDEWALK	ACTE L22 0031 ITEP	0043 WATER MAIN
X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	570	570	--	--	--	--	
XX005967	TOPSOIL (PLANTING MIXTURE)	CU YD	396	--	--	--	--	396	
XX006652	STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE 4 INCH (SPECIAL)	SQ FT	354	354	--	--	--	--	
XX007335	PVC CASING <sup>PIPE</sup> 8"	FOOT	173	--	--	--	--	173	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	16119	16119	--	--	--	--	
Z0004002	BOLLARDS	EACH	38	--	--	--	38	--	
Z0007430	TEMPORARY SIDEWALK	SQ FT	1844	1844	--	--	--	--	
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1	--	--	--	--	
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1	--	--	--	--	
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	1	--	--	--	--	
Z0007604	BUILDING REMOVAL NO. 4	L SUM	1	1	--	--	--	--	
Z0007605	BUILDING REMOVAL NO. 5	L SUM	1	1	--	--	--	--	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	--	--	--	--	
Z0023900	FILLING EXISTING WELLS	EACH	1	1	--	--	--	--	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	--	--	--	--	
					--	--	--	--	
					--	--	--	--	
					--	--	--	--	
					--	--	--	--	
					--	--	--	--	
Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1	1	--	--	--	--	
					--	--	--	--	
Z0049903	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 3	L SUM	1	1	--	--	--	--	
					--	--	--	--	
					--	--	--	--	
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	10	10	--	--	--	--	
Z0065000	SETTING PILES IN ROCK	EACH	7	--	--	7	--	--	
Z0067100	STEEL CASINGS 8"	FOOT	40	40	--	--	--	--	
52100500	ANCHOR BOLTS, 1/2"	EACH	18	--	--	--	18	--	
					--	--	--	--	
X0327065	ENGINEERED SOIL (SPECIAL)	TON	973	--	--	--	973	--	
X0327066	PAVEMENT COLOR AND TEXTURE (SPECIAL)	SQ YD	383	--	--	--	383	--	
81603158	UNIT DUCT, 600V, 5-1C NO.8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2261	--	--	--	2261	--	
X0327067	PVC CASING <sup>PIPE</sup> 10"	FOOT	22	--	--	--	--	22	
X0327066	IN GRADE FIXTURE FOR UPLIGHTING	EACH	26	--	--	--	26	--	

\* SPECIALTY ITEM

FILE NAME =  
0366547-SHT-SUM-QUANTS.DGN

USER NAME = ---	DESIGNED - JKC	REVISED - ---
	DRAWN - ARR	REVISED - ---
PLOT SCALE = 1"=10'	CHECKED - JKC	REVISED - ---
PLOT DATE = 08/10	DATE - 08/10	REVISED - ---

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.S. RTE. 1279	SECTION 6R,B	COUNTY LASALLE	TOTAL SHEETS 190	SHEET NO. 8
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT			CONTRACT NO. 66547	