

80% FED.
20% STATE

| CODE NUMBER | ITEM | UNIT | TOTAL | ROADWAY 0005 | STRUCTURE NO. 053-0188 0011 |
|-------------|--|--------|-------|--------------|-----------------------------|
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 75 | 75 | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 90 | 90 | |
| 20101000 | TEMPORARY FENCE | FOOT | 300 | 300 | |
| 20200100 | EARTH EXCAVATION | CU YD | 630 | 630 | |
| 20300100 | CHANNEL EXCAVATION | CU YD | 1,328 | 1,328 | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 1,245 | 1,245 | |
| X2070304 | POROUS GRANULAR EMBANKMENT, SPECIAL | CU YD | 98 | | 98 |
| 20800150 | TRENCH BACKFILL | CU YD | 64 | 64 | |
| 25000100 | SEEDING, CLASS 1 | ACRE | 0.75 | 0.75 | |
| 25000300 | SEEDING, CLASS 3 | ACRE | 0.75 | 0.75 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 136 | 136 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 136 | 136 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 136 | 136 | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 6,288 | 6,288 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 450 | 450 | |
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 40 | 40 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 1,491 | 1,491 | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 16 | 16 | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 1,920 | | 1,920 |
| 28200200 | FILTER FABRIC | SQ YD | 1,920 | | 1,920 |
| 31100500 | SUB-BASE GRANULAR MATERIAL, TYPE A 6" | SQ YD | 255 | 255 | |
| 31100910 | SUB-BASE GRANULAR MATERIAL, TYPE A 12" | SQ YD | 1,543 | 1,543 | |
| 40201000 | AGGREGATE FOR TEMPORARY ACCESS | TON | 131 | 131 | |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 706 | 706 | |
| 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 290 | 290 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 346 | 346 | |
| 40600990 | TEMPORARY RAMP | SQ YD | 60 | 60 | |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 789 | 789 | |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 219 | 219 | |

* SPECIALTY ITEM

△ REVISED 10/19/2010

80% FED.
20% STATE

| CODE NUMBER | ITEM | UNIT | TOTAL | ROADWAY 0005 | STRUCTURE NO. 053-0188 0011 |
|-------------|--|--------|--------|--------------|-----------------------------|
| 40800010 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 108 | 108 | |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 48 | 48 | |
| 42001430 | BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) | SQ YD | 42 | 42 | |
| 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 75 | 75 | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 293 | 293 | |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SQ FT | 210 | 210 | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 1,536 | 1,536 | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 255 | 255 | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 1,705 | 1,705 | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 159 | 159 | |
| 44000400 | GUTTER REMOVAL | FOOT | 92 | 92 | |
| 48101500 | AGGREGATE SHOULDERS, TYPE B 6" | SQ YD | 128 | 128 | |
| 50100100 | REMOVAL OF EXISTING STRUCTURES | EACH | 1 | | 1 |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 185 | | 185 |
| 50300100 | FLOOR DRAINS | EACH | 10 | | 10 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 150.8 | | 150.8 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 375.6 | | 375.6 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 898 | | 898 |
| 50300280 | CONCRETE ENCASEMENT | CU YD | 17.6 | | 17.6 |
| 50300300 | PROTECTIVE COAT | SQ YD | 1,188 | | 1,188 |
| 50500105 | FURNISHING AND ERECTING STRUCTURAL STEEL | L SUM | 1 | | 1 |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 4,986 | | 4,986 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 96,780 | | 96,780 |
| 50800515 | BAR SPLICERS | EACH | 1,026 | | 1,026 |
| 51201800 | FURNISHING STEEL PILES HP14x73 | FOOT | 1,051 | | 1,051 |
| 51202305 | DRIVING PILES | FOOT | 1,051 | | 1,051 |
| 51203800 | TEST PILE STEEL HP14x73 | EACH | 2 | | 2 |
| 51204650 | PILE SHOES | EACH | 7 | | 7 |
| 51500100 | NAME PLATES | EACH | 1 | | 1 |

* SPECIALTY ITEM

| | | | | | | | | | | | |
|-------------|----------------------|-----------------|-----------|---|------------------------------|-----------------|--------------------------|-------------------|---------------------|---------------------------|--------------------|
| FILE NAME = | USER NAME = #USER# | DESIGNED - JML | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.P. RTE. 317 | SECTION (25)BR-2 | COUNTY LIVINGSTON | TOTAL SHEETS 58 | SHEET NO. 3 | |
| #FILEL# | PLOT SCALE = #SCALE# | DRAWN - JJO | REVISED - | | | SCALE: | SHEET NO. OF SHEETS STA. | TO STA. | FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT | CONTRACT NO. 66823 |
| | PLOT DATE = #DATE# | CHECKED - MSW | REVISED - | | | | | | | | |
| | | DATE - 08/13/10 | REVISED - | | | | | | | | |