

CODE NUMBER	ITEM	UNIT	80% FED. 20% STATE		STRUCTURE NO. 053-0188 0011
			TOTAL	ROADWAY 0005	
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	75	75	
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	90	90	
2010030	TEMPORARY FENCE	FOOT	300	300	
2020000	EARTH EXCAVATION	CU YD	630	630	
2030000	CHANNEL EXCAVATION	CU YD	1,328	1,328	
2040000	FURNISHED EXCAVATION	CU YD	1,245	1,245	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	98		98
20800150	TRENCH BACKFILL	CU YD	64	64	
25000100	SEEDING, CLASS 1	ACRE	0.75	0.75	
25000300	SEEDING, CLASS 3	ACRE	0.75	0.75	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	136	136	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	136	136	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	136	136	
25100630	EROSION CONTROL BLANKET	SQ YD	6,288	6,288	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4,050	4,050	
28000305	TEMPORARY DITCH CHECKS	FOOT	40	40	
28000400	PERIMETER EROSION BARRIER	FOOT	1,491	1,491	
28000500	INLET AND PIPE PROTECTION	EACH	16	16	
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,920		1,920
28200200	FILTER FABRIC	SQ YD	1,920		1,920
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	255	255	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1,543	1,543	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	131	131	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	706	706	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	290	290	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	346	346	
40600990	TEMPORARY RAMP	SQ YD	60	60	
40601080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	789	789	
40601335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	219	219	

• SPECIALTY ITEM

CODE NUMBER	ITEM	UNIT	80% FED. 20% STATE		STRUCTURE NO. 053-0188 0011
			TOTAL	ROADWAY 0005	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	108	108	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	48	48	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	42	42	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	75	75	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	293	293	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	210	210	
44000100	PAVEMENT REMOVAL	SQ YD	1,536	1,536	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	255	255	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,705	1,705	
44000600	SIDEWALK REMOVAL	SQ FT	159	159	
44000400	GUTTER REMOVAL	FOOT	91	91	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	128	128	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	185		185
50300100	FLOOR DRAINS	EACH	10		10
50300225	CONCRETE STRUCTURES	CU YD	150.8		150.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	375.6		375.6
50300260	BRIDGE DECK GROOVING	SQ YD	898		898
50300280	CONCRETE ENCASEMENT	CU YD	17.6		17.6
50300300	PROTECTIVE COAT	SQ YD	1,188		1,188
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	4,986		4,986
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	96,780		96,780
50800515	BAR SPLICERS	EACH	1,026		1,026
51201800	FURNISHING STEEL PILES HP14x73	FOOT	1,051		1,051
51202305	DRIVING PILES	FOOT	1,051		1,051
51203800	TEST PILE STEEL HP14x73	EACH	2		2
51204650	PILE SHOES	EACH	7		7
51500100	NAME PLATES	EACH	1		1

• SPECIALTY ITEM

FILE NAME	DESIGNED - JML	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCALE	CHECKED - MSW	REVISED -				317	(25)BR-2	LIVINGSTON	EB	3
DATE	DATE - 08/13/10	REVISED -				CONTRACT NO. 66823				
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				