

80% FED.  
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0005	STRUCTURE NO. 053-0188 0011
52100520	ANCHOR BOLTS, 1"	EACH	48		48
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	36	36	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	169	169	
55100500	STORM SEWER REMOVAL 12"	FOOT	97	97	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	56		56
<del>Z0046304</del>	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	142		142
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1	
60240200	INLETS, TYPE A, SPECIAL	EACH	1	1	
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2	
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	4	4	
60262510	INLETS TO BE ADJUSTED WITH NEW FRAME AND GRATE (SPECIAL)	EACH	1	1	
60263100	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	2	2	
60404300	FRAMES AND GRATES, TYPE 3	EACH	1	1	
60500060	REMOVING INLETS	EACH	3	3	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	24.3	24.3	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,430	1,430	
60605500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	70	70	
60614600	PAVED DITCH (SPECIAL)	FOOT	76	76	
• 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125	
• 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
• 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	250	250	
66503200	BARBED WIRE FENCE, FIVE STRAND	FOOT	513	513	
66503400	BARBED WIRE FENCE REMOVAL	FOOT	517	517	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6	6	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	

• SPECIALTY ITEM

80% FED.  
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0005	STRUCTURE NO. 053-0188 0011
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
• 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,380	1,380	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10,102	10,102	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	26	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,879	3,879	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,387.5	1,387.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,375	1,375	
• 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2,346	2,346	
• 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	300	300	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16	
• 78200405	GUARDRAIL MARKERS	EACH	12	12	
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	18		18
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
X0322208	TEMPORARY STORM SEWER PLUGS	EACH	1	1	
<del>Z0073002</del>	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	498		498
<del>X1660410</del>	REMOVE RIGHT-OF-WAY MARKERS	EACH	1	1	
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	300	300	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
X5080600	MECHANICAL SPLICERS	EACH	36		36

• SPECIALTY ITEM

FILE NAME =	USER NAME = \$USER\$	DESIGNED - JML	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILEL\$		DRAWN - JJO	REVISED -					317	(25)BR-2	LIVINGSTON	58	4
	PLOT SCALE = \$SCALE\$	CHECKED - MSW	REVISED -					CONTRACT NO. 66823				
	PLOT DATE = \$DATE\$	DATE - 08/13/10	REVISED -					FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				
				SCALE: SHEET NO. OF SHEETS STA. TO STA.								