

TEMPORARY PAVING MATERIALS		
LOCATION	AGGREGATE FOR TEMPORARY ACCESS	TEMPORARY RAMP
	TON	SQ YD
STA 468+65		15
STA 472+42.71		15
STA 475+31.29		15
STA 477+17 40' LT TO STA 479+71 38' LT	131	
STA 480+38		15
TOTAL	131	60

REMOVAL OF PAVING MATERIALS					
LOCATION	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	GUTTER OUTLET REMOVAL
	SQ YD	SQ YD	FOOT	SQ FT	FOOT
STA 469+54 LT TO STA 470+00 LT					
STA 469+54 RT TO STA 470+00 RT					46
STA 470+00 LT TO STA 473+00 LT			300		46
STA 470+00 RT TO STA 472+89 RT			289		
STA 470+72 TO STA 472+93	638				
STA 474+75 RT TO STA 480+38 RT			563		
STA 474+81 TO STA 477+92	898				
STA 474+85 LT TO STA 480+38 LT			553		
STA 476+12 LT TO STA 476+65 LT				159	
STA 477+10 LT		48			
STA 478+10 RT		91			
STA 478+35 LT		58			
STA 479+58 LT		58			
TOTAL	1,536	255	1,705	159	92

DRAINAGE							
LOCATION	STORM SEWER REMOVAL 12"	STORM SEWERS, CLASS A, 12"		TEMPORARY STORM SEWER PLUGS	CLASS SI CONCRETE (OUTLET)	COMBINATION CONCRETE CURB AND GUTTER	PAVED DITCH (SPECIAL)
	FOOT	FOOT		EACH	CU YD	FOOT	
		TY 1	TY 2			TY B-6.24	TY B-6.24 (VARIABLE WIDTH GUTTER FLAG)
STA 469+50 TO STA 470+00					24.3		
STA 470+00 LT TO STA 472+30 LT						230	
STA 470+00 RT TO STA 472+22 RT						222	
STA 472+22 RT TO STA 472+39 RT							17
STA 472+30 LT TO STA 472+47 LT							17
STA 475+46 LT TO STA 475+57 LT							11
STA 475+46 LT TO STA 480+38 LT						492	
STA 475+52 RT TO STA 475+77 RT							25
STA 475+52 RT TO STA 480+38 RT						486	
STA 475+61.50 LT TO STA 475+62 LT	12						
STA 476+60 LT TO STA 477+35 LT			72				
STA 476+89 LT TO STA 476+93 RT	42						
STA 476+89 LT TO STA 477+31.50 LT	43						
STA 476+95.21 RT TO STA 477+35 LT			56				
STA 477+18 LT TO STA 477+35 LT		36					
STA 477+23 2' LT				1			
STA 477+25 LT TO STA 478+00 LT							76
STA 477+35 LT TO STA 477+75 LT			41				
TOTAL	97	36	169	1	24.3	1,430	70

GUARDRAIL				
LOCATION	GUARDRAIL REMOVAL	SPBGR, TYPE A, 6 FT POSTS	TRAF BAR TERM TY 6	TRAF BAR TERM TY 1 SPL TAN
	FOOT	FOOT	EACH	EACH
STA 471+10.51 RT TO STA 471+60.51 RT				1
STA 471+56.47 LT TO STA 472+06.47 LT				1
STA 471+60.51 RT TO STA 472+10.51 RT		50		
STA 472+06.47 LT TO STA 472+18.97 LT		12.5		
STA 472+10.51 RT TO STA 472+54.26 RT			1	
STA 472+18.97 LT TO STA 472+62.72 LT			1	
STA 472+28 RT TO STA 472+90.50 RT	62			
STA 472+38 LT TO STA 473+00.50 LT	62			
STA 474+73.50 RT TO STA 475+36 RT	63			
STA 474+84 LT TO STA 475+46.50 LT	63			
STA 475+10.74 RT TO STA 475+54.49 RT			1	
STA 475+20.53 LT TO STA 475+64.28 LT			1	
STA 475+54.49 RT TO STA 475+66.99 RT		12.5		
STA 475+64.28 LT TO STA 476+14.28 LT		50		
STA 475+66.99 RT TO STA 476+16.99 RT				1
STA 476+14.28 LT TO STA 476+64.28 LT				1
TOTAL	250	125	4	4

INCIDENTAL PAVING MATERIALS		
LOCATION	BIT MATLS PRIME COAT	INCIDENTAL HMA SURFACING
	GALLON	TON
STA 477+17 40' LT TO STA 479+71 38' LT	108	48
TOTAL	108	48

FENCING			
LOCATION	BARBED WIRE FENCE REMOVAL	BARBED WIRE FENCE, FIVE STRAND	TEMPORARY FENCE
	FOOT	FOOT	FOOT
STA 468+10 RT TO STA 473+22.50 RT		513	
STA 468+10 RT TO STA 473+27 RT	517		
STA 470+00 54' LT TO STA 473+00 68' LT			300
TOTAL	517	513	300

FILE NAME =	USER NAME = #USER#	DESIGNED - JML	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - JJO	REVISED -			317	(25)BR-2	LIVINGSTON	98	9	
		CHECKED - MSW	REVISED -			CONTRACT NO. 66823		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			
		DATE - 08/13/10	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.		

FARNSWORTH GROUP, INC. CONSULTING ENGINEERS - 2709 MCGRAW DRIVE BLOOMINGTON, ILLINOIS 61704 (309) 663-8435 / (309) 663-1571 FAX