

80% FEDERAL  
20% STATE

NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0040
20200100	EARTH EXCAVATION	CU YD	70	
20400800	FURNISHED EXCAVATION	CU YD	36	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	241	
* 25000210	SEEDING, CLASS 2A	ACRE	0.4	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	
* 25100115	MULCH, METHOD 2	ACRE	0.4	
25100630	EROSION CONTROL BLANKET	SQ YD	73	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	360	
28000305	TEMPORARY DITCH CHECKS	FOOT	48	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	184	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	241	
35501342	HOT-MIX ASPHALT BASE COURSE, 14 1/2"	SQ YD	165	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	152	
40600300	AGGREGATE (PRIME COAT)	TON	4	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.35	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	64	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	346	
40600990	TEMPORARY RAMP	SQ YD	30	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	159	
44000100	PAVEMENT REMOVAL	SQ YD	184	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	90	
50800105	REINFORCEMENT BARS	POUND	6060	
Z0026407	TEMPORARY SHEET PILING	SQ FT	713	

80% FEDERAL  
20% STATE

NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0040
54003000	CONCRETE BOX CULVERTS	CU YD	41.1	
54010503	PRECAST CONCRETE BOX CULVERTS 5' X 3'	FOOT	108	
63200310	GUARDRAIL REMOVAL	FOOT	281	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	
67100100	MOBILIZATION	L SUM	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	75	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	180	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1670	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	629	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	362.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1160	
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	150	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	76	
X0324043	GRATING FOR CONCRETE HEADWALL	EACH	2	
X5015200	REMOVE EXISTING CULVERTS	EACH	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	

\* SPECIALTY ITEM

FILE NAME =  
0366870-SHT-000.DGN

USER NAME = ---	DESIGNED - JKC	REVISED - ---
DRAWN - NV	CHECKED - JKC	REVISED - ---
PLOT SCALE = 1"=1'	DATE - 01/10	REVISED - ---
PLOT DATE = 01/10		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE. 681	SECTION (115)I	COUNTY LIVINGSTON	TOTAL SHEETS 20	SHEET NO. 3
CONTRACT NO. 66870				
ILLINOIS FED. AID PROJECT				