

EARTHWORK QUANTITIES				
LOCATION	THEORETICAL		FURNISHED EXCAVATION SHORTAGE (-) OR EXCESS (+)	REMARKS
	CUT	FILL		
	CU YD	CU YD	CU YD	
	(A)	(B)	[(A)0.75]-(B)	
STA. 147+00 TO STA. 151+00, LT. & RT.	70	88	-36	
TOTAL	70	88	-36	
	PAY ITEM	---	PAY ITEM	

PAVEMENT SCHEDULE											
LOCATION	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	TON	SQ YD	SQ YD
	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	HMA BASE COURSE, 8"	HOT-MIX ASPHALT BASE COURSE, 14 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	LEVELING BINDER (MACHINE METHOD), N50	HMA SURFACE COURSE, MIX "C", N50	AGGREGATE SHOULDERS, TYPE B	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
STA 146+10 TO STA 146+70	--	--	--	--	--	--	--	--	--	173	15
STA 151+30 TO STA 151+90	--	--	--	--	--	--	--	--	--	173	15
STA. 148+98 TO STA. 149+55 (STAGE I)	70	--	60	--	--	--	--	--	--	--	--
STA. 148+98 TO STA. 149+55 (STAGE II)	114	19	105	--	--	--	--	--	4	--	--
LT. STA. 147+60.5 TO STA. 150+94 (STAGE I)	--	111	--	--	--	--	--	--	25	--	--
RT. STA. 147+57 TO STA. 150+90.5 (PRIOR TO STAGE I)	--	111	--	--	--	--	--	--	25	--	--
STA. 146+70 TO STA. 148+98	--	--	--	--	--	0.20	--	--	--	--	--
STA. 149+55 TO STA. 151+30	--	--	--	--	--	0.15	--	--	--	--	--
STA. 146+76 TO STA. 151+24	--	--	--	--	--	--	64	--	--	--	--
STA. 146+10 TO STA. 151+90	--	--	--	152	4	--	--	159	36	--	--
TOTAL	184	241	165	152	4	0.35	64	159	90	346	30

EROSION CONTROL BLANKET	
LOCATION	SQ YD
LT. END OF BOX CULVERT	36.5
RT. END OF BOX CULVERT	36.5
---	---
TOTAL	73

PAVEMENT REMOVAL	
LOCATION	SQ YD
STA. 148+98 TO STA. 149+55 (LT. & RT.)	184
---	---
TOTAL	184

TEMPORARY DITCH CHECKS	
LOCATION	FOOT
LT. STA. 149+09	12
LT. STA. 149+65	12
RT. STA. 148+88	12
RT. STA. 149+43	12
TOTAL	48

GUARDRAIL REMOVAL	
LOCATION	FOOT
RT. STA. 148+52.00 TO STA. 149+92.56	141
LT. STA. 148+76.57 TO STA. 150+16.67	140
---	---
TOTAL	281

PAVEMENT MARKING				
LOCATION	FOOT	FOOT	EACH	EACH
	EPOXY PAVEMENT MARKING - LINE 4"	EPOXY PAVEMENT MARKING - LINE 6"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STA 146+10 TO STA 151+90	1160	150	8	8
---	--	--	--	--
---	--	--	--	--
---	--	--	--	--
---	--	--	--	--
TOTAL	1160	150	8	8