

CODE NUMBER	ITEM	UNIT	TOTAL	80% FED. STATE	STP (L2S) FORD CO.	STP (L-2S) FORD CO.	BRF (L1C) FORD CO.	BRF (L1C) FORD CO.	STP (L2S) TROQUOIS CO.
				STRUCTURE NO. 027-2018 0011	STRUCTURE NO. 027-2553 0040	STRUCTURE NO. 027-0100 0011	STRUCTURE NO. 027-0098 0011	STRUCTURE NO. 038-2549 0040	
20200100	EARTH EXCAVATION	CU YD	8,145	3,100	1,985	2,395	495	170	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	338	98	96			144	
20300100	CHANNEL EXCAVATION	CU YD	4,240			1,540	2,700		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	625	220	125			280	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	130			60	70		
20800150	TRENCH BACKFILL	CU YD	308		257	18	33		
25000300	SEEDING, CLASS 3	ACRE	6.50	2.00	1.00	2.00	1.00	0.50	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	585	180	90	180	90	45	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	585	180	90	180	90	45	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	585	180	90	180	90	45	
25100630	EROSION CONTROL BLANKET	SQ YD	24,492	8,018	3,743	7,714	4,413	604	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	21,250	6,600	3,300	6,600	3,300	1,450	
28000305	TEMPORARY DITCH CHECKS	FOOT	265	90	60	65	50		
28000400	PERIMETER EROSION BARRIER	FOOT	6,779	1,850	1,158	1,756	1,278	737	
28000500	INLET AND PIPE PROTECTION	EACH	18	1	5	5	5	2	
28100105	STONE RIPRAP, CLASS A3	SQ YD	66		44			22	
28100107	STONE RIPRAP, CLASS A4	SQ YD	3,253	471	415	970	1,295	102	
28200200	FILTER FABRIC	SQ YD	3,253	471	415	970	1,295	102	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1,730	333	1,210			187	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	429		90	181	158		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,664	416	626	311	163	148	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	897	498	77	203	97	22	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,384	346	346	173	173	346	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	983	196	673			114	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	780	233	178	203	107	59	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	149			59	90		

\* SPECIALTY ITEM

FILE NAME =  
#FILE#

USER NAME = #USER#

DESIGNED - JML

REVISED -

PLOT SCALE = #SCALE#

DRAWN - DJM

REVISED -

PLOT DATE = #DATE#

CHECKED - MSW

REVISED -

DATE - 08/04/10

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	*	FORD/TROQUOIS	146	3
CONTRACT NO. 66880				

FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT

24-8271