

CODE NUMBER	ITEM	UNIT	TOTAL	80% FED. 20% STATE	STP (L25) FORD CO.	STP (L25) FORD CO.	BRF (L1C) FORD CO.	BRF (L1C) FORD CO.	STP (L25) IROQUOIS CO.
				STRUCTURE NO. 027-2018 0011	STRUCTURE NO. 027-2553 0040	STRUCTURE NO. 027-0100 0011	STRUCTURE NO. 027-0098 0011	STRUCTURE NO. 038-2549 0040	
44000100	PAVEMENT REMOVAL	SQ YD	1,879		220	1,004	247	300	108
X4401190	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,302				1,013	289	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	4,224	1,064	671	1,030	734	725	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1					
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1					
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1				
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1		1				
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1			1			
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1				1		
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1						1
50104400	CONCRETE HEADWALL REMOVAL	EACH	6			3	3		
X5015200	REMOVE EXISTING CULVERTS	EACH	19	3	3	8	5		
50200100	STRUCTURE EXCAVATION	CU YD	328			174	154		
50300100	FLOOR DRAINS	EACH	16			8	8		
50300225	CONCRETE STRUCTURES	CU YD	302.9			141.2	161.7		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	689.7			317.2	372.5		
50300260	BRIDGE DECK GROOVING	SQ YD	1,064			509	555		
50300280	CONCRETE ENCASEMENT	CU YD	23.8			11.2	12.6		
50300300	PROTECTIVE COAT	SQ YD	1,370			655	715		
50800105	REINFORCEMENT BARS	POUND	25,060	10,130	8,090				6,840
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	161,740	510		75,360	85,180		690
51201610	FURNISHING STEEL PILES HP12x63	FOOT	2,593			1,439	1,154		
51202305	DRIVING PILES	FOOT	2,593			1,439	1,154		
51203610	TEST PILE STEEL HP12x63	EACH	3			2	1		
51204650	PILE SHOES	EACH	36				36		
51500100	NAME PLATES	EACH	3	1		1	1		

* SPECIALTY ITEM

FILE NAME =	USER NAME = *USER*	DESIGNED - JML	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 681	SECTION *	COUNTY FORD/IROQUOIS	TOTAL SHEETS 146	SHEET NO. 4
*FILE#		DRAWN - DJM	REVISED -		SCALE:	SHEET NO. OF	SHEETS	STA. TO STA.	CONTRACT NO. 66880				
		CHECKED - MSW	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								
		DATE - 08/04/10	REVISED -		* 116 BR/1116 BR, (BR-2)BR, I & BR-3J								