

CODE NUMBER	ITEM	UNIT	TOTAL	80% FED- 20% STATE	STP (L25) FORD	STP (L25) FORD CO.	BRF (L1C) FORD CO.	BRF (L1C) FORD CO.	STP (L25) IROQUOIS CO.
				STRUCTURE NO. 027-2018 0011	STRUCTURE NO. 027-2553 0040	STRUCTURE NO. 027-0100 0011	STRUCTURE NO. 027-0098 0011	STRUCTURE NO. 038-2549 0040	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2		2				
54003000	CONCRETE BOX CULVERTS	CU YD	178.1		71.4	47.7			59.0
54020403	PRECAST CONCRETE BOX CULVERTS 4' x 3' (M273)	FOOT	60		60				
54020605	PRECAST CONCRETE BOX CULVERTS 6' x 5' (M273)	FOOT	76			76			
54020808	PRECAST CONCRETE BOX CULVERTS 8' x 8' (M273)	FOOT	86						86
54021007	PRECAST CONCRETE BOX CULVERTS 10' x 7' (M273)	FOOT	114		114				
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	153		24	45		84	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	344				250	94	
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	135			135			
542A5497	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	42			42			
54213450	END SECTIONS 15"	EACH	5			1		4	
54213459	END SECTIONS 24"	EACH	10				7	3	
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	6			6			
54214527	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 42"	EACH	2			2			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	76				36	40	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4		2	2			
60100945	PIPE DRAINS 12"	FOOT	12						12
60046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	262				126	136	
60602800	CONCRETE GUTTER, TYPE B	FOOT	138						138
60603300	GUTTER OUTLET	EACH	2						2
60801015	FLAP GATE 15"	EACH	2		1	1			
60801024	FLAP GATE 24"	EACH	6				3	3	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,800		500	275	650	187.5	187.5
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	225						225
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	150		100				50
* 63100045	TRAFFIC BARRIER TERMINAL TYPE 2	EACH	1					1	

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED - JML	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
*FILE#		DRAWN - DJM	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	681	*	FORD/IROQUOIS	146	5
		CHECKED - MSW	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						
		DATE - 08/04/10	REVISED -						CONTRACT NO. 66880						

FARNSWORTH GROUP, INC.

CONSULTING ENGINEERS - 2709 MCGRAW DRIVE BLOOMINGTON, ILLINOIS 61704 (309) 663-8435 / (309) 663-1571 FAX

* 116 BR/116 BR, (BR-2)BR, I & BR-31

24-8271