

SCHEDULE OF QUANTITIES

48102100 AGGREGATE WEDGE SHOULDER, TYPE B

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AVERAGE THICKNESS (FOOT)	(TON)
45+65.14		47+00.00	LT 135.0	4.0	0.125	4.5
47+00.00		49+00.00	LT 200.0	4.0	0.250	13.3
49+00.00		51+00.00	LT 200.0	4.0	0.125	6.7
45+25.00		45+77.15	RT 53.0	4.0	0.125	1.8
45+77.15		47+00.00	RT 122.9	4.0	0.125	4.1
47+00.00		49+00.00	RT 200.0	4.0	0.250	13.3
49+00.00		49+83.75	RT 83.8	4.0	0.125	2.8
TOTAL =						46.5
USE =						50.0

Z0038700 PERMANENT BENCH MARKS

LOCATION	DESCRIPTION	(EACH)
S. N. 092-2039	STRUCTURE HEADWALL	1.0
TOTAL =		1.0
USE =		1.0

66600105 FURNISH AND ERECT ROW MARKERS

STATION	OFFSET	(EACH)
45+38.75	45.0' LT	1.0
45+25.00	45.0' RT	1.0
46+75.32	45.0' LT	1.0
46+75.32	45.0' RT	1.0
48+95.32	45.0' RT	1.0
49+50.00	37.0' LT	1.0
49+50.00	80.0' LT	1.0
49+50.00	33.0' RT	1.0
49+50.00	45.0' RT	1.0
TOTAL =		9.0
USE =		9.0