

# SCHEDULE OF QUANTITIES

## 70300100 SHORT-TERM PAVEMENT MARKING

STATION	TO	STATION	DESCRIPTION	LENGTH (FOOT)
47+00		49+00	YELLOW: LINE 4 INCH CENTERLINE	20.0
TOTAL =				20.0
USE =				20.0

## 70300220 TEMPORARY PAVEMENT MARKING LINE 4 INCH

STATION	TO	STATION	LOCATION	DESCRIPTION	LENGTH (FOOT)
45+00		52+00	CENTERLINE	YELLOW SKIP DASH	175.0
SUBTOTAL =					175.0
45+00		52+00	LEFT EOP	WHITE SOLID	700.0
45+00		52+00	RIGHT EOP	WHITE SOLID	700.0
SUBTOTAL =					1400.0
TOTAL =					1575.0
USE =					1575.0

## 70301000 WORK ZONE PAVEMENT MARK REMOVAL

STATION	TO	STATION	DESCRIPTION	AREA (SQ FT)
47+00		49+00	YELLOW: LINE 4 INCH CENTERLINE	6.6
TOTAL =				6.6
USE =				10.0

## 78001110 PAINT PAVEMENT MARKING LINE 4 INCH

STATION	TO	STATION	LOCATION	DESCRIPTION	LENGTH (FOOT)
45+00		52+00	CENTERLINE	YELLOW SKIP DASH	175.0
SUBTOTAL =					175.0
45+00		52+00	LEFT EOP	WHITE SOLID	700.0
45+00		52+00	RIGHT EOP	WHITE SOLID	700.0
SUBTOTAL =					1400.0
TOTAL =					1575.0
USE =					1575.0