

**SCHEDULE OF QUANTITIES**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N&TS-1	McLEAN	497	45
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

REMOVAL OF EXISTING STRUCTURES			50100100
LOCATON	OFFSET	EACH	
STA. 0+260.990, SIX POINTS RD., 1.5m X 1.5m RCB X 10.8m	LT \ RT	1	
STA. 10+407.700, GREENWOOD AVE., INLET STRUCTURE	4.4M RT	1	
STA. 0+980, SPRINGFIELD ROAD., 1.5m X 1.2m RCB X 5m	RT	1	
	TOTAL	3	
FIRE HYDRANTS TO BE MOVED			56400100
LOCATION	OFFSET	EACH	
STA. 0+151.6, MORRIS AVENUE	3.8 MLT	1	
STA. 0+604.0 MORRIS AVENUE	6.9 M RT	1	
STA. 0+001.1, SIX POINTS ROAD	8.1 MLT	1	
STA. 0+104.8, SIX POINTS ROAD	6.9 MLT	1	
STA. 0+213.0, SIX POINTS ROAD	8.1 MLT	1	
STA. 0+371.8, SIX POINTS ROAD	9.4 MLT	1	
STA. 7+015.5, GREENWOOD AVE.	5.2 MLT	1	
STA. 10+337.2, GREENWOOD AVE.	34.5 MLT	1	
	TOTAL	8	
FIRE HYDRANTS TO BE ADJUSTED			56400300
LOCATON	OFFSET	EACH	
STA. 0+531.2, MORRIS AVE.	9.5 M RT	1	
STA. 0+945.9, SPRINGFIELD ROAD	9.1 MLT	1	
STA. 10+499.3, GREENWOOD AVE.	5.5 MLT	1	
	TOTAL	3	
MANHOLES TO BE ADJUSTED			60255500
LOCATION	OFFSET	EACH	
STA. 0+430.955, MORRIS AVE.	8.364 MLT	1	
STA. 0+499.502, MORRIS AVE.	7.266 MLT	1	
	TOTAL	2	
MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID			60255800
LOCATION	OFFSET	EACH	
STA. 0+417.925, MORRIS AVE.	14.288 M L	1	
STA. 0+220.400, SIX POINTS ROAD	14.544 M L	1	
STA. 10+181.130, GREENWOOD AVE.	7.446 M R	1	
STA. 10+192.266, GREENWOOD AVE.	8.681 M RT	1	
STA. 10+237.586, GREENWOOD AVE.	3.309 M R	1	
STA. 10+359.377, GREENWOOD AVE.	16.526 M L	1	
STA. 10+412.294, GREENWOOD AVE.	1.674 M R	1	
	TOTAL	7	
MANHOLES TO BE RECONSTRUCTED WITH NEW TY. 1FR., CLOSED LID			60258200
LOCATION	OFFSET	EACH	
STA. 0+219.900, SIX POINTS ROAD	8.420 M R	1	
STA. 0+250.200, SIX POINTS ROAD	14.177 M R	1	
STA. 0+350.780, SIX POINTS ROAD	13.543 M L	1	
STA. 7+128.287, GREENWOOD AVENUE	0.835 M LT	1	
STA. 7+125.187, GREENWOOD AVENUE	8.819 M LT	1	
	TOTAL	5	

VALVE BOXES TO BE ADJUSTED			60266600
LOCATION	OFFSET	EACH	
0+150.038, MORRIS AVE.	7.995 M R	1	
0+150.592, MORRIS AVE.	4.958 M LT	1	
0+249.923, MORRIS AVE.	10.595 M R	1	
0+250.182, MORRIS AVE.	8.785 M R	1	
0+319.973, MORRIS AVE.	6.226 M LT	1	
0+328.456, MORRIS AVE.	12.016 M R	1	
0+367.336, MORRIS AVE.	12.321 M R	1	
0+395.070, MORRIS AVE.	11.821 M R	1	
0+412.574, MORRIS AVE.	10.558 M R	1	
0+443.120, MORRIS AVE.	10.586 M R	1	
0+530.978, MORRIS AVE.	8.796 M R	1	
0+567.830, MORRIS AVE.	6.196 M R	1	
0+016.330, SIX POINTS ROAD	6.649 M R	1	
0+102.751, SIX POINTS ROAD	3.662 M LT	1	
0+209.975, SIX POINTS ROAD	9.091 M RT	1	
7+018.208, GREENWOOD AVE.	4.368 M LT	1	
10+004.184, GREENWOOD AVE.	5.647 M R	1	
10+016.012, GREENWOOD AVE.	5.488 M LT	1	
10+016.285, GREENWOOD AVE.	4.374 M R	1	
10+019.421, GREENWOOD AVE.	3.976 M R	1	
10+181.134, GREENWOOD AVE.	5.002 M R	1	
10+235.381, GREENWOOD AVE.	5.878 M R	1	
10+384.672, GREENWOOD AVE.	9.022 M LT	1	
10+476.943, GREENWOOD AVE.	3.498 M LT	1	
10+499.320, GREENWOOD AVE.	4.339 M LT	1	
	TOTAL	25	
REMOVING MANHOLES			60500040
LOCATION	OFFSET	EACH	
STA. 16+801.1, SPRINGFIELD ROAD	5.0 MLT	1	
	TOTAL	1	
REMOVING INLETS			60500060
LOCATION	OFFSET	EACH	
0+561.5 MORRIS AVE.	LT	1	
0+575.8 MORRIS AVE.	LT	1	
0+103.6 SIX POINTS ROAD	RT	1	
0+118.4 SIX POINTS ROAD	RT	1	
0+179.0 SIX POINTS ROAD	RT	1	
0+222.5 SIX POINTS ROAD	RT	1	
16+601.2 SPRINGFIELD ROAD	LT	1	
16+601.2 SPRINGFIELD ROAD	RT	1	
10+203 GREENWOOD AVE.	LT	1	
10+431 GREENWOOD AVE.	RT	1	
10+650 GREENWOOD AVE.	LT	1	
	TOTAL	11	
TRAFFIC BARRIER TERMINAL TYPE 5			63100070
STATION	OFFSET	EACH	
2+785 VETERANS PARKWAY	6.000M LT	1	
	TOTAL	1	

TRAFFIC BARRIER TERMINAL TYPE 6			63100085
STATION	OFFSET	EACH	
2+877 VETERANS PARKWAY	6.000M LT	1	
0+635 SIX POINTS ROAD	4.850M LT	1	
	TOTAL	2	
TRAFFIC BARRIER TERMINAL, TYPE 1 (TANGENT)			63100167
STATION	OFFSET	EACH	
2+520.2 TO 2+535.4, VETERANS PARKWAY	RIGHT	1	
2+770.0 TO 2+785.2, VETERANS PARKWAY	RIGHT	1	
3+029.15 TO 3+044.35 VETERANS PARKWAY	LEFT	1	
16+422.2 TO 16+437.4 SPRINGFIELD ROAD	RIGHT	1	
16+423.7 TO 16+438.9 SPRINGFIELD ROAD	LEFT	1	
	TOTAL	5	
TRAFFIC BARRIER TERMINAL, TYPE 2			63304395
STATION	OFFSET	EACH	
2+634.46 TO 2+638.27, VETERANS PARKWAY	RIGHT	1	
2+857.59 TO 2+861.40, VETERANS PARKWAY	RIGHT	1	
	TOTAL	2	
RAISED REFLECTIVE PAVEMENT MARKERS			78100100
LOCATION		EACH	
STA. 2+213 TO STA. 2+335, VETERANS PKWY	N. BOUND	5	
STA. 2+213 TO STA. 2+359.4, VETERANS PKWY	S. BOUND	6	
STA. 2+280 TO STA. 2+335, VETERANS PKWY, LT TURN LN.	N. BOUND	5	
STA. 2+409 TO STA. 2+486, VETERANS PKWY, LT TURN LN.	S. BOUND	6	
STA. 2+412.2 TO STA. 2+705.0, VETERANS PKWY	N. BOUND	12	
STA. 2+409.0 TO STA. 2+701.8, VETERANS PKWY	S. BOUND	12	
STA. 2+739 TO STA. 2+803, VETERANS PKWY, LT TURN LN.	S. BOUND	5	
STA. 2+757.2 TO STA. 3+050.0, VETERANS PKWY	N. BOUND	12	
STA. 2+757.2 TO STA. 3+050.0, VETERANS PKWY	S. BOUND	12	
STA. 2+647.9 TO STA. 2+672.3, VETERANS PKWY	GORE	6	
STA. 0+057 TO STA. 0+117, MORRIS AVE.	CENTER	10	
STA. 0+134 TO STA. 0+256, MORRIS AVE.	CENTER	20	
STA. 0+197 TO STA. 0+256, MORRIS AVE.	N. BOUND	10	
STA. 0+311 TO STA. 0+395, MORRIS AVE.	S. BOUND	14	
STA. 0+340 TO STA. 0+395, MORRIS AVE.	N. BOUND	7	
STA. 0+428 TO STA. 0+494, MORRIS AVE.	S. BOUND	5	
STA. 0+434 TO STA. 0+606, MORRIS AVE.	CENTER	28	
STA. 0+014 TO STA. 0+390, SIX POINTS RD.	CENTER	37	
STA. 0+014 TO STA. 0+390, SIX POINTS RD.	LANES	30	
STA. 0+307 TO STA. 0+353, SIX POINTS RD.	TURN LN.	4	
STA. 0+440 TO STA. 0+520, SIX POINTS RD.	LANES	12	
STA. 0+866 TO STA. 1+094, SPRINGFIELD RD.	CENTER	9	
STA. 1+039 TO STA. 1+084, SPRINGFIELD RD.	TURN LN.	4	
	TOTAL	271	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p align="right">DRAWN BY</p> <p align="right">DATE 05-27-09</p> <p align="right">CHECKED BY</p>

**SCHEDULE OF QUANTITIES**