

# SUMMARY OF QUANTITIES

90% FED/  
10% STATE    90% FED/  
10% STATE    90% FED/  
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY <b>URBAN</b>	MAINLINE ROADWAY 0004	STRUCTURE SNO57-0249 0011	STRUCTURE SNO57-0250 0011													
20200100	EARTH EXCAVATION	CU YD	362	362															
20400800	FURNISHED EXCAVATION	CU YD	23,080	23,080															
* 25000210	SEEDING, CLASS 2A	ACRE	7.5	7.5															
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	675	675															
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	675	675															
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	675	675															
* 25100115	MULCH, METHOD 2	ACRE	0.75	0.75															
25100630	EROSION CONTROL BLANKET	SQ YD	5,113	5,113															
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	27,516	27,516															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	750	750															
28000305	TEMPORARY DITCH CHECKS	FOOT	210	210															
28000500	INLET AND PIPE PROTECTION	EACH	1	1															
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	3,151	3,151															
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	923	923															
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,696	1,696															
40600300	AGGREGATE (PRIME COAT)	TON	19.5	19.5															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	640	640															
40600990	TEMPORARY RAMP	SQ YD	120	120															
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	1,397	1,397															
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	635	635															
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	5,502	5,502															
42001300	PROTECTIVE COAT	SQ YD	7,384	7,384															
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,882	1,882															
44000100	PAVEMENT REMOVAL	SQ YD	17	17															
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2,832	2,832															
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	151	151															
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	2,176	2,176															
44000174	HOT-MIX ASPHALT SURFACE REMOVAL, 6 1/4"	SQ YD	1,024	1,024															

**LEGEND:**

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = keyarb	DESIGNED -	REVISED -
c:\pwork\pwork\keyarb\0101450\0570530-shr-500.DGN		DRAWN -	REVISED -
Johnson, Depp & Oulsenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20,0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 8/19/2010	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE:      SHEET NO.    OF    SHEETS    STA.      TO STA.

**SHEET NO. 1 OF 5**

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(57-7HB-2 & 57-7HB-1)BR	MCLEAN	153	3
FED. ROAD DIST. NO.    ILLINOIS FED. AID PROJECT			CONTRACT NO. 70520	