

68600105 FURNISH AND ERECT RIGHT OF WAY MARKERS

IL 54			TR 547			EACH
STA	O/S		STA	O/S		
359+00.00	40.00	RT				1.0
362+34.37	75.00	RT				1.0
365+70.78	87.71	RT				1.0
365+78.27	80.00	RT				1.0
370+10.00	80.00	RT				1.0
371+30.00	130.00	RT				1.0
372+70.00	130.00	RT				1.0
375+07.72	100.00	RT	0+87.69	94.18	RT	1.0
			0+60.21	45.00	RT	1.0
			0+74.96	45.00	LT	1.0
			0+14.16	45.00	LT	1.0
377+00.00	95.00	RT				1.0
380+00.00	95.00	RT				1.0
381+47.69	116.21	RT				1.0
386+84.38	60.00	RT				1.0
393+00.00	60.00	RT				1.0
393+00.00	40.00	RT				1.0
360+00.00	40.86	LT				1.0
360+00.00	65.86	LT				1.0
367+50.00	66.46	LT				1.0
367+50.00	58.46	LT				1.0
371+42.71	58.78	LT				1.0
374+18.18	59.01	LT				1.0
375+50.00	59.11	LT				1.0
375+50.00	65.11	LT				1.0
382+50.00	64.68	LT				1.0
382+50.00	55.68	LT				1.0
387+00.00	55.10	LT				1.0
387+00.00	51.10	LT				1.0
393+00.00	50.47	LT				1.0
393+00.00	40.47	LT				1.0
TOTAL						31.0
USE						31.0

PAVEMENT MARKING ITEMS

LOCATION			LT EDGE (WHITE)	RT EDGE (WHITE)	CL DASH (YELLOW)	78001110 PAINT PAVEMENT MARKING LINE 4"	78100100 RAISED REFLECTIVE PAVEMENT MARKERS	70300220 TEMPORARY PAVEMENT MARKING LINE 4"	70301000 WORK ZONE PAVEMENT MARKING REMOVAL
STA	TO	STA	FOOT	FOOT	FOOT	FOOT	EACH	FOOT	SQ FT
360+00.0	TO	375+28.2	1528.2	1528.2	382.0	3438.4	19.0	3438.4	1146.2
375+28.2	TO	377+12.2	184.0		46.0	230.0	3.0	230.0	76.7
377+12.2	TO	389+63.7	1251.5	1251.5	312.9	2815.8	16.0	2815.8	938.6
390+79.2	TO	395+00.0	420.8	420.8	105.2	946.8	6.0	946.8	315.6
TOTAL						7431.1	44.0	7431.1	2477.0
USE						7432.0	44.0	7432.0	2477.0

SIGN PANEL AND POST

LOCATION/DESCRIPTION				72000100 SIGN PANEL TYPE 1	72900100 METAL POST TYPE A
O/S	STATION	MUTCD #	DESCRIPTION	SQ FT	FOOT
30.2 LT	0+61.2	R1-1	STOP SIGN	4.0	12.5
TOTAL				4.0	12.5
USE				4.0	12.5

X7240300 SIGN REMOVAL

O/S	*STATION	MUTCD #	SIGN DESCRIPTION	EACH
RT	356+29	W1-4	"REVERSE CURVE" WITH 45 MPH ADVISORY SIGNS	1.0
LT	356+29	W1-4	"REVERSE CURVE" WITH 45 MPH ADVISORY SIGNS	1.0
RT	362+78	W1-13	"TRUCK ROLLOVER WARNING" WITH 45 MPH ADVISORY SPEED SIGNS	1.0
LT	365+04	W1-8	"CHEVRON"	1.0
LT	365+84	W1-8	"CHEVRON"	1.0
LT	366+84	W1-8	"CHEVRON"	1.0
LT	367+46	W1-8	"CHEVRON"	1.0
RT	371+99	W1-8	"CHEVRON"	1.0
RT	372+78	W1-8	"CHEVRON"	1.0
RT	373+60	W1-8	"CHEVRON"	1.0
RT	374+39	W1-8	"CHEVRON"	1.0
RT	375+12	W1-8	"CHEVRON"	1.0
RT	380+19	W1-2	"CURVE" WITH 50 MPH ADVISORY SPEED SIGNS	1.0
RT	384+78	W1-4	"REVERSE CURVE" WITH 45 MPH ADVISORY SIGNS	1.0
LT	384+78	W1-4	"REVERSE CURVE" WITH 45 MPH ADVISORY SIGNS	1.0
LT	390+97	W1-13	"TRUCK ROLLOVER WARNING" WITH 45 MPH ADVISORY SPEED SIGNS	1.0
LT	395+68	W1-2	"CURVE" WITH 50 MPH ADVISORY SPEED SIGNS	1.0
TOTAL				17.0
USE				17.0

\*STATIONING IS RELATIVE TO EXISTING ALIGNMENT

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\p\d0t\keysrb\d0101441\0570592-sht-Schedules		DRAWN -	REVISED -			71	121R	MCLEAN	87	10	
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 70592					
	PLOT DATE = 8/9/2010	DATE -	REVISED -			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT