

#### General Notes

Build tops of headwalls parallel to the grade lines.

All construction joints shall be bonded according to Article 503.09 of the Standard

Reinforcement bars shall conform to the requirements of ASTM A706 Gr. (IL Modified). See Special Provisions,

The 6" Porous Granular Material required per Art. 540.06 of the Standard Specifications shall also extend beneath the Box Culvert End Sections and shall be considered included in the cost of Precast Concrete Box Culverts and Box Culvert End Sections.

When lapping sheets of welded wire fabric, the overlap measured between the outermost cross wires of each fabric sheet shall not be less than 8"

End Sections will be paid for at the contract unit price per each for BOX CULVERT END SECTIONS, as outlined in Section 540 of the Standard Specifications.

Class SI Concrete shall be used throughout.

Concrete, Rebar, and Welded Wire Fabric quantities and lengths calculated for the cast-in-place End Sections may vary based on the precast box culverts supplied.

Drain holes shall be provided in accordance with Article 503.11 of the Standard Specifications.

The box culvert end section shall be built in the field and a precast option is not allowed except the cut-off wall may be precast. If the contractor elects to use a precast cut-off wall, shop drawings and a proposed construction sequence shall be submitted to the Fnaineer for approval.

The ends of the precast box sections adjacent to the end section shall be formed without the male and female shapes specified in Article 8.1 of AASHTO M259. See Sections B-B, D-D, E-E, and F-F on Sheet 2,

The design fill height for this box is greater than 2 feet. The Precast Concrete Box Culvert Sections shall conform to the requirements of AASHTO M 259.

The joints between precast box sections shall be sealed, all voids filled with a mastic joint sealer. In addition, the joints shall be externally sealed on all four sides with a 13 inch wide external sealing band. The seal shall be centered over the joint, secured in place and protected during the backfilling process.

All dimensions are in FEET (') - INCHES (") unless otherwise noted.

Drawings not to scale.

RNG 6E. 3RD P.M.

### TOTAL BILL OF MATERIAL

Item	Unit	Total
Removal of Existing Structures No. 1	Each	1
Precast Concrete Box Culverts 12'x6'	Foot	108
Box Culvert End Sections	Each	2
Name Plates	Each	1
Permanent Benchmark	Each	1

## SHEET 1 OF 4

GENERAL PLAN AND ELEVATION DOUBLE 12'x6' PRECAST BOX CULVERT F.A.P. ROUTE 71 - SECTION 121R MCLEAN COUNTY STATION 363+70.00 S.N. 057-2047 CULVERT NO. 1

## Design Scour Elevation Table

PR. STR. 057-2047

STA. 363+70.00

UPSTREAM

Riprap, Special

(See Spl. Prov.)

ELEV. = 746.92

Instream **I**Downstrea Desian Scour Elevation (ft. 743.92

SCALE:

# DRAIN DETAIL FILE NAME =

- All-time H.W.E. is estimated at 0.33 ft. higher than existing low-grade elevation. DESIGNED REVISED USER NAME = keysrb :\pw\_work\pwidot\keysrb\d0101441\D7059 sht-BoxCulverts.dar DRAWN REVISED CHECKED REVISED PLOT DATE = 10/16/2009 DATE REVISED

ALL-TIME H.W.E. & DATE:

50

100

500

Design

Overtopping

343

10 YEAR VELOCITIY THROUGH EXISTING BRIDGE = 11.4 ft/s

572

676 896

933 1235

455

758

48

48

48

48

105

131

143

144

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

752.6 751.3

756.3 752.4

Over 754.2

752.9

Over

10 YEAR VELOCITIY THROUGH PROPOSED BRIDGE = 4.6 ft/s

~ 757.4 ft. - High Water Report dated 06/20/1990 states that flood water observed 4" deep over pavement

LOCATION SKETCH SECTION COUNTY **GENERAL PLAN AND ELEVATION** 121R MCLEAN 87 28 PROPOSED CULVERT NO. 1 - STR. NO. 057-2047 CONTRACT NO. 70592 SHEET NO. OF SHEETS STA.